THE
INSTITUTION
OF
CIVIL ENGINEERS.

SESSION 1901-1902.—PART III.

SECT. I.—MINUTES OF PROCEEDINGS.

11 February, 1902.

CHARLES HAWKSLEY, President,
in the Chair.

(Paper No. 3278.)

“The Port of Dundee.”

By GEORGE CUNNINGHAM BUCHANAN, M. Inst. C.E.

IN 1895 the late Mr. David Cunningham, M. Inst. C.E., contributed to the Institution a Paper¹ on “The Estuary of the Tay,” in which the general physical conditions of the Firth were fully described. In this Paper the Author proposes to deal with the harbour and docks of Dundee, and the effects of the harbour and railway works on the sandbanks in their vicinity.

THE HARBOUR AND DOCKS.

Historical.—Dundee, situated on the north bank of the Firth of Tay, 9 miles from its mouth, is the third town and port in Scotland, and the centre of the jute and linen industries. The harbour is managed by a public trust, under various Acts of Parliament consolidated in the Act entitled “The Dundee Harbour Consolidation Act 1875.” The jurisdiction of the Harbour Trustees extends from the Bar of Tay on the east to Balmerino on the west, a distance of 17 miles, and on them devolves the maintenance of the navigation-channel, including the upkeep of the lightship, lighthouses, buoys and beacons, the fishery harbour at Broughty Ferry, and the docks and wharves at Dundee. They also own the Tay Steam Cart Ferries, which ply between Dundee and Newport. Owing to the exposed position of the port in the estuary, harbour protection-works were essential from the earliest times when ships frequented it. The first mention of built structures in the local records is in 1447, and in 1770 Smeaton executed considerable repairs and extensions to the works. In 1812, when a connected history of the harbour may

¹ Minutes of Proceedings Inst. C.E., vol. cxx. p. 299.

be said to begin, the accommodation consisted of a tidal basin about $4\frac{1}{2}$ acres in extent, with protecting piers on the east and west, and two insulated breakwaters on the south or sea side, forming one principal and two narrow entrances. There was also a scouring-basin, $\frac{1}{2}$ acre in area, the walls of which were just below high-water level of neap tides, and at low water, on sluice-valves being opened, the basin and entrance were partially cleansed of mud.¹

Building of the West Docks.—In 1815 a want of dock accommodation began to be felt, and Thomas Telford designed a new and comprehensive dock system, comprising a tidal basin, wet dock, and graving-dock. Dundee being partly situated on a narrow strip of flat ground extending from the river-bank to steep rising ground on the north, docks were only practicable by reclaiming from the river, and all subsequent harbour-extensions have been carried out on similar lines. These works were completed in 1825 at a cost of £90,000 (Fig. 1, Plate 1). The wet dock encloses a water-area of $6\frac{1}{4}$ acres, and has 2,430 lineal feet of quayage, and a lockway 39 feet in width by 170 feet in length. The dry dock is 278 feet in length, with similar breadth of entrance, and although now only used for the smallest class of vessels, was at the date of construction found fault with on account of its large size, and was described by Telford as not inferior in excellence to any in the kingdom. The walls of both wet and dry docks were constructed of masonry from local sandstone-quarries.

The result of a progressive policy soon became apparent, as the tonnage of ships visiting the port increased from 70,000 tons in 1815 to 165,000 tons in 1829, and the revenue from £1,700 in 1814 to £11,000 in 1829. In 1830 it became evident that dock-extensions were essential to the welfare of the town, and between that date and 1848 the tidal harbour was converted into the Earl Grey Dock, having an area of 5 acres, 2,240 feet of quayage, and an entrance lock 55 feet in width by 215 feet in length, with a depth of water of 17 feet 6 inches at high water of spring tides. The gates had cast-iron heel- and mitre-posts and cast-iron ribs, planked on both sides with Memel fir, and cost £2,795; the masonry and excavation of the lock costing £9,000, and the whole work £46,000. A slip was also provided, the marine parade was extended, and the east tidal harbour was built (Fig. 2, Plate 1).

Construction of East Docks.—In 1855 the average draught of the larger vessels frequenting the port was between 16 feet and 17 feet, and as on a neap tide the depth of water on the sill of the Earl

¹ According to Mr. Cunningham's Paper, the range of ordinary spring tide at Dundee is $16\frac{1}{2}$ feet.—SEC. INST. C.E.

Grey Dock was only 14 feet 6 inches, they were obliged to load or discharge a large part of their cargoes in the river by lighters, at great additional cost and inconvenience. The revenue of the harbour had increased from £16,810 in 1840 to £23,361 in 1854. The first importation of jute in any quantity occurred about 1835, and although up to 1840 the manufacturers had obtained their supplies from the London and Liverpool markets, a direct trade with Calcutta was being established, and the importation at the harbour had increased from 1,948 tons in 1842 to 9,048 tons in 1855. Many proposals for additional accommodation were formulated, and finally an Act of Parliament was obtained to convert the east tidal harbour into the Camperdown Dock. This work was commenced in 1857, but the collapse of the whole of the east wall of the dock and a lengthy lawsuit with the contractors delayed its completion until the year 1865, when the dock was opened to traffic, having cost £100,000 to build. The dock has an area of $8\frac{1}{2}$ acres, with 2,400 lineal feet of quays, and an entrance 60 feet wide, with a depth of 21 feet 8 inches of water on the sill at high water of spring tides, and closed by a hinged caisson (Fig. 5, Plate 1).

The Victoria Dock and the East Graving-Dock were next constructed, in 1871-1876. The Victoria Dock has an area of $10\frac{3}{4}$ acres, 3,014 feet of quays, and a depth of water of 21 feet at high water, Fig. 4. The East Graving-Dock is 500 feet long, with a width of entrance of 53 feet, and a depth on the sill of 18 feet 6 inches at high water. The walls of the graving-dock are built of rubble sandstone masonry, founded on a bed of flat stones. The outer faces are of hammer-dressed rubble, with ashlar courses at the sides of the floor, and on the altars, copings, timber slides, caisson platform, invert, stairs, etc. The floor is 8 feet 4 inches in thickness at the centre, has an inverted arch of rubble on a foundation bed of Portland-cement concrete, and is paved with rubble blocks on the surface, Fig. 6, Plate 1. The dock is closed by a caisson 7 feet in breadth and 25 feet 3 inches in height, the lower part of which is divided by five watertight plate floors

Scale, 1 inch = 16 feet.
CROSS SECTION OF VICTORIA DOCK WALL.

into four sets of chambers, and the caisson is provided at one end with hinges, and at the other with a vertical pneumatic chamber. There are also five sluices, each measuring 2 feet 9 inches by 2 feet, through which water is admitted into the dock, Figs. 7, Plate 1. The Victoria Dock cost £98,000, and the Graving-Dock £60,645.

Deep-Water River-Wharves.—In 1891 the question of harbour-extension was again brought forward, by a report from the harbourmaster drawing attention to the serious detention of large steamers, owing to the fact that with few exceptions all vessels drew 23 feet of water, and had to be lightened in the river before entering the docks. From want of foresight on the part of the Harbour Board of that date, the only piece of ground available for dock extension eastward had been let to a shipbuilding firm; and a proposal to extend into the river and build a dock embracing the Beacon Rocks was negatived on the score of expense. It was finally decided to build river-wharves, and to erect sheds east of the shipbuilding-yards, abandoning the use of the docks for large vessels. The construction of 2,800 lineal feet of river-wharf, with 24,650 square yards of shed, has enabled the largest steamers to lie and discharge at any time of the tide without inconvenience. The timber wharf being of a temporary nature, and more shed-accommodation being required, the construction of a permanent river-wall, 140 feet outside the present wharf, is about to be commenced. The new wall will be 2,000 feet in length, with a dredged depth alongside of 27 feet at low water of ordinary spring tides, and an additional row of sheds will be built outside those at present in use, Fig. 3, Plate 1.

Tidal Dock for Steam Trawlers.—In 1898 it was found necessary to provide special accommodation for the steam trawlers fishing from the port, Parliament having decreed that until this was done dues could not be levied. The modern steam trawler, a vessel of 120 feet to 150 feet in length, 20 feet to 25 feet in beam, and drawing up to 14 feet of water aft, has revolutionised the fishing-industry; and as quick despatch and a dock that can be entered at any state of the tide are essential to success, the small shallow harbours which abound on the coast have been rendered in a large measure useless, and a concentration of the trade has taken place at various centres. In Dundee there was no suitable accommodation, the West Docks being deficient in depth, and it was impossible, except at a prohibitive cost, to remedy this defect. The river-wharves had abundance of water alongside, but no protection for small steamers from the gales that sweep down the estuary. The Author was of opinion that the most suitable site would be at the extreme east end of the harbour, where there was a large piece of

vacant ground available for fish-curing purposes; and he designed a tidal dock having 8 acres of water-space, 2,743 lineal feet of quay, and 6,700 square yards of market, with a depth of water in the entrance-channel of 12 feet 6 inches at low water of ordinary spring tides. The first section was opened in June, 1900. To give protection from westerly gales, a breakwater was run out to the point where the new deep-water quay will commence, and the body of the dock was formed by excavating a portion of the ground reclaimed from the river in former years. The breakwater consists of two rows of whole-timber pitch-pine main piles 8 feet

Figs. 8.

Scale, 1 inch = 20 feet.

BREAKWATER OF NEW TIDAL BASIN FOR TRAWLERS.

apart from centre to centre, and half-timber sheeting, the space between the two rows being filled with rubble, *Figs. 8*.

The landing-wharf is 12 feet 6 inches in width, is constructed of two rows of main piles, 9 feet apart from centre to centre, with sheeting between the piles of the first row, and is tied by iron tie-rods, $1\frac{1}{2}$ inch in diameter, and 50 feet in length, *Figs. 9*. There are bollards along the face of the wharf, 18 feet apart, and numerous ladders down to low-water level.

The market is 50 feet in width, with wooden framed ends, and a row of cast-iron columns at back and front supporting the girders which carry the steel principals of the roof. In lieu of sliding

doors, which take up a great deal of room, the Author adopted wooden roller-shutters, 16 feet in width, and 11 feet in height (Figs. 10, 11, 12, Plate 1). These were made in the harbour workshops of pitch-pine laths threaded on steel wire and fastened to an iron drum, 1 foot in diameter. By means of balance-weights and a simple gearing, one man can with ease lift and lower the shutters.

The works were carried out departmentally. The breakwater cost £11 per lineal foot, and the landing-wharf £9 2s. 6d. per lineal foot, or 14s. 5d. per square foot of quay. The cost of pile-

Figs. 9.

Scale, 1 inch = 20 feet.

NORTH WHARF OF NEW TIDAL BASIN FOR TRAWLERS.

driving throughout averaged 2s. 3d. per cubic foot, being 1s. 8½d. for timber and 6½d. for labour; whilst that of the other timber work averaged 3s. per cubic foot, viz., 1s. 9d. for material and 1s. 3d. for labour. To these amounts ironwork added 5d. per cubic foot of timber used. The market cost complete 4s. 11d. per square foot of flooring, the rolling shutters costing 3s. per square foot of opening.

EQUIPMENT AND WORKING OF HARBOUR.

Apart from a general coasting and continental trade and a large timber importation, Dundee depends almost entirely on the Indian jute-industry for its support, and special facilities and equipment

are provided for this particular trade. On an average one million bales, or 180,000 tons, of raw jute are imported from Calcutta annually, the greater part of which arrives at the port between the months of October and April in cargoes ranging between 20,000 bales and 50,000 bales, each bale measuring 4 feet by 1 foot 6 inches by 1 foot 9 inches, and weighing 400 lbs.

Transit-Sheds.—Around the docks and river-quays there are single-storey transit-sheds covering an area of 45,000 square yards. A cross section of one recently erected by the Author is shown in Fig. 13, Plate 1. It is 300 feet in length by 120 feet in breadth, in two roof-spans of 60 feet, and the height from ground-level to the eaves is 13 feet 9 inches. The walls are of brick, with ashlar quoins and tabling, and there is a row of cast-iron columns along the centre of the shed supporting the roof, and a similar row on the river-front, which is closed in with wooden sliding doors. The roof covering is of slate, and the principals and girders are of mild steel. The shed is floored with granolithic pavement consisting of a 4-inch layer of broken stone, upon which is laid 4 inches of Portland-cement concrete, covered with 2 inches of granolithic, composed of clean granite chips and Portland cement, gauged 1 to 1. The cost is 5s. per square yard, and this flooring is found very satisfactory for both light and heavy traffic. The total cost of the buildings averages 3s. per square foot of ground covered.

Iron Storage-Warehouses.—In the jute-season considerable difficulty is experienced in getting the transit-sheds cleared, owing to the cargo being discharged from the steamer much more rapidly than it can be carted to the mills and town warehouses. This is specially the case at the east wharf, where, on account of the lack of depth in the docks, the majority of the Indian liners are berthed; and at the Author's suggestion a row of storage-warehouses has been built immediately opposite the transit-sheds, by which means the congestion of the traffic has been considerably abated. They are single-storey warehouses, constructed of iron with party-walls of rubble-masonry, and cost 0·97d. per cubic foot of contents, or 2s. per square foot of ground covered.

Warehouse for General Merchandise.—In addition to the sheds, there is a five-floor warehouse at Victoria Dock, with a capacity of 270,000 cubic feet, which cost £16,147 to build.

Hydraulic Machinery.—Up to the year 1882, jute-cargoes were discharged by means of small steam-engines placed on the quay, but the danger from fire, owing to the inflammable nature of the jute, and the damage to goods and sheds from smoke and dirt was so considerable that a small installation of hydraulic machinery

was put down, which has been since extended. The harbour is now almost entirely worked by hydraulic machinery, and the present plant consists of a central station containing one compound non-condensing pumping-engine, made by Messrs. Sir W. G. Armstrong and Company, having cylinders $10\frac{1}{2}$ inches and $15\frac{1}{2}$ inches in diameter by 15 inches stroke; one compound horizontal surface-condensing pumping-engine made by Messrs. Tannett Walker and Company, having cylinders 14 inches and 24 inches in diameter by 21 inches stroke; one compound surface-condensing steam pumping-engine capable of discharging 160 gallons of water per minute at the accumulator pressure of 700 lbs. per square inch, supplied in 1897 by Messrs. Sir W. G. Armstrong and Company; one Lancashire boiler, 6 feet in diameter, 18 feet in length, working-pressure 100 lbs. per square inch; one internally-fired multitubular boiler, 6 feet in diameter, 16 feet 6 inches in length, working-pressure 95 lbs. per square inch; one internally-fired multitubular boiler, 5 feet in diameter, 11 feet 6 inches in length, working-pressure 80 lbs. per square inch.

There are two accumulators at the central station with 10-inch and 12-inch rams respectively, and 12 feet stroke, and an auxiliary accumulator at the east wharf with a ram 10 inches in diameter and 12 feet stroke. The main pressure-pipes are 3 inches and 4 inches in internal diameter, and the working-pressure is 700 lbs. per square inch.

The machines used are 5-cwt. movable jigger-hoists supplied by Messrs. Sir W. G. Armstrong and Company, and there are now thirty-two of these in operation, *Figs. 14*. They have rams $7\frac{1}{4}$ inches in diameter with 2 feet 2 inches stroke, and by means of multiplying sheaves and drums can lift the load of 5 cwt. through a height of 50 feet at the rate of 12 feet per second. The pressure pipes are laid underneath the deck-planking of the wharf, and have numerous jigger-connections conveniently placed. A stage on trestles runs from the wharf to the steamer's hatchway; the bales are hoisted up one by one at the end of a hemp rope passing from the jigger-drum over a pulley on the ship's derrick, and are received by a man and pulled to the stage; they are then slid to the wharf, where they are wheeled to the transit-sheds, weighed and loaded on to lorries by the harbour-porters. A jigger can make five lifts per minute, so that a steamer with five hatchways and a jigger at each, can, theoretically, be discharged at the rate of twenty-five bales, or 5 tons per minute. Unfortunately this rate is never continuous for any length of time,

as numerous stoppages occur, both to break out the cargo and on

Figs. 14.

MOVABLE JIGGER-HOIST.

account of congestion in the transit-sheds; but a steamer with a

cargo of 33,000 thousand bales has been cleared in 59 hours from the time of berthing. The average discharge, however, is about 4,500 bales per working-day.

The total cost per ton for discharging and loading on to lorries is 4*d.* from ship to quay, and 6*d.* to 8*d.* from quay to lorry, the latter charge including depositing in shed, selecting, weighing and loading. Besides hydraulic jiggers there are, worked by hydraulic machinery, a 20-ton crane, warehouse hoists, capstans, etc.

A hydraulic coal-hoist, adapted to lift a wagon of 20 tons through a height of 50 feet above the level of the jetty, and to tip it, when raised to that height, through an angle of 45°, is in course of erection (Figs. 15, Plate 2). Owing to the difficulty in providing suitable foundations at a moderate cost, the hoist having to stand in the river 120 feet out from the line of the existing quay, the Author decided to adopt the suspended hoist of Messrs. Sir W. G. Armstrong, Whitworth and Company instead of that in which the cradle is lifted by direct-acting cylinders placed in a well below the surface of the quay. A substantial timber jetty was accordingly built, on which the hoist is being erected. The hoist-framing is of steel, braced and strutted, and securely bolted to the timber-work of the jetty. The cradle and tipping-frame are lifted and lowered by four chains, two for lifting and two for tipping; the lifting-cylinder is fixed vertically against one side of the framing, the tipping-cylinder is fixed on the upper end of the lifting-cylinder, and each cylinder is fitted with a plunger, multiplying sheaves, guide-bars, etc. The hoist is also furnished with a 2½-ton anti-breakage crane, having a lift of 55 feet; an auxiliary accumulator, having a ram 1 foot 8 inches in diameter and 35 feet stroke, has been placed in the vicinity. The hoist is the largest built of that particular type, and will cost, complete with foundations, jetty and railways, £12,500.

The fire-extinguishing appliances consist of thirty-seven box hydrants, with an effective pressure of 100 lbs. per square inch, and a steam fire-engine. There are also a 90-ton steam-crane, a 30-ton steam-crane and numerous 5-ton hand-cranes placed round the docks.

There are 8½ miles of railway on the harbour estate with which both the North British and Caledonian Railway Companies have connection. The Dundee and Perth line was made in 1846, and the North British main line to Aberdeen, viâ the Tay Bridge, passes under Dock Street by means of a tunnel, and was built in 1878.

MOVEMENTS OF SANDBANKS IN THE VICINITY OF THE HARBOUR.

The estuary of the Tay is of the narrow-necked type, and at Broughty Ferry, which is the narrowest part of the neck and $7\frac{3}{4}$ nautical miles from the bar, the width is $\frac{3}{4}$ mile, and the depth at low water of spring tides 60 feet. The Port of Dundee is situated on the north bank, 3 miles above Broughty Ferry, and the width there is $1\frac{1}{4}$ mile, widening uniformly to $2\frac{3}{4}$ miles at a distance of 4 miles farther up, whence it decreases to $\frac{1}{4}$ mile at the mouth of the River Earn, 24 nautical miles from the bar. Over the upper part of the estuary, sandbanks extend over many square miles, mainly on the north side, and the Author proposes to trace the movements and changes in the banks in the immediate neighbourhood of the harbour as shown in Figs. 16, Plate 2.

In the year 1816, which is the date of the first reliable chart, the Middle Bank had an area of 140 acres above low water of spring tides, and an average height of 8 feet above the same level. Its formation was probably due to a reduction in the average speed of the tidal currents in that portion of the estuary in which the bank was situated, owing to the greater breadth of that portion as compared with the portion below, and to the fact that although the body of the tide ebbed on the south side, there was a strong set of the flood-tide on the north side, the bank lying between the two. The main channel of the Tay opposite the harbour was then, as now, on the south side, but there was on the Dundee side a subsidiary channel to the north of the Beacon Rocks, and thence into Queens Roads, and between the latter and the south channel lay the Middle Bank. The ballast-bank lay on the north side of the river, stretching east from Magdalen Point, and was a natural result of the configuration of the coast.

The state of the sandbanks in 1833 showed but little change since 1816. In 1870 the ballast-bank had moved down, and was blocking the entrance to the harbour, the portion above low water of spring tides being 2 feet in height. The Middle Bank had travelled north and become reduced in size from 140 acres to 20 acres above low water of spring tides.

Between 1835 and 1842 the Perth Harbour Commissioners, acting on the advice of Messrs. Stevenson, had carried out improvement-works in the upper portion of the river, involving the removal of 841,480 tons of material from its bed, thus equalizing the depths in the shallows to 5 feet at low water and 15 feet at high water of spring tides. These works depressed the low-water level at Perth by 2 feet, and increased the velocity of

the tidal wave between Newburgh and Perth by $1\frac{2}{3}$ mile per hour. The harbour-works at Dundee were begun in 1816, and between that date and 1869, 135 acres of ground were reclaimed from the foreshore of the river, the total amount of reclamation up to the present date being 328 acres.

Diverse opinions have been expressed by engineers as to the cause of the change in the banks opposite Dundee, some attributing it to the excavations in the upper part of the river. The Author considers the movement of the ballast-bank undoubtedly due, first, to the construction of the Dundee and Perth railway embankment in 1845, and secondly, to the building of the Dundee esplanade in 1869, as the speed of the tidal currents outside the straight line of wall must have been increased, and the sand immediately in front been carried down stream and deposited in front of the harbour. The decrease in the size of the Middle Bank was a natural result of narrowing the estuary by the projection of the docks and esplanade into the river, and thus increasing the velocity of the tidal currents in the main channel. In 1870 dredging-operations were commenced on the bank in front of the harbour, and between then and 1879, 500,000 tons were removed, and the whole of the river-bed formerly occupied by the bank was deepened to 6 feet below low water of spring tides.

Railway Bridges over the Tay at Dundee.—The construction of the first Tay Bridge was commenced in 1871 and was completed in 1878, and in view of the effect of these works on the harbour-approaches, the Author presents the following brief description of their construction:—

On the north side the bridge consisted of 25 spans of 67 feet each, on a curve of 20 chains radius, 11 spans of 130 feet, and one span of 162 feet. Then came the navigation-spans, 11 spans of 245 feet, and 2 spans of 227 feet. The piers were formed of iron cylinders filled in with brick and cement, were carried up to 5 feet above high-water level, and measured in the large spans 28 feet in length and 16 feet in breadth, the small spans being 12 feet 6 inches in length and 11 feet in breadth. The first bridge fell in the gale of the 28th December, 1879, and the second bridge was commenced in 1882 and completed in 1887. The centre-line of the new bridge was laid out 60 feet west of the old piers, but the number and length of the spans remained the same. Each pier was formed of two wrought-iron cylinders filled with concrete and brickwork, and sunk into the river-bed. The cylinders of the narrow spans were 9 feet in diameter up to high-water level, and 17 feet apart, the cylinders of the 130-foot spans were 10 feet

6 inches in diameter at high-water level, and 15 feet 6 inches apart, and the cylinders for the navigation-spans were 14 feet 6 inches in diameter between low-water and high-water levels.

Between the year 1871, when the first bridge was commenced, and the year 1879, when it fell, the bed of the river between the navigation-spans was lowered an average of 5·41 feet by scouring action, and from observations made by the Author in 1898, it was ascertained that, since the erection of the new bridge, the bed of the river in the navigation-spans had been lowered an additional 3·39 feet, or 8·80 feet in all. In 1879 the Middle Bank was entirely gone, and on its former site was 15 feet to 17 feet of water at low water of spring tides (Figs. 16, Plate 2). A new Middle Bank, having an area of some 67 acres above low-water level had, however, appeared about 2,500 feet from the north shore, stretching from the Tay Bridge eastward. In 1885, although the area above low-water level had decreased, the depth of the river-bed below low-water of spring tides in front of the esplanade had diminished, and from that date up to 1893 the area of the bank above low water increased steadily year by year, and the buoy marking the passage for the ferry-steamers at the tail of the bank was moved in a north-easterly direction 1,700 feet altogether. Since 1893 there has been no change in the position of the buoy, and it is not apprehended that there will be any further downward movement, as, owing to the gradual narrowing of the estuary, the speed of the tidal currents becomes too great to allow sand to lie farther down the stream. The lower end, although not permanently extending, is constantly changing. A prolonged drought and high spring tides have the effect of diminishing the bank, whilst the effect of land-floods and neap tides is to cause it to increase.

In 1888 the Dundee Corporation commenced an extension of their esplanade westward, which was completed in 1893. The wall was built on a sandbank, and the immediate effect was to scour in the neighbourhood of the elbow 150,000 tons of sand, which was deposited below the bridge and formed another bank between the new Middle Bank and the shore. The Corporation have now obtained powers to reclaim an additional 132 acres of foreshore, and to construct an extended esplanade 7,000 feet in length. The material on which it is proposed to build this wall consists, for a depth of 16 feet, or 14 feet below low water of spring tides, of soft fine sand and mud, and it seems probable that a vast amount will be scoured and deposited in the vicinity of the harbour. The superior force of the ebb-tide will then in due

course carry it in front of the docks, blocking the entrances, as was the case in 1869. From a series of cross sections of the river taken at different periods (Figs. 17, Plate 2), the Author has computed that between the years 1879 and 1900, 2,639,000 cubic yards of material have been deposited over the area between the esplanade on the north, the south side of the new Middle Bank on the south, the Tay Bridge on the west, and the Craig Pier on the east.

Reasons for the Shoaling of the River-bed.—The serious shoaling of the bed of the estuary which is so prejudicial to the interests of the harbour, and especially to the Tay Ferries Navigation, is, in the opinion of the Author, almost entirely due to the obstruction of the tidal currents caused by the piers of the Tay Bridge (Fig. 18, Plate 2) which, from pier No. 41 to pier No. 78, a length of 3,350 feet on the north side of the estuary, have, owing to the plan on which the bridge has been constructed, diminished the speed of the tidal currents to an extent sufficient to allow the sand brought down by the river to be deposited over the area referred to; and whereas the main channel through the navigation-spans has been deepened, and the speed of the currents increased, a sand-trap has been formed in the slack water on the north side between the bridge and the Craig Pier, into which the sand from above the bridge and that scoured down in consequence of the new esplanade works, has been deposited.

In conclusion, the Author would point out that in his opinion the approaches of Dundee Harbour could have been materially improved by carrying out the works in accordance with the following plan:—

- (1) The construction of the Tay Bridge with wide spans on the north or Dundee side.
- (2) Dredging through the sandbank known as “My Lord’s Bank” to the deep-water channel to the south-west.
- (3) The removal of the Fowler and Beacon Rocks.

The Chief Engineers to the Dundee Harbour Trust have been : The late Mr. James Leslie, M. Inst. C.E. (1832–1846); the late Mr. Charles Ower (1846–1869); and the late Mr. David Cunningham, M. Inst. C.E. (1869–1896). The Author succeeded Mr. Cunningham in 1896, and held the office until his appointment to the Chairmanship of the Port Trust, Rangoon, in 1901.

The Paper is accompanied by fourteen drawings, from which Plates 1 and 2 and the Figures in the text have been prepared.

Fig. 1.

Fig. 2.

Fig. 3.

Fig. 13.

Fig. 7.

Fig. 10.

Fig. 11.

Fig. 12.

Fig. 5.

Fig. 6.

SCALES.

Fig. 1, 2, and 3	1 Inch = 1000 Feet.
Fig. 5	1 Inch = 100 Feet.
Fig. 6 and 7	1 Inch = 16 Feet.
Fig. 10	1/2 Inch = 1 Foot.
Fig. 11	3/4 Inch = 1 Foot.
Fig. 12	3 Inches = 1 Foot.
Fig. 13	1 Inch = 50 Feet.

RIVER-BED OPPOSITE HARBOUR: 1816 — 1900.