Associate Members.

HUGH MACANDREW BAIKIE, B.Sc. (*Edin.*).
 EDWARD CAMM.
 WILLIAM HENRY ELSLEY CARR.
 MAURICE VAUGHAN COOPER.
 GEORGE MALCOLM CRUICKSHANK, M.A.
 (*Cantab.*).
 GEORGE CHARLES WOLSELEY DAVSON.
 CYRIL HORACE MORTIMER ELWELL,
 B.Sc. (Engineering) (*Lond.*).
 GEORGE GRAY FORSTER.
 JOHN FORSTER.
 GO KHEK GHEE, Stud. Inst. C.E.
 FREDERICK WILLIAM HEY.
 ROBERT CHARLES HODSON.
 EDWIN WILLIAM ARNOLD HUMPHREYS.
 HARIOCHANDRA KRISHNARAO KOR-
 GAOKAR, B.Sc. (Engineering) (*Lond.*).
 FREDERICK TREMAYNE LANE, Stud.
 Inst. C.E.

CHARLES WILLIAM LAWMAN.
 NAGINDAS JAKISONDAS MODI, L.C.E.
 (*Bombay*).
 WILLIAM DUDLEY VERE MONIES, B.Sc.
 (Engineering) (*Lond.*).
 GEORGE FREDERIC PALMER.
 WILLIAM PEARCE.
 HASTINGS GEORGE REGINALD PEET.
 NOEL FREDERICK PEMBERTON-PIGOTT.
 CYRIL WILLIAM RICE.
 IVOR FRANCIS SHELLARD.
 PERCY FRANCIS SPILLER, Stud. Inst.
 C.E.
 DUDLEY HEPBURN STENT.
 JOHN TAYLOR THOMPSON, Stud. Inst.
 C.E.
 ALEXANDER THOMSON.
 THOMAS WALMSLEY.

(Paper No. 4184.)

“The Present Conditions of Arterial Drainage in Some English Rivers.”

By RICHARD FUGE GRANTHAM, M. Inst. C.E.

In his Inaugural Address in November last the President drew attention to the fact that the agricultural resources of this country are not fully utilized, and in particular he alluded to the want of combination or unification of authorities in the control of some of the principal rivers for the purpose of dealing with the flooding of large areas of land, by which in the past great damage and loss has been sustained.

The Author, as one of the two Special Commissioners appointed by the Board of Agriculture and Fisheries in 1913 to inquire into and report upon the conditions affecting arterial drainage in certain river-valleys, has had recent opportunities of examining the drainage-systems in the valleys of many of the rivers on the east side of England, in which perhaps the largest and most injurious amount of flooding has taken place; and although the inquiries so made, in conjunction with his colleague Mr. C. Bidwell, Past-President of the Surveyors' Institution, have been largely connected with the administrative aspects of the question of the prevention of floods, many features of engineering interest have presented themselves.

The conditions relating to some of the basins of the rivers to which it may be interesting to refer have been fully described and discussed in Papers by the late Mr. W. H. Wheeler¹ and the late Mr. J. E. Williams.² But, with the exception of the outfall works on the Witham, so little has been done for many years in the valleys in which floods have principally occurred that it may be worth while to refer to their present condition, in view of the important though temporary measure recently passed by Parliament at the instance of the Board of Agriculture and Fisheries, for the improvement of arterial drainage, and of the Provisional Order issued by the Board, under the provisions of that measure, for the improvement of the Great Ouse.

EAST NORFOLK AREA: RIVERS BURE, YARE, AND WAVENEY.

The valleys in East Norfolk were among the first which the Author and Mr. Bidwell were directed to examine. They are drained by the rivers Bure, Yare, Wensum, and Waveney, and their tributaries (Figs. 1-3, Plate 6). The total area drained by the system is about 786,000 acres, and the area within the watersheds liable to flood and injury by flood is approximately 74,000 acres of marsh land. Some of this land lies as low as 2 to 4 feet above Ordnance Datum, that is below and near the level of high water of ordinary spring-tides at Great Yarmouth. Most of it is embanked against the tides, and the interior drainage is pumped up into the rivers.

All the water from these four rivers is discharged, through the narrow channel of the Yare past Great Yarmouth, into the sea opposite Gorleston.

For many years past, when the Author has had occasion to visit some of the marshes, complaints have been made to him that the rise of the tide has increased, causing overflows, so that the embankments have had to be raised. The additional rise has been attributed to improvement-works in Yarmouth Harbour. Before this question can be decided, however, other facts must be considered. Breydon Water, a large natural tidal reservoir about 1,000 acres in extent, is, and has been for many years, silting up. For a long time after the sea had left the flat land of the valley, Breydon Water was

¹ "Description of the River Witham and its Estuary, and of the various works carried out in connection therewith, for the drainage of the Fens and the improvement of the navigation," Minutes of Proceedings Inst. C.E., vol. xxvii, p. 59. "The Conservancy of Rivers: the Eastern Midland District of England," *ibid.*, vol. lxvii, p. 201.

² "The Witham New Outfall-Channel and Improvement Works," Minutes of Proceedings Inst. C.E., vol. xcv, p. 78.

probably almost entirely covered by most tides; now, however, large areas of mud-flats are visible which are covered only by high tides.

The river Yare also is liable to become silted up, and for some distance below Norwich there is a large accumulation in the bed of the river. Much of the silting at the present time is attributed to the passage of swift motor-boats and steam-launches, the wash from which frets away the edges of the banks on both sides all along the river. The material thus eroded from the banks falls into the river; and considerable quantities must, owing to the sluggish currents above Reedham, remain there. It is probable that overflows of the tide are due not so much to the rise of tides as to subsidence of the embankments.

After the terrible experience of the flood on the 25th and 26th August, 1912, Mr. Arthur E. Collins, the City Engineer of Norwich, reported to the Corporation on the improvement of the river with a view to relieve the city of Norwich of floods.¹ The following Table shows the rainfall in various parts of Norfolk on the occasion of the flood in question:—

RAINFALL OF THE 25TH AND 26TH AUGUST, 1912, AT NORFOLK STATIONS.
(Compiled by Mr. A. W. PRESTON, of Norwich.)

	Inches.		Inches.
Denver	3·92	Brundall	8·09
Wareham	4·24	Moulton	7·13
Spörle	2·72	Northrepps	5·46
Dunham	3·57	Gunton	6·89
Watton	3·80	Worstead	5·89
Caston	3·85	Dilham	3·86
Santon	4·66	Rippon Hall	6·05
Great Witchingham	3·37	Acle	4·05
Hingham	3·99	Ormesby	6·59
Wymondham	6·52	Great Yarmouth	5·12
Hethersett	7·33	Dunston	7·22
Keswick	6·88	Swainsthorpe	7·01
Drayton	6·60	Saxlingham	6·65
Norwich (Eaton)	7·34	Hedenham	4·03
„ (Ipswich Road)	7·36	Geldeston	4·48
„ (Cemetery)	7·51		

Thus the rainfall at Norwich on the 25th and 26th August, 1912, nearly equalled the total rainfall for the whole of the month in each of the two wettest years recorded, namely, 1878 and 1892.

Mr. Collins proposed in his report to dredge out from the bed of the river between Yarmouth Bridge and Foundry Bridge, Norwich, depths ranging from 2 feet 6 inches to 8 feet, the greatest

¹ A manuscript copy of the report, presented by Mr. Collins, is in The Institution Library.

depth being between Buckenham Ferry and Foundry Bridge. He proposed also to cut off various bends in the river near Norwich and to set back some of the embankments of the marshes, so as to form in time of extreme floods "wash-lands," and to improve the water-way through the city of Norwich. His estimate of the cost of these works was £350,000.

Tidal observations made by him in the Yare on the 3rd August, 1901, showed that at 11 a.m. on that day, when the level of high water was approximately 4 feet 9 inches above Ordnance Datum at the Gorleston Pier-Head, it was 2 feet 3 inches above O.D. at New Mills, Norwich, or 2 feet 6 inches lower than at the pier-head. At 5 p.m. on the same day, when the level was about 3 feet 2 inches below O.D. at low water at Gorleston Pier-Head, it was 2 feet 9 inches above O.D. at New Mills. Thus, while the tide had fallen 7 feet 11 inches in the 6 hours at Gorleston Pier-Head, at New Mills it had risen 6 inches. The distance apart is 31 miles. Mr. Collins says in his report:—"The resistance of the river in its lower reaches is so great that notwithstanding Breydon Water was very low at times during the recent floods, the river overflowed parts of the walls near Cantley, i.e., it was unable to discharge its volume properly, even with a low level of outfall."

The late Sir John Coode, in reporting to the Duke of Bedford on the River Nene in 1874, observed similar conditions in that river between Peterborough Bridge and Stone Ends—also a distance of 31 miles.

He showed that the level of water at Peterborough Bridge at high water of spring-tides on the 26th September, 1874, was practically 7 feet below high water at Stone Ends; also that on the neap-tide of the 21st September, 1874, high water at Cross Guns was 8 inches below high water at Stone Ends; and he expressed the opinion that the difference of 7 feet at springs is due in a considerable degree to the short duration of the flood, arising from the obstructions at the outfall and the state of the channel at and near Wisbech.

The late Mr. W. H. Wheeler, in an exhaustive report to the Denver Sluice Commissioners in 1884, shows on a longitudinal section of the Great Ouse that while the level of high water of an extraordinary tide on the 11th March, 1883, at Alexandra Dock, King's Lynn, was 16 feet 6 inches above O.D., the level of high water at Denver Sluice, 13 miles higher up the river, on the same date, was 15 feet 9 inches above O.D., or 9 inches lower than the level at the dock. The high waters of ordinary spring, mean and neap tides were, however, level throughout.

From these observations it appears that the lower level of high

water in a tidal river at its upper end, as compared with the level at the outfall some miles away, indicates obstructions in the bed and banks of the river.

Mr. Collins's scheme of improvement of the Yare would undoubtedly ensure a more rapid discharge of flood-water through Yarmouth Harbour, and would relieve not only Norwich City but also the agricultural lands below it.

A further proposal by Mr. Collins to relieve the river of flood-water was the erection of a large sluice at Mutford Bridge, near Lowestoft, so that the water might be discharged through Lowestoft Harbour.

After the passing of a local Act of Parliament in 1827 a new cut was made from the river Yare at Reedham to the river Waveney near Haddiscoe station, the Oulton Dike was improved and widened, and a communication was made between Oulton Broad and Lake Lothing, the latter being a natural tidal basin opening to the sea through Lowestoft Harbour. A lock and sluice were also erected to prevent the fresh waters from Oulton Broad and Dike from flowing into Lake Lothing. The whole of these works are now vested in the Great Eastern Railway Company.

The advantage of the proposed new sluice at Mutford Bridge will be apparent from consideration of the flow of the tides.

The flood-tide flowing from Great Yarmouth into Oulton Broad makes high water on the "Broad" side of the lock-gate at Mutford Bridge, about $18\frac{1}{2}$ miles from the bar at Great Yarmouth, 4 hours later than high water at Great Yarmouth bar, whilst high water at Lowestoft Harbour is only 40 minutes later than at Great Yarmouth bar. Thus the tide at Lowestoft has been falling for nearly $2\frac{1}{2}$ hours on the Lake Lothing side of the lock-gate at Mutford Bridge, about $1\frac{3}{4}$ mile from the sea at Lowestoft, before the flood-tide from Great Yarmouth has reached its highest level on the other side.

Great relief would therefore be felt in the valleys of both the Waveney and the Yare by the letting-off of flood-water, as soon as it began to rise, through large and easily-worked sluices at Mutford Bridge into the sea at Lowestoft. The sluice could, of course, be so worked as not to interfere with the ordinary level required for navigation.

Those interested in these proposals are the Great Yarmouth Port and Haven Commission, the Norwich Corporation, and the owners of land on the banks of the Waveney and Yare; but the Great Yarmouth Port and Haven Commission is the only authority empowered to deal with the rivers.

The Commission derives its existence and powers from an Act passed in 1835, but an Act passed in 1911 modified its constitution

and increased the number of Commissioners. Its jurisdiction extends up the river Bure from its confluence with the Yare to Coltishall lock; up the Yare from Great Yarmouth to New Mills, Norwich; and up the Waveney from its confluence with the Yare to Ship-Meadow lock. The Commission depends for its income upon tolls, dues, rents, etc., and has no power of rating land. Its statutory interest in the rivers is navigation; and although the dredging undertaken by it increases the capacity of the rivers for drainage, nothing more is done than will serve the purposes of navigation.

Three bodies of River Commissioners act as separate Committees for their respective rivers under the control and superintendence of the Port and Haven Commission: the Norwich Commissioners represent the Yare; the Norfolk Commissioners the Bure, and the Suffolk Commissioners the Waveney.

The Bure and its tributaries are in a neglected state, and their present condition is attributed in part to the flood of August, 1912, having deposited banks of mud, altering the channel entirely, and causing much obstruction to navigation and loss of trade.

The Waveney also is in need of improvement, and the embankments protecting the land from inundation are low. The Waveney Valley Drainage Act passed in 1866 created Commissioners for the purpose of improving a length of about 25 miles of the river from Beccles to Hoxne Mill. The Act appears to have become quite inoperative.

The river Yare is, of course, the most important of the three rivers, owing to the trade with Norwich. The Corporation of Norwich therefore, as well as the owners of the lands along the banks of the river, are most deeply concerned, owing to the damage and loss sustained in times of abnormal floods.

The marshes are flooded in such times chiefly by the bursting of the embankments surrounding them. These embankments are composed of the poorest kind of alluvium, and the height of the banks is not sufficiently maintained to prevent overflow. Although the surface is very good pasture, the subsoil of the land is quite unfit for making embankments which must be sufficiently compact to resist water-pressure. The best material that can be got in the district is that dredged from various parts of the rivers.

The difficulty in carrying out such a scheme of improvement as that designed by Mr. Collins is, as in the case of many—perhaps most—other rivers, not only the raising of funds sufficient for the purpose, but also the absence of any single authority with power to undertake the work.

In the case of the Yare, the Port and Haven Commissioners are

not concerned, nor probably could they apply their funds, to improve the drainage of the country; the Norwich Corporation, deeply interested as they are, could not equitably raise an adequate contribution, and the land that would derive benefit from the improvement in the valleys of the Yare and Waveney, about 32,000 acres in area, could not bear the heavy rate which would fall upon it.

THE FEN DISTRICT (Figs. 4 and 5, Plate 6).

In his Paper on River Conservancy in 1881 Mr. Wheeler gave full particulars of the areas drained by the Witham, the Welland, the Nene, and the Great Ouse; the rises, falls, and inclinations of the tides; and the improvements previously made in those rivers.

The Author proposes only to describe the present condition of the rivers and the steps which have been taken towards their improvement.

THE GREAT OUSE (TIDAL PORTION).

The area drained by the Ouse is about 2 million acres, but the area rateable for maintenance and improvement is approximately 364,000 acres, including the areas now governed by the Middle Level and the South Level Commissions (both at one time united with the North Level Commission in the jurisdiction of the Bedford Level Corporation) and by other bodies having rating-powers over, in some districts, the same areas.

The Bedford Level Corporation was created by Royal Charter in the reign of King Charles I, but an agreement had previously been made between Commissioners appointed by the King and by Francis, Earl of Bedford, whereby the Earl contracted to drain at his own cost the Great Level of the Fens, in consideration of a grant of 95,000 acres, of which the King was to receive 12,000 acres. Following this agreement, an indenture was made between the Earl of Bedford and other proprietors of 360,000 acres of land in the Great Level that they would contribute as adventurers to the costs of the works and divide the reserved lands in proportion to their contributions.

Subsequently large main drains were cut, and the course of the river was straightened by means of the Eau Brink Cut and the cuts made more recently by the Norfolk Estuary Company, so completing the system now in existence.

Under Acts of 20 & 21 Vic. 1857 and 25 & 26 Vic. 1862 the North Level area and the Middle Level area were separated from the jurisdiction of the Bedford Level Corporation, and each of those two districts is now governed by its own body of Commissioners.

It is well known that the surface of the fen land, like the surface

of many marsh lands in other parts of the country, is subsiding—in some fens, it is said, at the rate of 1 inch per annum—perhaps more in some places and less in others. A striking example of subsidence exists at Whittlesea Mere, where the surface has now subsided 5 to 10 feet below its original level. The Mere was first drained in 1851 by the establishment of a pumping-engine, and in 1876 the pumps had to be lowered in consequence of the subsidence.

On the other hand, the main rivers and artificial channels have been gradually silting up, and, so far as the Author is aware, no work has been done to improve them for many years, except a little dredging here and there.

But when the authorities concerned in, for example, the tidal portion of the Ouse are enumerated, the difficulties in the way of improvement will be appreciated. At the lower end of the Ouse the Norfolk Estuary Company is responsible for the maintenance of the bed and banks for about 4 miles below Fisher's Creek on the north side of King's Lynn. Through Lynn the King's Lynn Conservancy Board maintains the bed of the channel between Fisher's Creek and the north end of the Eau Brink Cut for navigation purposes only, and is not responsible for the condition of the banks, except so far as these banks form jetties.

The Ouse Outfall Board is responsible for the bed and banks of the river from the north end of the Eau Brink Cut up to St. Germans, at which point the sluices from the Middle Level discharge their water.

From St. Germans up to Denver Sluice the Denver Sluice Commissioners are authorized and required under their Act (1860) to expend the drainage-taxes assessed by them in scouring, cleansing, and deepening the river from Denver Sluice to the Eau Brink Cut, but the banks in that length are maintained by the Ouse Banks Commission, whose area is divided into six districts, each with its own length of bank and rateable area.

The Bedford Level Corporation is responsible for the maintenance of the bed and banks of the Hundred Foot river from Denver Sluice to Earith, and for some other banks.

At an inquiry held at King's Lynn in January, 1914, the principal complaint of the authorities charged with the duty of maintaining their own sections of the channel was that there were shoals in the river below the particular section of each district, so that it was useless for authorities above the Outfall Authority to undertake the clearing and deepening of the river above the outfall.

The Norfolk Estuary Company, under the powers conferred by their Act, commenced operations by making what is known as the Marsh Cut, about 2 miles in length, just below Lynn, and another

cut about 1 mile in length lower down through the Vinegar Middle Sands, the channel of which is confined by training-walls. The statutory depth of the upper end of the Marsh Cut was to be 10 feet below the level of zero on the present gauge on the Eau Brink Free Bridge, and the depth was to increase at the rate of at least 4 inches per mile. The width of the cuts was to be 250 feet at the bottom of the upper end of the Marsh Cut, and to increase 15 feet per mile throughout.

According to soundings which the Author had taken in 1913 the depth at the upper end of the Marsh Cut was 7 feet 6 inches instead of 10 feet, and the width of the bottom 450 feet instead of 250 feet, an excess in width of 200 feet caused by erosion of the banks.

Admiralty soundings taken in December, 1913, showed that at low water of spring-tides there was only 1 foot of water in the channel just opposite the Bull Dog Sand, about 2 miles below the end of the stone training-banks. The banks of the Marsh Cut are much in want of repair, and the stone training-banks have gaps in them which in a measure tend to reduce the effect of the scour which the banks were intended to promote so as to keep the channel clear.

Mr. Wheeler, in the report already referred to, recommended the regulation of the bed of the river from St. Germain's to Denver Sluice; also a new cut about $\frac{1}{2}$ a mile in length to straighten the river at the Magdalen Bend, which has always been an obstruction to the discharge of the water in the river. As long ago as 1809 Mr. John Rennie recommended this cut, but up to the present nothing has been done to give effect to the recommendation.

In March, 1913, the Author had soundings taken in the river from Fisher's Creek below King's Lynn up to the St. Germain's Sluice of the Middle Level Drainage, and found numerous shoals and obstructions, particularly, as might be expected, in the bends of the river.

Mr. Crocker, the Engineer of the Ouse Outfall Board, corroborated these soundings by some which he took subsequently from the end of the stone training-banks up to Denver Sluice, and in a Paper¹ read at a meeting of the Institution of Mechanical Engineers at Cambridge in July, 1913, he remarked that it had been found that low water of spring-tides did not fall to as low a level as in former years. This accords with information given to the Author at the Middle Level Sluice, that low water does not now fall so low by 1 foot 6 inches as it did when the sluice was built.

¹ "The Drainage of the River Ouse Basin," Proc. Inst. Mech. E., 1913, p. 805.

The extension of the stone training-banks for about $3\frac{1}{4}$ miles, to a channel with a depth of 15 to 20 feet, and the removal of the shoal or sand-bar recorded by the Admiralty, together with the regulation of the bed of the river, would undoubtedly lower the level of low water of spring-tides up to Denver Sluice and give relief to the discharge from the various sluices on the way. But the relief as far as St. Germain's would be limited, for according to Mr. Wheeler's statement (1881) the average low water at the Free Bridge above Lynn was at that time 3 feet 8 inches above low water of spring-tides in the estuary. According to Mr. Crocker, the difference is now 4 feet 2 inches between Free Bridge and Lynn Roads. The improvements from St. Germain's to Denver Sluice and the cutting-off of the Magdalen Bend would lower still further the level of low water at Denver Sluice. The effect of making the Eau Brink Cut was to lower low water at Denver Sluice by 6 feet.

No large works have been undertaken recently to improve the Ouse, but a reference to the steps which are now being taken towards that object will be of interest.

In December, 1914, an Act was passed entitled the Land Drainage Act, 1914, under which power is given to the Board of Agriculture and Fisheries to constitute by Provisional Order a body for the purpose of executing any work of drainage, embankment, or defence against water which, in the opinion of the Board, is desirable for the improvement or protection of any area, and for making such provision for the execution and maintenance of the work as the Board may think proper. The Provisional Order is to provide rating and borrowing powers.

In the first part of the Session of 1915 a Provisional Order confirmed by Parliament was obtained for creating a body for the purpose of carrying out the following improvements in the Ouse:—

The extension of the existing training-walls, and the clearing and dredging of the channel of the river between the north end of the Eau Brink Cut and the termination of such training-walls.

The cutting-off of the Magdalen Bend, and the clearing, widening, and deepening of the existing channel of the river between $\frac{1}{4}$ mile above Denver Sluice and the south end of the Eau Brink Cut.

The clearing, widening, and deepening of the channel between the north and south ends of the Eau Brink Cut, and the improvement and maintenance of the banks.

When carried out these works will undoubtedly give great relief to the discharge of the sluices up the river, e.g., the Marshland sluices draining about 37,000 acres, and the Middle Level Sluice draining 157,000 acres, and above all to Denver Sluice, draining

884,338 acres. It has been calculated that the improvement-works alone between St. Germain's and Denver Sluice would lower the level of low water in floods by 4 feet 6 inches, and of low water of ordinary spring-tides by 1 foot, without reckoning the additional depression caused by the removal of the sand-bar opposite the Bull Dog Sand, and the shoals above it.

The effect of these improvements on the areas draining through the Denver Sluice would be almost incalculable. In winter-time the surface of the water in the tributaries of the Ouse, particularly the Wissey, the Little Ouse or Brandon river, etc., stands for a long period at such a high level that there is not much margin between it and the tops of the banks for flood-water, and bursting of the banks is not infrequent.

The upper or west parts of the South, Middle, and North Levels were more or less flooded by the great rainfall of the 26th August, 1912, and it will be remembered that in January, 1915, excessive rainfall caused a bursting of the north bank of the Brandon river and a disastrous flood, submerging, when the Author saw it, an area of about 13,000 acres in the Feltwell New Fen District and the Feltwell Second District to a depth of about 2 to 4 feet. Subsequently to the Author's inspection the flood rose still higher and overflowed the main road into the Methwold district, covering altogether about 21,000 acres. At the time, the Feltwell New Fen Commissioners were erecting a new pumping-engine at Southery, but unfortunately the suction pipes had not been put in when the water rose about the engine-house floor. Temporary portable engines and pumps were fixed higher up the bank, but these could not do much within any appreciable time in lowering the flood-water, and for the season the land was utterly ruined for agricultural purposes. The area is a scene of devastation, as most of the farm-houses, cottages, and other buildings have been washed down and are in ruins.

Large areas in the South Level are in a deplorable condition, and at least 5,000 or 6,000 acres are waterlogged for want of a better system of drainage.

The Hundred Foot river, 21 miles long, up which the tide flows past Denver Sluice to Earith and to Bluntisham instead of up the old course of the Ouse, its passage being stopped up the Ouse by Denver Sluice, is much in want of widening and deepening, and the banks in the lower part are in a bad state of repair. Nothing has been done to it for years, and although it is 100 feet wide and fairly deep at Earith, lower down the present width of its channel is not more than 50 feet, and in some places less, and

in parts it is so shallow that barges are stranded on the bottom in summer-time. It is still silting up.

The Old Bedford river is also much choked and neglected in the upper part of its length. The consequence in 1912 was that large areas above Earith up to St. Ives and Huntingdon were severely flooded.

The Middle Level district, containing a rateable area of about 120,000 acres, discharges the whole of its water, besides upland water from 37,000 acres, through St. Germain's Sluice into the Ouse. Its main outfall drain, 8 miles long, from the sluice to Outwell, was designed and carried out by Messrs. Walker and Burges. At Upwell penstock-sluices worked by hand were built for the purpose of holding up the navigation level of water in the main drains in the district. A new roller sluice of one span, 45 feet wide and 12 feet deep, has been substituted recently for the four old sluices, each 10 feet in width, and is worked with much less labour.

The flooding of the upper or west end of the Level is due in a large measure to the want of a catch-drain to intercept the water coming from the high lands.

In 1809 Mr. John Rennie recommended the formation of catch-drains for the Middle Level, one to discharge into the Nene at Stanground, the other to join the Ouse at Earith. Later, Sir John Rennie recommended also the formation of a catch-drain discharging into the Nene, and another discharging into Monks Lode near Ramsay. Neither of these plans was carried out. At the present time the silted-up condition of the Nene on the one side and the Ouse on the other, and the high level of the water in the main drains, render such a scheme impracticable.

In 1842 Mr. James Walker designed a line of drain 32 miles long, for drainage apart from navigation, from St. Germain's Sluice through the Middle Level to Caldecot Farm at the foot of the high lands near Holme. Only 11 miles of this drain were cut, the lower 8 miles constituting the present main outfall drain of the Level. The remainder of the drain was abandoned, and in substitution parts of the original main drains which were then and are still used for navigation were widened and deepened. Considering that the fall on the surface of the water in the drains in floods is only 1 to 2 inches per mile, Mr. Walker's original proposal to cut the drains for drainage only would, in the Author's opinion, have been of great benefit to the drainage of the area and the means of intercepting the flood-water from the uplands, which in excessive rainfalls now causes so much damage to the upper or west end of the area—the lowest in altitude in the Level.

GREAT OUSE (NON-TIDAL PORTION).

Spring-tides in the Ouse flow as far as Brown's Hill Stanch, Bluntisham, above Earith. Above tidal limit the river, which passes through the counties of Cambridge, Huntingdon, and Bedford, through St. Ives, Huntingdon, Tempsford, and Bedford, is in a very neglected condition, most of it—except, perhaps, the reach at St. Neots—being almost filled with weeds, which cause the formation of banks and islands, thus arresting the silt and debris brought down during floods. Including Bluntisham Stanch, there are fifteen locks in the river up to Bedford. The valley is very narrow, so that the land affected by floods could not bear such a rate as would be necessary to repay the cost of improving the river; moreover, there is no single authority which can deal with it. It is said that an improvement of the river in that length would cause the revival of navigation, from which funds might be contributed to defray the cost of improvement. As long ago as 1876 the late Mr. James Abernethy reported to the Ouse Floods Committee on the condition of the river between the Hundred Foot river and Brampton, and recommended the removal of all impediments in the bed, the enlargement of the mill-weirs for the discharge of floods, and, amongst other things, the removal of the St. Ives Stanch, Brown's Hill Stanch, and the Sevenhole Sluice at Earith, as well as the enlargement and regulation of the channel of the Old Bedford river and the Hundred Foot river. In order to provide funds for the works, he suggested that a very light tax should be levied on the upland districts within the 756,000 acres draining through Earith.

THE NENE.

The obstructions in the outfall and the state of the channel of the Nene appear to remain very much as described by Sir John Coode in 1874.

As in the case of the Ouse, Admiralty soundings in December, 1913, discovered a shoal about $1\frac{1}{2}$ mile below the "Stone Ends" of the training-banks, the channel there being said to be awash at low water. Mr. Wheeler states that the improvement made about 80 years ago by the excavation of a new channel through the Cross Keys washes to Crabhole and a further extension of the training-banks for about $1\frac{1}{4}$ mile caused a lowering of low water at the North Level Sluice by 10 feet. A further extension of the training-banks some distance past the shoal noted by the Admiralty would

lower still further the level of low water at the North Level Sluice, but not to the same extent. On rare occasions the gates of the North Level Sluice are kept closed for some days owing to a combination of north-easterly gales and high tides.

In 1913 the Author had occasion to have soundings taken and cross sections made of the bed and channel of the river from Sutton Bridge through Wisbech to Guyhirne. The banks of the river are kept in excellent order between the North Level Sluice and Osborne House below Wisbech, but the Walton Dam below Wisbech, referred to by Sir John Coode as penning back the water, still exists. It has the effect of holding back flood-water as far as Guyhirne and more or less to Peterborough. The sharp and narrow bend through Wisbech remains, although all the eminent engineers who have reported on the improvement of the river since 1769 have recommended a new cut to avoid the bend.

The sectional area of the channel above Wisbech up to Guyhirne is much contracted and insufficient for the discharge of flood-water, and in some parts from Guyhirne to Peterborough the bed is so silted up that in summer-time it is possible to walk across it.

At Northey Gravel, between Guyhirne and Peterborough, the owners of the Thorney Estate have the right to take fresh water from the river to supply the estate, and it has been apprehended that an improvement to the river by deepening and regulating its bed above Guyhirne would be the means of bringing salt water up to the fresh supply at Northey Gravel. Proposals have been made to overcome the objection by erecting a dam with lock and sluices below Northey Gravel, but the possible effect of the dam on the regime of the river below it is open to question. The wash-lands above Guyhirne suffer severely from the obstructions in the river, and although they were intended to take flood-water for a time, so as to regulate the level of floods in the river, the water remains on the lands much longer than was anticipated.

In 1913 Messrs. Coode, Matthews, Fitzmaurice and Wilson, in a report to the North Level Commissioners on the flooding of the low-lying lands of the North Level, the drainage from which discharges into the Nene, referred to the fact that a good deal of water escaped from the Car Dike on to the adjoining fen land. The dike there is part of the catch-drain cut by the Romans from Lincoln to the Nene at Peterborough, and used by them as a canal. In some parts the banks of the dike are referred to as being so low that flood-water would overflow part of the North Level. The dike has been neglected, and in some parts abandoned, but if its banks were kept up to an adequate height and the channel

were maintained in good order, much of the water coming from the uplands would no doubt be intercepted and prevented from overflowing on to the fen lands.

A division of authorities similar to that in the Ouse exists in the tidal portion of the Nene, and so long as these conditions remain no effectual improvement of the tidal portion of the river can be made. The low-lying area that would benefit by improvements is about 160,000 acres.

THE WELLAND.

So far as the Author has examined the river, its condition, if not worse, is little better than as described by Mr. Wheeler.

The area administered by the Welland Outfall Trustees contains 82,000 acres, including 30,000 acres of the interior district, which comes within the jurisdiction of the Deeping Fen Trustees.

When the Witham Outfall Improvement Act, 1880, was before Parliament the Welland Trustees obtained the insertion of a clause to the effect that if within 20 years of the completion of the works in the Witham they desired to cut and form an improved channel from the then point of confluence of the two rivers, and intimated their desire to do so to the Witham Outfall Board, that Board should pay one-half the cost of the Welland Cut, or £20,000.

Nothing was done, however, owing to lack of funds available to the Welland Trustees, whose powers of rating were limited. The cut is undoubtedly much needed, as well as the deepening and improving of the bed of the river all the way up through Spalding to Market Deeping, and perhaps beyond.

Since 1912 the Deeping Fen Trustees have erected at Pode Hole new auxiliary pumping-plant, comprising a centrifugal pump and a Diesel oil-engine, by means of which they pump the water from their interior district into the Vernatts drain, which at the reservoir discharges through a sluice side by side with the outfall sluice of the Glen into the Welland.

The river Glen, the main tributary of the Welland, affords another example of divided authority for its maintenance. The Deeping Fen Trustees are responsible for its bed, the Glen Bank Trustees, the Black Sluice Commissioners and the Bourn South Fen Drainage Board for various parts of the banks.

From Pinchbeck Bars to near Kates Bridge the channel of the river is confined between high banks across the fens, the bed of the river being nearly on a level with the surface of the land. These banks, about 13 feet high, are made chiefly of peat and earth, and

rest on the peat foundations of the fens, so that when very high floods occur the banks are unable to withstand the pressure and give way at some weak point. Thus serious breaches have occurred in 1830, 1831, 1837, 1872, 1877, 1882, 1897, and 1910. The Author had occasion to inspect the breach in December, 1910, when the water from the river submerged about 11,000 acres of land, mostly arable.

In 1879 the Glen Sluice was rebuilt and the sill was lowered 6 feet, but advantage was not then taken of the increased depth to deepen up the river. A scheme has lately been prepared for deepening the bed and strengthening the banks from the sluice to Kates Bridge, and the Development Commission has provisionally approved a grant towards the expenditure.

THE WITHAM.

Notwithstanding the great improvement which followed the lowering of the low-water level caused by the new outfall cut in the Witham in 1880 and the widening of the lock at the Grand Sluice, large areas of land in the neighbourhood of Horsley Deep and upwards and above Lincoln are frequently under flood. In 1877 the late Sir John Hawkshaw proposed a scheme for the purpose of relieving this part of the district, his estimate of the cost being £567,820. He suggested that in order to raise the necessary capital the uplands should be brought within the rateable area.

Mr. J. Healey Johnson, the Engineer of the Witham General Commissioners, has informed the Author that at low water there is never less than 1 foot of water on the sill of the Grand Sluice, and that the tidal gates are open during only 4 hours of the tide. It would seem that under present circumstances some works, in addition to those which Sir John Hawkshaw proposed to diminish the flooding above Lincoln, are required above the Grand Sluice to relieve the flooded lands higher up.

Notwithstanding the fact that the Witham drains about 730,000 acres and the Witham General Commissioners have a rateable area of 146,800 acres, the area that would receive benefit from any works above the Grand Sluice is comparatively small; the rate due to the expenditure on the extensive works necessary would therefore be exceedingly heavy on that area.

Three authorities are responsible for the maintenance of the bed and banks of the Witham between the Grand Sluice and Lincoln and some distance above Lincoln, namely, the Witham General Commissioners, the Great Northern Railway, and, for some

distance above, the Lincoln Court of Sewers. The upper part of the river from Stapleford Bridge to its source is maintained by the Grantham Court of Sewers.

The Witham General Commissioners' area is divided into six districts, with a total rateable area of 146,800 acres; two of the districts are on the north and east sides of the river and four on the south and west sides. The rateable area of the Black Sluice Commission on the west side contains altogether 86,000 acres, and for drainage purposes rates the second and sixth districts of the Witham Commissioners' area, while the latter Commissioners rate the second and sixth districts only for the maintenance of the bank on the west side of the Witham.

The Black Sluice discharges the water into the tideway at the lower end of Boston, while the water from the fourth district of the Witham, besides that from an area of 5,000 acres on the east side of the Steeping river above Wainfleet, is discharged through the Hobhole Sluice and the Maud Foster Sluice into the tideway in and below Boston on the east side. Excluding the Black Sluice area and the fourth district, there remain only 36,488 acres of the remaining three districts in the Witham General Commissioners' area which could be brought within the scope of lands receiving benefit from improvements made in the Witham above the Grand Sluice. There are, however, areas partly below and partly above Lincoln containing in the aggregate about 8,625 acres which might be included in the rateable area of land deriving benefit from improvement works above the Grand Sluice, so making a total of 45,113 acres.

The importance of maintaining the Car Dike, the catch-drain made by the Romans to intercept the upland water from the high ground on the west side of the valley and used by them as a canal, seems to have been quite lost sight of, although Sir John Hawkshaw clearly pointed out what should be done with it. It is now for the most part an overgrown narrow ditch, and in some places it has been entirely filled and obliterated. If the dike were restored to adequate dimensions, provided with a sufficient outfall, and properly maintained, there can be no doubt that the low-lying land round about Horsley Deepes would be to a large extent relieved of a good deal of flooding. To open up only that part of the dike between Washingborough and the drain called Billingham Skirth would intercept water from an upland area of about 37,000 acres of land which now discharges through the intervening fens into the Witham.

The low-lying parts of the city of Lincoln are frequently flooded,

but it will be seen that even with a contribution from the city the large cost of the works necessary to relieve the district would inflict upon the area likely to receive benefit a rate too heavy to be borne.

A general survey in 1913-14 of the low-lying lands in the valleys referred to showed that a good many of the drains of the interior system had been neglected, and many other drainage-districts inspected by the Author in various parts of the country exhibit similar want of attention. During the long period of comparatively moderate rainfall, although there were occasional floods in some districts between 1883 and the great storm of rain which occurred in August, 1912, the necessity for keeping the drains clear seems to have been overlooked, and, beyond "roding out" to keep them clear of weeds, very little was done. The following Table shows the fluctuations of rainfall over Southern Lincolnshire, 1868-1912:—

Year.	Rainfall expressed as Percentage of the Average.	Year.	Rainfall expressed as Percentage of the Average.	Year.	Rainfall expressed as Percentage of the Average.
1868	101	1883	127	1898	81
1869	111	1884	75	1899	87
1870	75	1885	102	1900	110
1871	99	1886	118	1901	87
1872	142	1887	64	1902	91
1873	88	1888	89	1903	127
1874	77	1889	103	1904	83
1875	126	1890	78	1905	90
1876	128	1891	102	1906	103
1877	106	1892	95	1907	99
1878	107	1893	74	1908	78
1879	109	1894	92	1909	109
1880	144	1895	88	1910	108
1881	111	1896	92	1911	86
1882	128	1897	93	1912	133

After the great rainfall of August, 1912, an impression seems to have prevailed in the Fens that it was necessary, in order to relieve the land of flooding, to establish large pumping-stations at the outfalls of the various districts concerned, some of these districts containing areas as large as 20,000, 80,000, and 150,000 acres. No doubt the large pumping-plants required would have increased the velocity of the current of the water and lowered its level within certain limits in the vicinity of the pumps, but they would not have relieved the flooding of the upper ends of those areas, say, 10 to 20 miles away, unless the drains in the whole system were sufficiently deepened and enlarged to conduct the water to the pumps and keep them supplied.

In describing the conditions of the river Spey, the President alluded in his Inaugural Address to obstructions caused by loose stones and gravel, the interception or removal of which is not infrequently a source of difficulty and expense in dealing with rivers fed by mountain streams.

The Author has examined two smaller rivers in which the debris from the mountains causes considerable obstruction and overflow; one, the Derwent, in Cumberland, flowing from Derwentwater lake to Bassenthwaite lake and thence to the sea at Workington, and the other, the river Sulby, in the Isle of Man, discharging into the sea at Ramsey. In the Derwent large quantities of stone are washed in flood times down from the screes or heaps of broken stone which lie at a steep angle against the mountain sides. The stones thus brought down fill the river, and the flood-water overflowing bursts the banks and not only floods the marsh or moss below, but covers the fields for some distance with the stones. The Drainage Board's engineer proposed to form pits near the upper ends to catch the stone, which would be removed periodically and used for road-making and road-repair. He has now, however, been able to localize the deposition of the stones in a particular beck, and if this is kept clear, the catch-pits will be unnecessary. In the Sulby river, which drains an area of 19,500 acres, large quantities of earth and stones are washed down and choke the channel, so causing overflow and flooding of about 4,000 acres. The Highway Board's engineers proposed to form dams across the narrow valleys of the various streams in the mountains to intercept the earth and stones washed down in floods. The advantage of such dams is somewhat doubtful, inasmuch as the thousands of tons of earth and stone which are brought down by floods would quickly fill the dams and flow over them. To remove the debris from the dams would involve sending men long distances up into the

mountains, and the expense would add considerably to the cost of maintaining the river. In any case the periodical removal of materials of the kind must be a serious item in the cost of maintenance of rivers in such situations.

CONSERVANCY OF RIVERS.

The establishment of Conservancy Boards, each with powers for dealing with the whole length of the main river, has been advocated for many years, but up to 1915 all attempts to create them have failed, the suggested means of providing funds for the considerable amount of work necessary in each large river being at the root of the failure. The Rivers Conservancy Bill of 1879 proposed to divide the catchment-basin of each river into lowlands, midlands, and uplands, which were to be rated in a diminishing ratio according to their respective altitudes. This Bill, as a member of the Committee which sat to consider it informed the Author, was defeated by the midlanders, who next to the owners of the lowlands would have to pay the largest rates. As an illustration of the feeling in the matter, it may be mentioned that at an inquiry into the drainage conditions of the Welland, held by the Special Commissioners of the Board of Agriculture and Fisheries at Spalding in 1913, a question was asked as to rating some land above the present rating-area in the river Glen, when the late Lord Kesteven said that any attempt to rate the higher lands would be bitterly opposed. The warning contained in that remark was emphasized in the case of two schemes of drainage upon which the Author held inquiries in Yorkshire in 1914. It was then proposed, for the purpose of mitigating flooding, to form two drainage districts with rating powers under the Land Drainage Act, 1861, in the valleys of two rivers frequently and sometimes seriously flooded, the length of the river affected in one case being 14 miles and in the other 39 miles. The proposed boundaries of the districts coincided in some parts with the 100-foot contour-line, while the levels of the flood-water in the rivers were far below it. Both schemes were strongly opposed by the owners of the higher lands, and it was necessary to modify the boundary lines to a considerable extent. The interpretation of the intention of the Land Drainage Act and the Sewers Laws has always been that land should be rated according to benefit received or damage avoided, and it is impossible to maintain that agricultural land 50 feet or even 25 feet above the level of floods either derives benefit or avoids damage from the removal or lowering of the floods.

Two cases may be cited of the formation of large drainage-areas under private Acts of Parliament, under which drainage-works have been carried out without laying the higher lands under contribution.

The Thames Valley Drainage Act, 1871, created a body of Commissioners whose jurisdiction included the flat and much-flooded land in the valleys of the Ock, Cole, Cherwell, Evenlode, Windrush, Leach, Coln, Ray, Churn, and the Swill Brook, tributaries of the Thames above Long Wittenham. These tributaries drain an area of 826,900 acres, while the area actually flooded was 71,096 acres. The highest flood-line, and also a line 5 feet above it, were surveyed by the officers of the Ordnance Survey, and the area thus ascertained was divided into seven districts, each with its separate Drainage Board, charged with the duty of improving the watercourses and brooks within its limits, while the Commissioners have the exclusive right of executing, under the provisions of the Act, any works affecting such parts of the Thames and its tributaries, the Ock and a branch of the Ock, the Cherwell and the Ray, as fall within their jurisdiction. The rateable area is 58,679 acres. The operations of the Commissioners and of the District Boards have yielded much improvement in relieving the lands in the valleys of flooding.

Similarly, the Somersetshire Drainage Act, 1877, established a body of Commissioners whose jurisdiction extended over the flooded lands in the valleys of the Parrett, Tone, Carey, Brue, Axe, and Yeo. The area drained by these rivers is 607,400 acres, and in the winter of 1872-73 the floods covered an area of 69,000 acres. The rateable area is 125,465 acres. The area within the jurisdiction of the Commission is divided into sixteen districts, and in several of the districts the water is lifted by pumping-engines into the respective rivers.

The Commissioners have the exclusive right of carrying out any works affecting such parts of the bed-soil or banks of the rivers Parrett, Brue, Carey, Axe, Tone, and Yeo as are within the jurisdiction of the Commissioners, either for maintenance or improvement of existing works, or for the construction of new works; and they have also the exclusive right of constructing, maintaining, and repairing all sea-walls, banks, and other defences against the sea. The District Boards have exclusive rights of carrying out any works within their respective jurisdictions, but any improvements of existing works, or construction of new works, must have the consent of the Commissioners.

With the exception of the new cut for the outfall of the Witham,

the recommendations made in the numerous reports of engineers who have been engaged from time to time have not of late years resulted in any improvement of the rivers in the Fen districts, mainly because of the complication of authorities which control parts of the rivers. The Land Drainage (Ouse) Provisional Order Confirmation Act, 1915, may certainly be looked upon as a step in advance, for while it does not embrace the whole length of the river, or the whole of the low-lying districts drained by it, it specifies works for the improvement of about 20 miles of the lower and most important part of the tidal portion of the river, and gives power to raise funds from a large area to meet the cost of the improvements. It is believed that the Development Commissioners are disposed to render financial assistance towards the cost of the specified works.

The action of the Board of Agriculture and Fisheries in obtaining the Act, taken in conjunction with the benevolent attitude of the Development Commission, opens up possibilities of improvements in other rivers; but in order that the conservators of rivers may have control, not only of the main river but also of the tributaries, further legislation would appear to be necessary. A good deal of time for preparation will have been gained.

Perhaps, after the War, when labour problems of quite another character from those which now present themselves will have to be met, it may be considered expedient to proceed with some of the large and urgent works of drainage now awaiting favourable conditions for their fulfilment.

It can hardly be doubted that the areas of agricultural land now lying almost derelict, which could thereby be brought into profitable cultivation, and the lands which suffer at times so severely from flooding, would ultimately yield profitable returns upon the necessary expenditure incidental to those works.

The Author desires to express his thanks to Mr. J. Healey Johnson, M. Inst. C.E., Mr. Arthur E. Collins, M. Inst. C.E., Mr. Leopold Harvey, of Spalding, Mr. R. W. Ellett, of Cirencester, Mr. C. H. J. Clayton, of the Board of Agriculture and Fisheries, and others, for much valuable information and assistance.

The Paper is accompanied by four sheets of drawings, from which Plate 6 has been prepared.

ARTERIAL DRAINAGE IN ENGLISH RIVERS.

Fig: 1.

Fig: 3.

Fig: 4.