(*Paper No. 3235.*)

“Railway Bridge over the Fitzroy River at Rockhampton,
Queensland.”

By WALTER JAMES DOAK, B.E., Assoc. M. Inst. C.E.

THE bridge described in this Paper spans the Fitzroy River at a point about 40 miles from its mouth. At the site of the bridge the river has a width at low water of 500 feet, and an average depth of 40 feet. It drains the very large area of 54,700 square miles, and in the wet season, which occurs in the months of January, February and March, it is subject to very heavy floods, the greatest on record being that of 1896, when the water rose to 20 feet above high-water level. There is, however, little danger of any flood rising to a greater height than this, as there is a natural waste-channel about 5 miles above the bridge, which allows the bulk of the water of the heavier floods to escape along a chain of lagoons which appear to have once been the principal channel of the river; and it is notable that all the greater floods at Rockhampton have varied in height only a few feet. Both above and below the bridge the channel is much impeded by rocks, especially on the north side, and about 200 yards down-stream there is a bar of fissured rocks showing above low water and extending almost completely across the channel. There is little doubt that at some future time this bar will be removed and the flood-level at the bridge will be lowered. The bridge constitutes the connecting link between the railways running from Rockhampton almost due west to Longreach (424 miles), and from North Rockhampton to Broadmount (24 miles), the future deep-water harbour of the district. It carries a double line of way of 3 feet 6 inches gauge, and consists of two central spans of 246 feet, flanked at the north end by two 100-foot spans, and at the south end by one span of 100 feet (Fig. 1, Plate 3).

PIERS.

The first and second piers from the south side are founded in the bed of the river; the third and fourth piers are on rock, the surface of which is a few feet above high water. The open-caisson method was adopted for building the two river-piers, Nos. 1 and 2; of these, pier No. 2 was the first erected.

Pier No. 2.—Previous borings at the site of this pier showed that the bed of the river was composed of hard schistose rock, the dip of which, being about 40° south-west, caused the bottom to be of a very rough and pointed character. Before proceeding with sinking operations, this rock was levelled off with the aid of dynamite, care being taken to avoid shattering the rock outside the area of the pier.

The caisson for this pier was of wrought iron, with straight sides and circular ends, the dimensions being 42 feet in length, and 13 feet in width (Figs. 2, Plate 3). It consisted of two parts, permanent and temporary. The permanent portion is 46 feet 6 inches high from the cutting edge to the junction with the temporary top; the latter, being intended to keep out the water between high and low tides and to be removed after completion of the concreting above high-water mark, was 13 feet 6 inches high. The lower caisson was framed with vertical tee-bars, 4 inches by 3 inches by $\frac{3}{8}$ inch, spaced 4 feet apart on the straight sides, and 5.35 feet apart round the semicircular ends, and with horizontal channel-bars 5 inches by $1\frac{3}{4}$ inch by $\frac{9}{32}$ inch, also spaced 4 feet apart from centre to centre. This framing was covered on the sides by buckle plates, 4 feet by 4 feet by $\frac{1}{4}$ inch, and on the ends by $\frac{1}{4}$ -inch wrought-iron plating, except for the lowest 10 feet 6 inches of the caisson, which was covered by $\frac{1}{2}$ -inch wrought-iron plating. The side walls were connected by six vertical walls, dividing the caisson into seven chambers down to within 10 feet 6 inches of the cutting edge; three of these chambers were closed at the bottom and formed buoyancy-chambers, the other four were used as dredging-wells. In the lowest 10 feet 6 inches, constituting the working-chamber, there were no cross-walls, the requisite strength being obtained by vertical stiffening-plates, 1 foot 6 inches by $\frac{3}{8}$ inch, attached to the vertical framing at right angles to the walls, and strengthened against buckling along the edge by angle-bars, 3 inches by 3 inches by $\frac{1}{4}$ inch. A horizontal annular stiffening-plate, 1 foot 6 inches wide, running round the inside of the caisson at the 10-foot 6-inch level, was also

provided. The cutting edge consisted of a plate 12 inches by $\frac{1}{2}$ inch, riveted outside the bottom edge and projecting 2 inches below it. The lowest 34 feet 6 inches of the caisson was built on shore on its side, on launching-ways, with the cutting edge farthest from the water; the open ends of the buoyancy-chambers were boarded up, and the whole was strengthened by temporary timber struts. At the lower end a timber lip was provided along the whole width of the caisson, presenting an inclined surface to the water; the idea being that this lip, on striking the water, would assist the caisson to right itself and would prevent it from diving too deeply into the water. The absence of buoyancy-chambers in the lowest 10 feet 6 inches of the caisson insured the centre of gravity being sufficiently below the centre of buoyancy to cause the caisson to right itself when in water of the required depth. Cables were taken from the caisson to a steam-winch on a large punt anchored in the river opposite the launching-ways; these were to be hauled on as soon as the caisson took the water, in order to get it into deep water before it turned over.

The launch took place at high tide, about 11 o'clock on the 30th August, 1898. On the caisson taking the water it was seen that the lip did more harm than good, as it presented so square a front to the wave generated as to seriously retard the motion of the caisson: so much so, that before deep water was reached the cutting edge had grounded on the mud. On hauling with the steam-winch it was found that the anchor of the punt dragged, and instead of hauling the caisson into deep water the punt pulled itself shorewards. A wire rope was then carried across from the punt to the south bank and secured to a mooring-post, and by this means the caisson was successfully pulled out into deep water and towed to a position on the north side of the river between two punts, where the rest of the material could be brought to it and the erection of the upper portion could be proceeded with. As more material was added the caisson gradually sank, and for convenience in erection as well as to secure additional stability, the buoyancy-chambers were loaded with sand and water as ballast. Sufficient height having been built to insure the top being above water when the bottom was resting on the bed of the river, the caisson was brought to the levelled site and sunk. Its position was controlled by six cables; one of these was anchored in the river up-stream, one was taken to a hand-winch securely fixed above high water on rocks about 800 feet down-stream, and the other four were made fast to trees, etc., on the banks, two up-stream and two down-stream.

The excavation within the caisson was carried on by shifts of four divers at a time, the air being at first supplied by hand-pumps of three-throw type, and afterwards by an air-compressor on the north side. The air was led from the receiver of the compressor by pipe under water to a small receiver on a punt moored to the caisson, and from this receiver four separate pipes provided with gauges and regulating-valves supplied air to the divers. By this arrangement one man could regulate the pressure of each diver's supply according to his requirements. The material excavated was brought up in buckets by means of a steam jib-crane, and was deposited in a punt, which when full was taken a little way down-stream and emptied into the river. The sinking of this caisson proceeded very regularly. The rock was of such a nature as to break readily under the hammer and gad, and the excavation was easily taken out almost to the exact size required, 2 inches outside the caisson. The average rate of sinking was about 6 inches per day, and the amount of rock excavated was 198 cubic yards. Excavation commenced on the 7th October, and finished on the 29th November, 1898. The cost of excavation was £4 5s. per cubic yard. Before the bottom level was reached the first two rows of plates of the temporary caisson, making 9 feet in height, were put on; and these were sufficient, except at extremely high tides, to prevent the caisson from being completely submerged. The method of controlling the position and sinking of the caisson proved very satisfactory, the position of the pier being practically exact. On completion of the excavation, the bottom was thoroughly cleaned out and concreting was commenced.

Concreting.—About 26 cubic yards of concrete was deposited in bags containing about a cubic foot each. These bags were of oblong shape, and were placed as alternate headers and stretchers. A gutter had been excavated round the inside of the cutting edge, and the bags were packed tightly into it. Above this they were laid to a height of 4 feet against the caisson-wall with a batter of 1 to 1 towards the middle, forming a triangular wall on a 4-foot base. At the same time about forty rivets were cut out of the walls at about low-water mark, so that on the rising of the tide the water would fill the caisson through the rivet-holes instead of being forced through the partially set bagwork, and thereby destroying every possibility of watertightness. The concrete in these bags was composed of 1 part of Portland cement, 1 of clean sharp sand, and $2\frac{1}{2}$ parts of small blue metal screenings. Four or five of these bags were deposited close to the bank of the river, in order to give an idea of the state of those in the caisson. After a

fortnight they proved to have set well and to have some adhesion to one another and to the rock upon which they were deposited, showing that the cement had succeeded in passing through the meshes of the bags sufficiently to cause them to cohere. On the top of this bagwork, concrete, in the proportions of 1 part of Portland cement, 2 parts of sand, and 4 parts of stone broken to 2-inch gauge, was deposited through the water, by the aid of divers. The whole of the working-chamber and the dredging-chambers, to the top of the permanent caisson, was filled in this way. During the process of depositing this concrete through the water, a large quantity of cement was washed out, together with some of the sand, and floated to the surface in a scum or remained suspended in the water; in fact, the value of the concrete when deposited would be hardly, if at all, more than if it had been gauged 1 : 3 : 6. A fortnight later, when the water was pumped out, the top of this body of concrete was found to be covered with a layer of slurry, or, as it is technically called, "laitance," between 1 foot 6 inches and 2 feet thick, which had settled during the fortnight it was allowed to remain undisturbed. This material, when cleaned off and dried, shows about as much consistency as a poor lime plaster and is very light. Its chemical analysis shows it to consist of 31.04 parts of lime and 37.44 parts of silica, besides magnesia 1.67, alumina and iron 7.84, and sulphates of lime, etc., 2.59, in a total of 80.58 parts. No stoppages were allowed in the work; the men worked in eight-hour shifts, and the whole of this concreting was thus done in one operation. After the fortnight allowed for setting, the rivet-holes previously mentioned were plugged, and the temporary caisson was pumped out. There now remained the buoyancy-chambers unfilled. The water in these was gradually lowered by a small Worthington pump and a pulsometer. The chambers, as already described, were 13 feet wide, 4 feet long, and 34 feet deep. The plating on the 13-foot walls was removed, exposing the face of the concrete which had been deposited through the water. The 4-foot sides were part of the outer wall of the caisson, and under the pressure of about 45 feet of water at the highest tides, the channel-bars supporting the buckle plates deflected inwards, in some cases as much as $1\frac{1}{4}$ inch; and it was considered advisable to support them by 8-inch round poles, from side to side of the caisson, wedged against the centres of the bars. The exposed concrete proved to be rather insufficiently set, owing to very slow-setting cement having been used.

The slurry before mentioned as having been found on the top of the concrete also showed on the faces of the exposed walls, in depths varying between $\frac{1}{2}$ inch and 3 inches. It was also seen that in some parts the stone and mortar were more thoroughly mixed than in others. On the whole, however, the concrete must be regarded as satisfactory, as samples taken from it at various periods have hardened well and continue to harden, and there is every reason to believe that the concrete in the caisson is hardening in the same way; in fact, the concrete walls of the buoyancy-chambers hardened considerably during the time they were exposed before being covered by the concrete in the chambers. The latter were filled with cement concrete deposited in the ordinary open-air method, thoroughly rammed, and constituting solid masses of the best class of concrete directly under the bearings of the superstructure. The portion of the pier between high- and low-water was deposited inside timber framing in the ordinary way. On completion of this, the temporary caisson was stripped from the pier.

Pier No. 1.—The foundations were levelled off to receive the caisson in the same manner as for pier No. 2. The caisson is almost exactly similar, but is of different dimensions, the permanent portion being 40 feet long, 11 feet wide, and 50 feet 6 inches high. It was built on the same site as caisson No. 2, but about 40 feet farther up the bank; this was done because a beginning was made in laying down the plates before caisson No. 2 was launched. Some alterations were made in the method of launching, the timber lip provided for No. 2 being omitted altogether from No. 1, and care being taken to securely anchor the punt carrying the steam-winch. However, the result was not very different; the caisson slid gently into the water to a depth of about 8 feet before beginning to right itself, and the winch was not quick enough in taking up the slack to prevent the cutting edge from subsiding on to the mud; but the caisson was hauled without difficulty into deep water. The remaining portion was built partly close to the north bank and partly over the site of the caisson, 100 feet from the south abutment. This caisson, on account of its small width, was rather unstable in the water, and it was therefore necessary to put sand in the buoyancy-chambers to an average depth of 8 feet. Piles were driven between the south abutment and pier No. 1, and a temporary wharf was formed on which a jib-crane was erected and the smaller air-receiver for the divers was stationed. The outermost row of piles was placed so as to leave a clearance of

4 inches between the wharf and the side of the caisson. When the caisson was brought alongside, three more piles were driven on the outer side and connected near the heads by wales bolted to them, and the two end piles were tied to the wharf by short wales. The caisson was thus surrounded by guide-piles. Its movements were also controlled by four long steel-wire cables anchored to the shore on one side and to anchorages in the bed of the river on the other side. This caisson, however, was much more difficult to manage than No. 2, on account of its want of stability and the strong tidal currents. The range of tide is about 10 feet between highest and lowest springs, and about 6 feet between ordinary springs. This range causes very strong currents, which at the site of pier No. 1 attain a velocity of 4 miles per hour.

It was intended to sink this caisson in the same manner as that at pier No. 2; but when the cutting edge was still about 4 feet 6 inches above the level at which it was expected to found the pier, the caisson refused to sink deeper, although the buoyancy-chambers were loaded with sand and water equivalent in weight to 140 tons at low water. On investigation it was discovered that the walls of the working-chamber had been forced inwards, so that the cross widths tapered down from 11 feet at the top, where the walls of the chamber was supported by the cross walls, to an average of 8 feet 9 inches at the cutting edge. The work was temporarily suspended, and, after consideration, it was decided not to attempt to sink the caisson deeper, but to underpin it along the keels of the buoyancy-chambers by means of upright round timbers standing on sills laid in trenches excavated down to foundation-level. Excavation was then proceeded with, and the walls were forced back to within a few inches of their original position by hydraulic jacks, after divers had cleaned out the broken stone which had accumulated against the outside of the caisson. This débris continued to run in, so that before concreting it was found necessary to put in slabs of timber outside the cutting edge, in order to keep it out. The forcing in of the caisson-walls was no doubt due to pressure caused by the loose state of the surrounding rock, which, being of a soft nature, had been considerably broken up by the numerous piles which had been driven to provide guides for the caisson and a platform for convenience of working. Probably the walls began to be forced inwards when the caisson was only a few feet down, and consequently the excavation, which was done on the inside, following the cutting edge, took a wedge shape; and the deeper the caisson sank the more the sides were wedged in,

until the upper portion supported by the side walls, being too strong to yield, prevented the caisson from sinking deeper.

Taking advantage of the experience gained at pier No. 2, the concrete was made richer in cement, so that instead of the proportion being 1 of cement, 2 of sand, and 4 of stone, it was 1 of cement, $1\frac{1}{2}$ of sand, and 3 of stone. Concreting was stopped each night at 5 o'clock, and before starting again next morning all the slurry which had deposited during the night was thoroughly cleaned off in the hope of securing greater homogeneity. The permanent caisson, with the exception of the buoyancy-chambers, was filled up in this way. The stripping of the side walls of the buoyancy-chambers showed that the addition of one-third of a cask of cement to the mixing had a most beneficial effect, as the concrete was perfectly homogeneous and the amount of slurry was much less; this latter advantage, however, was no doubt due to the cleaning off after each day's work. In filling these chambers it was not found necessary to place struts across from side to side, the channel bars supporting the buckle plates, although deflected about $\frac{3}{4}$ inch near the bottom, not being stressed beyond the elastic limit. Indeed, it is probable that these bars would have withstood the pressure in caisson No. 2 had it been considered advisable to run the risk. A certain amount of leakage occurred in the up-stream and down-stream buoyancy-chambers, but it was easily met by baling.

SUPERSTRUCTURE.

250-foot Spans.—For these spans a hog-back Linville type of girder was adopted, the radius of the curve of the top boom being approximately 538 feet, giving a depth at the centre of 30 feet 9 inches, and at the ends of 16 feet 6 inches between the centres of intersections.

The main girders are 26 feet apart from centre to centre. The web-bracing consists of a double system of vertical posts and inclined ties (Figs. 3, Plate 3). The panel-length is 15 feet $4\frac{1}{2}$ inches, so that the sixteen panels give a length of main girder of 246 feet between the centres of the end posts. The top boom consists of side plates, four angle-bars on the outsides, and top flange-plates. The bottom boom consists of side plates and four angle-bars, the two end bays being furnished with double lacing to allow for reversal of stress under wind-pressure. The vertical posts near the ends are built of four angle-bars and two side plates with a single system of lacing; the seven posts near the centre have four angle-bars only, connected by lacing. The end posts are built with side plates and four angle-bars on

the inside, and are also furnished with a diaphragm up the centre. The seven tie-bars at the ends consist of four flat bars each, the middle four ties and the six counter-ties have only two flat bars each. All intersections are effected by means of riveted gussets.

The cross girders, 28 feet $3\frac{1}{2}$ inches long over all, are 3 feet 1 inch deep in the middle portion of 16 feet 6 inches, and decrease in depth towards the ends to 2 feet under the posts. The web-plate is $\frac{7}{16}$ inch thick, the flange-angles are 4 inches by 4 inches by $\frac{1}{2}$ inch, and the top and bottom flange-plates are 21 feet 9 inches and 16 feet long respectively, and alike 11 inches by $\frac{1}{2}$ inch in section. The ends of the longitudinals are riveted to the webs of the cross girders and obviate the necessity of web-stiffeners. The rivets for a distance of 18 inches inwards from the centre of the main girder are 1 inch in diameter, and the pitch is 3 inches; for the next 3 feet 3 inches, to the first longitudinal attachment, they are $\frac{7}{8}$ inch in diameter, with a 3-inch pitch, and in the remaining middle portion the diameter is $\frac{3}{4}$ inch and the pitch is 4 inches. The cross girders are suspended below the main girders by means of two tongue-plates riveted to the webs of the posts and the cross girders.

The deck is of the American type, the rails, weighing 60 lbs. per yard, being laid to 3 feet 6 inches gauge on hardwood transoms, 7 feet 6 inches by 8 inches by 5 inches, set on the narrow side 1 foot $8\frac{1}{2}$ inches apart from centre to centre. These transoms are laid on timber longitudinals, resting on the tops of the steel longitudinals, to the flanges of which the transoms are bolted. The timber longitudinals serve two purposes, one being to raise the transoms clear of the lower lateral wind-ties, and the other to enable the 4 inches of camber of the span to be reduced on the rails to 1 inch. The steel longitudinals on each track are spaced 5 feet 6 inches apart from centre to centre, and are 15 feet 4 inches long and 1 foot 7 inches deep. They consist of a $\frac{3}{8}$ -inch web-plate and four angle-bars 4 inches by $3\frac{1}{2}$ inches by $\frac{7}{16}$ inch, and are riveted to the webs of the cross girders at such a height as to cause the tops of cross girders and longitudinals to be in one plane.

Each span is provided with upper and lower lateral wind-bracing, the former consisting of angle-bars attached by riveted gussets to the top plate of the booms at every second post, and the latter of flat bars laid over the cross girders and longitudinals, and similarly attached to the booms at every second post. The main girders are also connected by heavy latticed

portal-bracing at the ends, and by light latticed sway-bracing at intermediate posts.

100-foot Spans.—These smaller spans are carried by simple rectangular Linville trusses, 16 feet 6 inches deep, with a single system of vertical posts and inclined ties. The top boom is built with side plates and four angle-bars outside, connected by two single systems of lacings. The bottom boom is built of flat bars, the posts of side plates and four angle-bars with single lacings. The end posts have two side plates and four angle-bars inside, the two sides being stiffened by four stay-plates spaced about 4 feet apart. The ties are all formed by two flat bars. The deck is of similar design to that on the 250-foot spans. The steel longitudinals are 12 feet $5\frac{1}{2}$ inches long and 1 foot 4 inches deep; the web is $\frac{3}{8}$ inch and the flange-angles $3\frac{1}{2}$ inches by $3\frac{1}{2}$ inches by $\frac{3}{8}$ inch. They are riveted to the webs of the cross girders, which are 2 feet $9\frac{3}{4}$ inches deep in the middle portion of 16 feet 6 inches, decreasing to 2 feet under the posts. The cross girders are 27 feet 2 inches long, the web is $\frac{7}{16}$ inch, the flange-angles are 4 inches by 4 inches by $\frac{1}{2}$ inch and the flange-plates are 21 feet and 15 feet long respectively, and alike 11 inches by $\frac{7}{16}$ inch in section. Upper and lower lateral bracing of design similar to that in the 250-foot spans is provided, also portal-bracing at the ends, and knee-bracing at the intermediate posts.

Expansion-bearings are furnished at one end of each span. In the 250-foot spans they are of cast steel, the six rollers, which are 8 inches in diameter and 2 feet 6 inches long at the bearing-surfaces, being shaped so as to lock in extreme positions, thus preventing the possibility of their working too far in one direction. They are kept parallel and square by means of wrought-iron frames fitting over studs in the ends of the rollers. These rest on a planed bed-plate $2\frac{1}{2}$ inches thick, and support a saddle-plate of $1\frac{1}{2}$ -inch metal with three feathers, 4 inches wide, tapering from nothing at the edges to $2\frac{1}{4}$ inches at the junction with the pin-socket. The saddle-plate carries a semicircular pin, 7 inches in diameter, with the flat side down, and on this rests the bearing-plate of 2-inch metal immediately under the centre of the end post of the span. The fixed bearings in the 250-foot spans consist of a bearing-plate resting on a 7-inch pin carried by a deep bed-plate. In the 100-foot spans the bearings are of cast iron. The six expansion-rollers are 2 feet long and 4 inches in diameter, and are designed to lock like the steel bearings, except that the pin is circular instead of semicircular.

Footway.—The design of the bridge includes a footway on the

down-stream side. Steel cantilevers are riveted on to the square ends of the cross girders. In the 250-foot spans they are 6 feet long, 1 foot 3 inches deep at the attachment to the cross girders, and 9 inches deep at the outer end. The web is of $\frac{1}{4}$ -inch plate, and the flange-angles are 3 inches by 3 inches by $\frac{3}{8}$ inch, with $\frac{3}{4}$ -inch rivets having a pitch of 4 inches. At 1 foot from the outer end rests the parapet-girder, 4 feet 6 inches high. The top flange is a T-bar 4 inches by 3 inches by $\frac{3}{8}$ inch; the bottom flange is a T-bar 5 inches by 4 inches by $\frac{3}{8}$ inch. The web consists of $1\frac{1}{2}$ inch by $\frac{1}{4}$ inch latticing, at an angle of 45° , forming openings 1 foot square. The rivets are $\frac{1}{2}$ inch throughout. Provision for expansion is made by means of cast-iron bearing-plates with studs through slotted holes in the flanges of the lower T-bar. Hardwood joists, tapering from 4 inches to $3\frac{3}{4}$ inches in depth, and $2\frac{1}{2}$ inches wide, spaced 18 inches apart from centre to centre, rest their ends on the flanges of the main and parapet girders, and are bolted thereto. The planking is of hardwood, 4 inches by $1\frac{1}{2}$ inch, laid diagonally.

Erection.—On account of the great floods to which the Fitzroy is liable in the summer months, it was considered advisable to specify that no falsework should be allowed between piers Nos. 1 and 3, that is, in the main stream. Consequently it was arranged to build the 250-foot spans on shore, and to launch them by means of the hulk “Jennie Parker,” which had previously been used successfully for a somewhat similar purpose at the Albert Bridge, Indooroopilly.¹ In the case of span No. 3, it was first necessary to build timber staging between piers Nos. 3 and 4 and the north abutment, and also on the 50 feet between pier No. 3 and the edge of the river-bank. Two sets of staging, 26 feet apart from centre to centre, were provided, in order to come directly below the main girders. The foundations here being solid rock on the surface, it was comparatively easy to sink the piles a few feet into the rock and to concrete them in. The piles in each set of staging were arranged in groups of four, 4 feet apart at the top, each pile battering out at 1 in 8. These groups of piles were spaced 18 feet 6 inches apart. Headstocks, 6 feet long and transverse to the bridge, connected the tops of the piles in pairs, and on these were laid four corbels 5 feet in length, which in their turn supported the four girders of spotted gum or ironbark in the round, 16 inches in diameter. The groups of piles were roughly braced with 8-inch saplings spiked

¹ Minutes of Proceedings Inst. C.E., vol. cxxxii. p. 288.

on. Ordinary ironbark sleepers, 6 feet 9 inches by 9 inches by $4\frac{1}{2}$ inches, were spiked down, 18 inches apart from centre to centre, to the girders, carrying 60-lb. rails laid in pairs to take double flanged wheels, the two outer rails being 3 feet 6 inches gauge. On completion of this rail-laying, the cross girders and longitudinals were set up. The former were supported at the ends on chocks, and were wedged up so as to give $4\frac{3}{4}$ inches of camber on the main girders, the extra $\frac{3}{4}$ inch being considered sufficient allowance for settling under their own weight. The longitudinals were riveted to the webs of the cross girders, and then the bottom booms were laid and the joints were riveted up. The posts and top booms were then erected, and after them the tie-bars. Previous, however, to the erection of posts, etc., a double line of rails and sleepers 11 feet apart from centre to centre had been laid on the longitudinals for the purpose of working a travelling erection-gantry (Figs. 4, Plate 3). This gantry, 43 feet high, was built with four main uprights at the corners, covering a base 15 feet by 14 feet 6 inches. These four uprights met in pairs at the top, and supported the arms, consisting of two beams 12 inches by 6 inches, which were also supported by diagonal braces as shown in Figs. 4. Three winches were provided—one for each arm, and one for moving the gantry along the rails. The wire rope from each of the lifting winches was led vertically to the top, over a fixed sheave, horizontally to a sheave carried by a small trolley with four wheels running on rails laid on the tops of the arms, and thence downwards, terminating in ordinary lifting-gear. The small trolley was worked along the arm by a long screw (one for each arm) fitted with a wheel at the outer end, carrying an endless chain long enough to come within reach of a man at the foot of the gantry. The trolley could thus be moved transversely to the bridge. The gantry was provided with a platform at the base, on which the winches were placed. Under each side was placed a four-wheeled trolley, running on the two tracks 11 feet apart. The longitudinal movement of the gantry was accomplished by the hand winch before mentioned, hauling on a fixed wire-rope. In the erection of span No. 2, however, much time was saved by running the gantry by a fixed steam winch. With this gantry the heaviest sections could be lifted and brought into position. Whenever a section was so heavy as to endanger its stability, it was brought close to the gantry, which was then run into position, the side farthest from the section was anchored down to the rails, and the section was run out into place. In general it was found convenient to build

the two main girders simultaneously, and to run out similar sections on each side of the gantry, which was then evenly balanced. For erecting sway- and portal-bracing, a small jib projecting from the side was used. After most of the main-girder riveting was accomplished, the portal- and sway-bracing was erected, and finally the upper and lower laterals. The span now occupied such a position that the north end was just clear of the abutment, and the south end was about 50 feet beyond pier No. 3. Trolleys were placed on the double tracks 26 feet apart from centre to centre; at the north end in the centre of the second bay, or 23 feet from the centre of the end post; and at the south end in the centre of the third bay, or 46 feet $1\frac{1}{2}$ inch from the centre of the end post. These trolleys were built of two balks of spotted gum, 12 inches wide by 16 inches deep, and one balk 3 inches wide by 16 inches deep, all 13 feet long, strongly bolted together. On the under-side, recesses were cut 5 feet apart to receive the three 6-inch fixed axles, fitted with heavy cast-iron wheels 2 feet 6 inches in diameter, with a single flange in the centre of the tread adapted to fit between the double rails previously laid. The main girders were then stiffened with heavy round timbers arranged to relieve the cross strain in the bottom booms at the trolleys, the weight of the girders being transferred from the nearest intersections in the top booms along the timbers direct to the trolleys. Stiffening-timbers were also provided to take the reversal of stress in the tie-bars in the overhanging portions. Just previous to launching, the rails and sleepers on the 11-foot roads were removed; the gantry, of course, had been previously removed to allow of the erection of portal-bracing at the north end.

The launch of this span took place on the 14th June, 1899. The first operation was to run the span forward about 50 feet, so that the end might overhang sufficiently to allow of the hulk "Jennie Parker" being brought beneath in such a position that the centre of the ship would be exactly under the centre of the second bay, about 23 feet from the centre of the end post. This was accomplished by means of a winch manned by four men, which was securely fastened down to the cross girders and longitudinals. A 2-inch wire rope passed from this winch to the south side of the river, round a fixed block and back to the span, to which it was attached by a bridle, secured at the two ends to a cross girder close up to the main girders. The block was held by wire ropes passed round the back of the south abutment. This having been done, the "Jennie Parker" was brought beneath the projecting

end at low tide, and the space between the top of the staging on the hulk and the bottoms of the girders was packed in with 12-inch square pine balks and wedges. On the tide rising, the weight kept the vessel down until her draught was increased 17 inches. The whole of the weight was then on the hulk at the one end, and on the northern trolleys at the other. As soon as the southern trolleys were lifted clear of the rails, a commencement was made to haul across. Besides the hauling-gear on the span, six winches on the hulk were used—three in the bows and three in the stern; of these, two at each end hauled on cables anchored to the banks on both sides of the river a little up-stream and down-stream respectively. By means of these the sideway movement of the hulk could be controlled so as to be at the same rate as the movement of the span, and for this purpose a plumb-line was hung on the centre of the staging, to show immediately any alteration in their relative positions. The other two winches hauled on up-stream and down-stream cables, the former anchored about 200 yards up-stream, the latter firmly anchored to rocks which show above water about the same distance down-stream. By means of these two, lateral deviation from the centre line was kept under control. The movement of the trolleys was assisted by men with heel-bars. The time occupied in the launch was about 55 minutes. The tide, although only just high enough to lift the forward trolleys, had still 1 foot 6 inches to fall to allow the span to come down on its bearings at the central pier. After this had been accomplished, and the tide had fallen a few inches further, the "Jennie Parker" was removed, leaving the span resting on its permanent bearings on the central pier and on the trolleys at the north end. By means of 100-ton hydraulic jacks the north end was lifted off the trolleys and was supported on timber blocks. The trolleys were removed, and the girders and transoms, which would have prevented the span from coming down by reason of the underhung cross girders, etc., were taken off the temporary staging. The span was then gradually lowered on to the expansion-bearings by the jacks working on the tops of the corbels of the temporary staging nearest the pier.

The cross girders and longitudinals for spans Nos. 4 and 5 (100 feet each) were now laid down on the staging between piers 3 and 4 and the north abutment, at such levels as to give $1\frac{1}{8}$ inch of camber on the main girders. On these a temporary double road, 11 feet between centres, was placed; and the two main girders of span No. 4, which had previously been erected on the bank just beyond the abutment, were mounted on eight of the trolley-wheels,

two at each end of each girder. The two girders were temporarily braced together and were run forward over their allotted position by means of a hand winch; blocks were then placed under them and the wheels were removed. It was then necessary to increase their distance apart from 11 feet to 25 feet 9 inches from centre to centre, which was done first at one end and then at the other; the two girders were then lowered simultaneously on to the cross girders and the connections were riveted, leaving only the upper and lower lateral bracing and the portal- and sway-bracing to be completed. Span No. 5 was erected in an exactly similar manner, and, on its completion, the fixed bearings and the expansion-bearings were put in place. The ends of the spans were packed up with timber chocks, the girders and transoms of the staging were removed, and the spans were then jacked down on to the bearings.

The erection of span No. 2 proceeded much more quickly than that of span No. 3, owing to the fact that the greater portion was done on the bank instead of wholly on staging, so that much readier access to the work was obtained. The launching was effected in a similar manner to that of span No. 3, except that the rear trolleys were placed immediately under the end posts. The forward trolleys were as before under the centre of the third bay. This alteration threw additional weight on to the forward trolleys. In span No. 3 the weights on the trolleys were approximately 93 tons on the forward and 79 tons on the rear trolley; in span No. 2 they were 102 tons and 70 tons respectively. This increase in load caused a little trouble in the preliminary operation of running the span forward to overhang the hulk; as the weight was sufficient to drive some of the staging-piles farther into the bed of the river, at one place as much as 5 inches. This subsidence greatly increased the power required to haul the span forward. On the next day, before proceeding with the launch, the depression was taken out by packing the rails, and, in view of further possible subsidence a camber of about 2 inches was left in them. This portion of the staging was anxiously watched during the remainder of the launch, but the rear trolley, being more lightly loaded, was unable to do more than flatten out the 2 inches of camber, and no additional strain was thereby put on the hauling-winch. The arrangements for hauling were almost exactly similar to those previously adopted, and the launch was accomplished in 45 minutes. On reaching pier No. 2, the span was about 6 feet above its bearings; it was not till nearly 5 hours later that it came on to them. This launch took place on the 25th July, 1899. For

lowering the southern ends, the jacks were placed on the top of pier No. 1, under the terminal cross girders, which are riveted to the sides of the end posts; and, in order to relieve the rivets from too great a shearing stress in the process of lowering, timber struts were placed between the top of the cross girders immediately above the points of application of the jacks and the corners formed by the junction of the portal-bracing and the end posts. The weight of the span was thereby transmitted from the tops of the posts along the struts direct to the jacks. The cross girders and longitudinals for span No. 1 were then laid on the bank, close to the south abutment, and the main girders, previously erected, were placed in position, as described for spans Nos. 4 and 5. The whole of the wind- and sway-bracing was erected, and the building of the span was completed. Four-wheel trolleys were then placed under each corner, and the span was hauled forward over the staging provided for launching span No. 2. The ends were packed up, the rails, transoms, girders and corbels of staging were removed, the span being lowered on to its bearings on the 1st September, 1899. The timbering of the deck was then rapidly proceeding, and also the erection of parapet-girders for the footway. All riveting was completed on the 13th September, and all other work, except painting, on the 17th October.

On the 20th October the spans were tested with a rolling load consisting of two trains of two engines each, followed and preceded by five loaded trucks; the total live load was equivalent to 1.66 ton per lineal foot on the 250-foot spans, and to 2.28 tons per lineal foot on the 100-foot spans. The maximum deflections were 1.7 inch on the 250-foot spans, and 0.9 inch on the smaller spans; the permanent set being 0.12 inch on the former and 0.06 inch on the latter.

Loads and Stresses.—The loading provided for in the calculation of stresses in the main girders consisted of a train-load weighing 0.66 ton per lineal foot, preceded by two B 15 engines (Fig. 5, Plate 3), which are of the heaviest type at present in use on the Queensland railways; the total weight of one of these engines with tender is 51.7 tons, the wheel-base is 38 feet 8 inches, and the length over buffers is 45 feet 7 inches. For wind-stresses, 50 lbs. per square foot was allowed for in the upper lateral bracing, and for the lower lateral system 30 lbs. per square foot with a train assumed to be on the bridge, and 50 lbs. with no train. For floor-beams other than the longitudinals the 8 D 15 engine (Fig. 6) caused the heaviest stresses.

For the longitudinals, 12 feet 6 inches long, on the 100-foot

spans the heaviest live load was given by the driving-wheels of engine A 14 (Fig. 7), of which there are four carrying a load of 17·4 tons on a wheel-base of 8 feet.

In all floor-beams a working-stress of 7·5 tons per square inch for dead load and of 5 tons for live load was adopted. In main girders the allowed stress in tension-members was $C \left(1 + \frac{\text{minimum}}{\text{maximum}} \right)$, the constant C being determined in the following manner:—

Ratio of total dead load to total live load is approximately $\frac{1}{2}$.

Working-stress for dead load = $7\frac{1}{2}$ tons per square inch.

” ” live ” 6 ” ”

Stress for combined dead and live loads—

$$\frac{6 \times 2 + 7\frac{1}{2} \times 1}{2 + 1} = 6\cdot5.$$

Hence $C \left(1 + \frac{\text{minimum}}{\text{maximum}} \right) = 6\cdot5,$

$$\text{or } C = \frac{6\cdot5}{1 + \frac{\text{minimum}}{\text{maximum}}} = \frac{6\cdot5}{1 + \frac{1}{3}} = 4\cdot87 \text{ tons.}$$

And stress allowed in any member

$$= 4\cdot87 \left(1 + \frac{\text{minimum}}{\text{maximum}} \right) \text{ tons per square inch.}$$

In the posts the live-load unit-stress was $+ 8,500 - 55\frac{l}{r}$ pounds per square inch, and the dead-load unit-stress was $17,000 - 110\frac{l}{r}$, where l = unsupported length in inches, r = least radius of gyration.

For compression-chords the Cooper formula was adopted; viz., for live-load unit-stress —

$$P = \frac{120}{100} \left(8,000 - 30 \frac{l}{r} \right),$$

$$\text{and for dead load } P = \frac{120}{100} \left(16,000 - 60 \frac{l}{r} \right).$$

The factor $\frac{120}{100}$ is necessary to adapt the formula, intended for wrought iron, to steel.

$$\text{For combined load } P = 11,520 - 43\cdot2 \frac{l}{r}.$$

In the wind-bracing 8 tons per square inch was allowed in tension-members and $\left(P = 13,000 - 85 \frac{l}{r} \right)$ in compression-members.

The stresses in the main girders were calculated by the "engine excess" method, the 250-foot span being treated in two systems. The concentrated-load method is too elaborate, without compensating increase in accuracy, in girders with curved top boom and double system of web-bracing.

The bridge was designed by, and the work was carried out under the supervision of, Mr. H. C. Stanley, M. Inst. C.E., the Engineer-in-Chief for Railways, the Resident Engineer being Mr. L. A. Bernays, M. Inst. C.E., under whom the Author acted as Assistant Engineer. The contractor was Mr. G. C. Willcocks, who was represented on the work by his engineer and manager Mr. H. J. Beatty. The steel for the superstructure and the wrought iron for the caissons were imported from Great Britain and manufactured in Brisbane, whence the finished parts were shipped to Rockhampton. The cast-steel bearings were made in England, but the cast-iron bearings were made at Rockhampton.

The Paper is accompanied by 5 tracings, from which Plate 3 has been prepared, and by 6 photographs.

BRIDGE OVER THE FITZROY RIVER, ROCKHAMPTON, QUEENSLAND.

PLATE 3.

Fig: 1.

Fig: 2.

Fig: 3.

SECTION C C.

Fig: 5.

SCALES

Fig: 1, ... 1 Inch = 80 Feet.

Fig: 2, 4, 5, 6, and 7, 1/16" = 1 Foot.

Fig: 3, ... 1/32" = 1 Foot.

Fig: 6.

Fig: 7.