Mr. Bernays. of form D. C represented the briquette used at Chatham; D that used by the Metropolitan Board of Works. A and B were formerly used at Chatham, but had long since been abandoned.

* * * The reply of Mr. Grant will be found at the end of the Correspondence.

Correspondence.

Professor
Bauschinger.

Professor BAUSCHINGER sent two pamphlets¹ containing the results of numerous experiments made with different kinds of cements. His observations had shown that there was no fixed relation between the crushing and tensile strength of cement. In a series of experiments made with nine cements, the ratio between crushing and tensile strength varied from 11 to 1 to 7 to 1. He had obtained much more uniform results by crushing briquettes having an area of 144 square centimètres, than by the tensile strain on a section of 5 square centimètres. Even when the briquettes were made exactly according to the standard rules by two different experimenters, the results obtained might differ widely. He advocated, in order to decide between competing cements, the adoption of more reliable methods and testing machines, which, though costly, might yet be made accessible to all through the medium of central testing stations.

Mr. Belk.

Mr. WILLIAM BELK stated that works of a similar character to those described by Mr. E. A. Bernays had been carried out at Hartlepool. The Hartlepool Port and Harbour Commissioners had recently constructed a sea wall composed exclusively of blocks formed of Portland cement concrete. The concrete of which the blocks were made consisted of 1 part of Portland cement to 7 parts of Portsmouth grit and sand, each block measuring 18 inches by 9 inches by 9 inches. The parapet of this wall was composed of concrete made in boxes, each box of a length of 12 feet by 3 feet 6 inches, by 18 inches wide, the concrete in this case consisting of 1 part of Portland cement to 9 parts of Portsmouth grit and sand. A quantity of rock was also placed in the hearting of it. The face of the wall and parapet was quite uniform, and in appearance equal to any stone masonry. In addition to the above work, the Commissioners were at present engaged in constructing a break-water for the protection of the harbour, which was also formed

¹ "Mittheilungen aus dem mechanischtechnischen Laboratorium der k. Polytechnischen Schule in München." No. 7, Munich, 1877. No. 8, Munich, 1879.

of concrete blocks, consisting of 1 part of Portland cement to 10 Mr. Belk. parts of shingle, sand and rock, each block measuring 9 feet by 4 feet 6 inches by 4 feet. The seaward faces of these blocks, of a thickness of 5 or 6 inches, were, however, made of a slightly superior quality of concrete, consisting of 1 part of Portland cement to 7 parts of Portsmouth grit and sand. In the earlier stages of this work the facings were composed of Portland cement mixed with crushed granite or whinstone; experience, however, showed that, whilst the facings so composed were more expensive than those composed of Portsmouth grit, yet the latter were equally durable, and consequently grit facings were now exclusively used.

The parapet of this work was formed in boxes *in situ*. Each box measured 14 feet by 10 feet 6 inches by 7 feet; the ingredients in this case being used in the same proportion as in the above blocks. On the removal of the sides of these boxes, the facings were found to be perfect. The cement used in the construction of the above works was of uniformly good quality, finely ground, and weighed 115 lbs. to the striked bushel. The test briquettes of a section of $1\frac{1}{2}$ inch by $1\frac{1}{2}$ inch, after being kept in water for seven days, bore a tensile strain of at least 850 lbs. Great care was taken in the storing of the cement, it being turned out on the floor of the storing house to a height not exceeding 2 feet, and allowed a free current of air.

Herr F. BÖMCHES sent some observations on the use of hydraulic Herr Bömches. lime in the harbour works at Trieste. The reason that hydraulic lime was used instead of Portland cement was that so little was known of the durability of the latter material in the waters of the Adriatic, while hydraulic lime had been successfully used for many years in different parts of the Mediterranean. The lime was obtained from Teil in France; its composition was:—

Insoluble silica	6·20
Soluble „	14·78
Alumina	1·61
Oxide of iron	0·99
Lime	61·83
Magnesia	1·15
Water	6·97
Carbonic acid	6·76
	<hr/>
	100·29
	<hr/>

The proportions adopted were: 1 cubic mètre of sand, 362 kilogrammes of lime, and 0·271 cubic mètre of water. The blocks were parallelopipeds of from 9 to 11 cubic mètres, and were provided

Herr Bömches, with two grooves to receive chains. The blocks were built up in the same way as ordinary rubble masonry, care being taken that each stone was surrounded with mortar. The best stones were selected for the face, and dressed with the hammer if necessary. The corners and grooves were built with great care, and with a proper bond. No mould was used, but the grooves were built with the aid of posts 0·15 metre square. The proportion of stone to mortar varied from 60 to 40 up to 65 to 35, according to the regularity of the stones and the coarseness of the sand. The blocks were allowed to harden at least three months before use. In twelve years 8,538 blocks had been immersed, of which 3,987 were raised again by divers, on account of alterations which had become necessary. Of this number 91·3 per cent. were in perfectly good condition, 6·2 per cent. in such a state that they could be repaired, and 2·5 per cent. beyond repair. Among those which had remained sound were some which had been immersed to a depth of 12 mètres below low water, and others which had been subjected to enormous strain through the settling of the wall of which they formed part. In most cases the fracture had taken place through the imbedded stones, showing the strength of the cementing material.

This communication was accompanied by the report of a committee named by the Austrian Association of Engineers and Architects, to consider the question of the uniform nomenclature and testing of hydraulic limes,¹ and by the rules adopted (April 10th, 1880), by that Association in conformity with the report of the committee.

Mr. Cay.

Mr. W. DYCE CAY stated that he had tested and used about 15,000 tons of Portland cement at Aberdeen Harbour Works in the last ten years, manufactured by six different makers and delivered in one hundred cargoes. He used seven-day and fourteen-day tests for tensile strength, and occasionally broke some briquettes at twenty-eight days. All were made with neat cement, and many of them were immersed in water when gauged, were taken out when set and removed from the mould, and then at once returned to the water, where they remained till taken out to be broken. When the cement was to be used for concrete in bags or for concrete in mass, which was to be deposited in water before setting, he preferred this system of testing to the ordinary one of waiting till setting had taken place sufficiently for removal

¹ Wochenschrift des oesterreichischen Ingenieur- und Architektenvereines, No. 18. 1880.

from the mould before immersion in water, as being more analogous Mr. Cay. with the use of the cement in the work. The proportion of water used for mixing with the cement, omitting exceptional cases, was 8 oz. of fresh water to 36 oz. of cement. He had also made a number of experiments with salt water for mixing, the proportion being 7 oz. of salt water to 36 oz. of cement.

The following Table gave instances of the great increase of strength obtained by the use of salt water, and would seem to show, as far as experiments with neat cement could show it, that in sea works the use of salt water for mixing in place of fresh is advantageous instead of being merely optional. Roughly speaking, the salt-water briquettes were as strong in a week as the fresh-water ones were in a fortnight, and as strong in a fortnight as the fresh-water ones were in a month.

Though the German system of testing with cement mortar mixed in the proportion of 3 parts of standard sand to 1 part of Portland cement, and broken after twenty-eight days' immersion in water, was in many respects superior to the old system of testing with neat cement briquettes broken after seven and fourteen days' immersion, he trusted the latter would not be altogether abandoned, as the twenty-eight-day tests would involve practical difficulties on many works, owing to the delay necessitating large storage accommodation to prevent stoppage of the works. The suitability of the sand employed also introduced a new element of dispute and investigation. He still thought that the seven- and fourteen-day neat cement tests, combined with a sufficiently severe test for fineness, would give a good idea of the quality. The invariableness of the specific gravity given by Messrs. Dyckerhoff's experiments, showed that the weight per bushel was not a criterion of the value of the cement, but rather an index of the grinding, the finer ground being the lighter. Having found the same result from practice, he had altered his specifications of later years, to avoid paying for the useless weight, and had specified that the weight was not to be less than 108 lbs. and not greater than 115 lbs. per bushel, the manner of filling the measure being also specified. The German test with cement mortar briquettes, however, did away with the use of the weight test, as fine grinding, or the lowest weight per bushel, was essential for high results with it.

Mr. C. COLSON observed, with regard to the question of grinding, that in the earlier days of Portland cement the degree of fineness was never alluded to; now, however, the custom was to specify that the cement should pass through a sieve of a given number of

Mr. Colson.

TABLE SHOWING THE RELATIVE STRENGTH OF BRIQUETTES OF NEAT CEMENT WHEN MADE WITH FRESH WATER and when MADE WITH SALT WATER.

Proportions used :—8 oz. of fresh water to 36 oz. of cement ; 7 oz. of salt water to 36 oz. of cement.
Briquettes immersed in water when sufficiently set to allow of their being taken out of the mould.

Number of Cargo.	Tons Delivered.	Date of delivery.	Weight per Bushel, of 10 Bushels.	Fineness.		Tensile Strength.					
				Weight of a Bushel which was Sifted.	Residue on Sieve with 900 Holes per Square Inch.	Seven-day Tests.			Fourteen-day Tests.		
						Fresh Water.		Salt Water.	Fresh Water.		Salt Water.
						Number of Briquettes Broken.	Average Tensile Strength of $1\frac{1}{2}'' \times 1\frac{1}{2}''$ Area.	Number of Briquettes Broken.	Average Tensile Strength of $1\frac{1}{2}'' \times 1\frac{1}{2}''$ Area.	Number of Briquettes Broken.	Average Tensile Strength of $1\frac{1}{2}'' \times 1\frac{1}{2}''$ Area.
70	290	1875 Sept. 3	Lbs. 120.0	Lbs. 118.5	6.8	14	836	15	907	Lbs.	Lbs.
71	220	" 10	120.0	120.0	3.5	16	840	14	1,002	994	1,044
72	215	" 14	118.5	119.5	5.7	17	782	14	908	953	1,080
73	135	" 17	120.5	120.5	7.0	21	865	9	933	954	1,012
74	280	" 29	122.2	121.0	5.0	15	720	13	938	1,074	977
75	213	Oct. 4	119.0	112.5	4.0	16	696	16	875	879	1,114
								5	1,033	3	1,053
								2	1,179	3	1,274
								1	1,300	3	1,218
								1	1,220	3	1,189

meshes per square inch, and fixing a certain percentage of residue Mr. Colson. or coarse particles; but he would ask why any percentage should be allowed. The argument on the part of manufacturers was, he believed, that to grind to such an extent as to reduce the whole of the coarse particles to the requisite degree of fineness would raise the cost of production so much as to be practically prohibitory. The cost would of course be increased, but he doubted its being prohibitory; and were it understood that a specified degree of fineness meant that there should be no residue, the difficulty would soon be overcome. He agreed that the fineness should depend upon the process of grinding, and not simply upon the removal of the coarse particles by sifting, for the reasons given by Mr. Grant; but it was not that the whole bulk of the cement was to be passed back into the mill, and ground and re-ground until every particle of coarse material was reduced to powder, but that a given proportion had to be separated from the general bulk by sifting, raised to the stone and re-ground; the extra value of the cement would, therefore, be represented by the cost of those extra operations. He considered there was no insurmountable difficulty in the matter, and he believed that ultimately this very desirable condition would be complied with, viz., that the whole of the cement supplied should pass the specified sieve, leaving no residue.

With regard to the weight of Portland cement, in former Papers on the subject¹ he had alluded to the fact that the results of his experiments led to the conclusion that the weight, taken alone—that was, without reference to the degree of fineness—was no true indication of its quality; but he was prepared to admit, as pointed out in the first Paper, that with cements ground or screened to the same degree of fineness, the heavier sample would undoubtedly give the best ultimate results. He agreed that no sound conclusions could be arrived at as to the comparative value of different samples of cement with a seven days' test. With regard to the unit of weight, or measure, the bushel was almost universal. He endorsed the opinion expressed by General Scott and Mr. Redgrave, that the foot cube would be more convenient; it was the unit of proportion used generally on works, and would therefore be much more suitable than the bushel as a measure of capacity. Mr. Bernays appeared to doubt the value of fine grinding; but inasmuch as the power of cement to give off a greater strength when combined with sand was increased, beyond all

¹ *Vide Minutes of Proceedings Inst. C.E., vol. xli., p. 125; and vol. liv., p. 264.*

Mr. Colson. doubt, by fine grinding, the utility of it was, he thought, manifest.

With regard to the method of testing the cement with the admixture of sand, this was a point to which he had before alluded, and he was glad to see that Mr. Grant had taken the initiative in the matter; it was undoubtedly the fairer way to test cement, in the interest of both manufacturer and consumer. There were, however, one or two points which might be raised as objections to this method of testing, viz., the possible difficulty of ensuring the same quality of sand being used by both manufacturer and purchaser. Should there be any variation in the quality of the sand, in regard to its being of a coarser or a finer character, angular or rounded grains, the resulting tensile strain would be affected to a great extent; the degree of dampness of the same would also have a marked effect upon the result. Objections such as these would undoubtedly have considerable weight, but could not in any sense be considered insurmountable, although attended with an increased expenditure of money and trouble.

In alluding to the method of mixing concrete, Mr. Bernays advocated the use of an excess of water, on account of the loss in getting the concrete into place. No doubt some advantage was gained in the increased facility with which wet concrete was manipulated, as compared with dry; but, on the other hand, there was great risk—indeed a certainty, of some of the cement being carried off by the excess of water, and thus acting detrimentally upon the mass in a two-fold manner; at the same time, an error could be made in having too little water. It was necessary that there should be sufficient water to act in some measure as a vehicle, by which the matrix was carried into the interstices of the mass. These remarks would also apply to brickwork laid in cement mortar; most engineers knew how difficult it was to get bricklayers to properly fill the joints, particularly with stiff mortar; under such circumstances, a very few units only of the full area of the joint were filled. It was better, therefore, that sufficient water should be used to ensure the whole of the joint being filled—with mortar of a reduced quality, it was true, but by reason of the whole area of the joint being occupied, a greater aggregate strength was obtained.

It had been the habit to value concrete from the point of view that no skilled labour was needed in its preparation; that it was a material of so simple a character that any man who could use a shovel could mix it. Was this correct? He believed that the more skill and thought exercised in the manipulation of con-

crete, the more satisfactory would be the result. As a rule, a great want of attention was displayed in preparing and depositing the mass; it was left too often to the care of the men who had no feeling of interest in the matter, and therefore cared little whether the mass was properly mixed or not; and in specification little more was said than that the shingle or gravel was to bear a given ratio to the cement. Concrete was, after all, but a kind of rubble masonry, the shingle, gravel, or other material taking the place of the larger stones, and the cement and sand the mortar; therefore the strength of the mass would depend mainly upon two conditions, viz., the adhesive power of the material, and the quality of the mortar. Even in Mr. Grant's specification for concrete, no provision was made for ensuring a proper proportion of sand. The better way was, he thought, to provide that the concrete should be composed of 1 part of approved Portland cement, to n parts of clean shingle (or ballast, or other material, as the case might be), and sufficient sand to thoroughly fill the interstices. The quantity of sand required should be determined by experiment from time to time, by placing the clean shingle or other material in a known cubic measure, and filling up with water; the measure of the water, with a percentage added for shrinkage when wetted, to be the proportion of sand to be used. This being determined the specification would read, 1 part of cement to n parts of sand and n' parts of clean shingle, broken stones, &c. This was, in his opinion, one of the most important points to be attended to in the making of concrete, and one to which attention could not be too strongly drawn.

Another point, to which he should like to draw attention, was the proportion usually specified for cement mortar: 2 parts to 1 part appeared to be the proportion generally adopted. His experiments, however, showed that a much stronger mortar than any lime mortar could be made, and used with a much less proportion of cement. A mixture of 4 or 6 parts of sand to 1 part of cement would produce a mortar far superior to anything that could be made with lime. A less proportion of cement than this could be used, but it was not so convenient, being raw or harsh in character, so much so that an addition of lime would be required to render it plastic.

MR. THOMAS DYKE remarked that in the year 1869, being at that time the engineer to the Port and Harbour Commissioners of Hartlepool, he commenced the extension of the breakwater projecting from the Heugh, a headland which protected the entrance

Mr. Dyke.

of the old harbour at Hartlepool. The breakwater several years before had been carried as far as the low-water line and left unfinished, and the exposed end stepped back, with a view to readily add to the work. It was composed of a hearting of concrete blocks formed of shingle and Portland cement faced with stonework, and though much exposed to the sea the concrete blocks showed no signs of damage. It was, therefore, determined to continue the work with concrete blocks alone, though of a larger size; but to provide against the effects of scour caused by the shingle cast up by the waves, and to give a better face to the breakwater, the common concrete composed of shingle and Portland cement was protected by a facing of superior concrete, consisting of Portland cement and whinstone in the proportion of 1 part of the former to 4 parts of the latter. The whinstone was broken in one of Blake's machines, so that the maximum size was $\frac{1}{2}$ inch in diameter, and the fractures were found to be clean, sharp and angular.

The concrete blocks were formed in the usual moulds by filling in layers of concrete about 9 inches deep. The layers of whinstone face concrete were made alternately 9 inches and 18 inches wide, so as to break joint with the ordinary concrete forming the body of the block, and the two materials were kept distinct during the formation of each layer by internal partition-boards, with distance pieces alternately 9 inches and 18 inches in length. Experiments as to the relative degradation of superior concrete formed of like preparations of whinstone, granite and shingle, were made by applying small blocks of each material under the same pressure to the face of a revolving grindstone. The results were greatly in favour of the whinstone. It was found that the whinstone concrete formed a hard smooth face to the breakwater, and that on account of the angular form of the particles of whinstone they became firmly wedged together, leaving small interstices between them to be filled by the cement. Several blocks were broken up under blows from a ram, and no liability to fracture at the junction of the two materials was found.

Mr. Gostling.

Mr. WILLIAM GOSTLING observed that the necessity now generally felt for improving the tests for Portland cement had given rise to much discussion. It was highly desirable that engineers' and architects' specifications should be more uniform. No qualified judge would maintain the proposition that many varieties of specifications were needed to adapt the material to a corresponding variety of uses. In truth, only one quality of cement was required

to produce good concrete, and therefore one specification should be sufficient for all engineering purposes. However, on examining the specifications in use, it was difficult to find two which corresponded in all particulars. The vagueness and the curious variety of divergence which characterised them were remarkable, and it was evident that the subject of cement tests had not yet received that sustained attention from the great body of engineers which it deserved, otherwise greater agreement would prevail. It might not be amiss to exhibit the confusion which existed, by the citation of a number of specifications of recent date, taken at random as those readiest to hand, and which might be fairly accepted as a true representation of the state of the case. Those who might have doubted the utility of proceeding with investigations, having for their object the establishment of greater uniformity, might thus be brought to see the necessity for action. It was difficult to imagine that this state of things could be allowed to continue much longer, displaying as it did a backwardness on the part of those concerned, in comparison with German engineers, who had been so much later in entering the field, and who, from being disciples, now appeared as teachers and examples. With them there was a general consent with regard to tests, which was highly conducive to the interests both of producers and consumers. The evidence of this was furnished by published rules, adopted in common by the Society of Architects of Berlin, the Society of Builders of Berlin, the German Society for the manufacture of bricks, earthenware, lime and cement, and the Society of German Cement Manufacturers. These rules had been translated by the London Portland Cement Company into English, and they demonstrated the possibility of concerted action on this subject, and exhibited the points which the Germans had brought within the scope of their agreement. Their peculiar methods of testing might also serve as a criterion by which to judge of English methods, and they might even, in some respects, commend themselves, on trial, for adoption here. In fact, one specification that had come under his notice was based on the German tests, and although isolated attempts to introduce tests so different from those in general use in this country were to be deprecated, the fact that this specification had been put forth by a very influential body, furnished a striking proof of the importance of immediate action on the part of engineers and architects, for the establishment of an authoritative standard to which their specifications would conform, and which would serve as a guide to the public.

Certain specifications for Portland cement might be thus classi-

Mr. Gostling.

Mr. Gostling. fied in reference to the three tests of fineness, weight, and tensile strain:—

1. *Fineness.*

In 3 specifications, no mention of fineness.

5	„	finely ground.
1	„	very finely ground.
2	„	extremely finely ground.
2	„	residue not to exceed 10 per cent. with sieve of 1,600 meshes per square inch.
1	„	residue not to exceed 20 per cent. with sieve of 2,500 meshes per square inch.
1	„	residue not to exceed 15 per cent. with sieve of 2,500 meshes per square inch.
1	„	residue not to exceed 10 per cent. with sieve of 2,500 meshes per square inch.
1	„	90 per cent. to pass through a sieve having apertures of not more than $\frac{1}{40}$ inch in diameter.
1	„	no residue on passing through a sieve of 50 meshes to lineal inch.
1	„	80 per cent. to pass through sieve 5,800 meshes per square inch.
1	„	85 per cent. to pass through sieve 5,800 meshes per square inch.
1	„	fineness to be satisfactory to inspector; unsatisfactory if tests made from screened cement are stronger than those made from unscreened.

—
21 specifications, with thirteen varieties of test.
—

It was scarcely necessary to point out the inconvenience of requiring fine grinding merely in general terms. Such specifications betrayed an inadequate estimate of the value of fine grinding, and opened a wide field for disputes. Of the other specifications, two indicated the use of sieves of 40 wires per lineal inch, and three required sieves of 50 wires. In using these the percentages varied, and only one specification demanded complete sifting. An important specification, lately issued, assumed either that there was no appreciable difference between screened and unscreened cement if finely ground, or that, if there was a difference, unscreened cement was the stronger, assumptions which were open to question. Then there was an isolated attempt to introduce the use of sieves of 5,800 meshes to the square inch, hitherto unused by the trade in England. All recent investigations in Germany and England demonstrated the importance of fine grinding, and surely it was time that this fact should be recognised, and that a uniform system, reconciling practice and theory, should be established and applied in drawing specifications.

2. *Weight per bushel.*

Mr. Gostling.

In 1 specification not less than 100 lbs. per struck imperial bushel.

1	"	"	110	"	"	"
8	"	"	112	"	"	"
1	"	"	114	"	"	"
4	"	"	115	"	"	"
1	"	"	116	"	"	"
1	"	about	118	"	"	"
1	"	not less than	108	"	nor more than	115 lbs. per imp. bush.
1	"	"	112	"	"	118 " "
2	"	without any reference to weight.				

—
21 specifications, containing ten varieties of tests.

Sixteen of these specifications placed no limit to excess of weight per bushel, merely guarding against undue lightness. One specification demanded a specified weight, and two specifications only adopted the more rational method of confining the weight within definite limits. There was no guiding principle apparent. The fact that the weight should bear a definite relation to the strength and fineness was not recognised, and weight of itself appeared to be deemed an indication of quality. The new specifications of one important public body discarded the test of weight entirely, rightly deciding that fineness of grinding, and strength, were the true tests. Assuredly, if this test was to be retained, some kind of scale, by which the relation between the weight and strength might be determined, should be adopted.

3. *Tensile breaking strain, seven days after gauging.*

In 1 specification not less than 200 lbs. per sq. in., or 450 lbs. per 2¼ ins. section.

1	"	"	250	"	"	562½	"	"
2	"	"	267	"	"	600	"	"
5	"	"	300	"	"	675	"	"
1	"	"	311	"	"	700	"	"
1	"	"	333	"	"	750	"	"
2	"	"	350	"	"	787½	"	"
2	"	"	356	"	"	800	"	"
1	"	"	378	"	"	850	"	"
2	"	"	400	"	"	900	"	"
1	"	"	444	"	"	1,000	"	"
1	"	cement gauged with 3 times its weight of sand, to stand a strain of 140 lbs. per square inch twenty-eight days after making briquettes.						
1	"	cement gauged with 3 parts sand, to bear 150 lbs. per square inch twenty-eight days after gauging, if the cement set neat in less than two hours, and 170 lbs. per square inch if taking more than two hours to set.						

—
21 specifications, embracing thirteen varieties of tests.
—

Mr. Gostling. Thus in these twenty-one specifications there were thirty-seven variations in the tests; and, as a greater number of specifications would doubtless add to these variations, and admit of the three tests being combined differently, it was difficult to estimate the number of the varieties in actual use.

In conclusion, it was earnestly to be desired that this subject would receive consideration by The Institution of Civil Engineers, who might elicit much valuable information, which would serve as a general guide, and would be adopted in all specifications in this country.

Dr. Heintzel. Dr. C. HEINTZEL sent a letter accompanied by an article on the physical properties of Portland cement, which was published in 1878.¹ He called special attention to those tests by means of which any increase of volume that might take place during the hardening of cement could be detected. These he considered sufficient to indicate whether the cement under examination could be used with safety, although they might not afford any insight into the strength.

Mr. Higgin. Mr. G. HIGGIN thought it might interest the members of the Institution to know the result of the employment of concrete in the City Improvement Works of Buenos Ayres. These works, upon which upwards of £2,000,000 sterling had been spent, under the direction, as engineer-in-chief, of Mr. J. F. Bateman, Past-President of the Institution, and of himself as Mr. Bateman's representative, afforded a good example of the use of cement concrete in almost every form that could be devised. No stone was to be obtained in Buenos Ayres; for a radius of 200 miles on the land side not a pebble could be found. At the time of commencing the works, the province produced no bricks fit for employment in such works, and it became necessary to have recourse to concrete. About 11 miles of large subterranean conduits, varying from 12 feet by 14 feet to 7 feet in diameter, had been built, almost entirely in concrete. In addition to this there were 12 miles of intercepting sewers, varying from 7 feet in diameter to 3 feet, and 20 or 30 miles of collecting sewers, egg-shaped, varying from 4 feet wide to 2 feet 6 inches, almost all of the same material. Concrete had also been used in building the workmen's houses; in the roofs of engine-houses, and in the copings of walls, caps of columns, heavy retaining-walls against the river, filters, settling pools, in fact in almost every conceivable way.

¹ "Jahreshefte des naturwissenschaftlichen Vereins für das Fürstenthum Lüneburg," 1878, p. 55.

For all the fine work the mixture used was 1 part of Portland Mr. Higgin. cement to 6 parts of coarse sand. The sand was of an admirable description; it was dredged up from the bed of the La Plata, on the opposite, or Uruguay, side, of the river, a distance across of 30 miles. It was clean and of any required degree of coarseness or fineness. The cement used was English, carefully tested in England, shipped in extra-strong barrels, and carefully tested again when put on the work. Great care was taken in the mixing of the materials, and in their measurement; no guesswork was allowed, but the various quantities were measured off in boxes constructed for the purpose. The materials were turned over three times when dry, and water was then slowly added by a rose-headed hose, or can, until the concrete had just sufficient consistency to retain its form when squeezed in the hand. Though Mr. Bernays seemed to think that an excess of water was no objection, Mr. Higgin was decidedly opposed to this view of the case, and considered an excess of water not only injurious to the quality of the material, but that it also interfered greatly with its proper manipulation. All the concrete used in the underground work was placed *in situ*, with the exception of some places where there was a constant influx of water at the bottom. In such cases the inverts were formed of blocks, cast in boxes overground, the blocks being, as a rule, 3 feet long by 1 foot broad.

For the 12-feet by 14-feet tunnels, a thickness of concrete of 14 inches was used, and it varied from this downwards to 6 inches in the case of the smaller collecting sewers. In the large conduits, the earth having been got out to a template for a length of 12 feet, the lower half of the circle was put in, carefully pounded, swept by rods to the exact form, and smoothed with a kind of float. It was then left for forty-eight hours, or sometimes more, when it was sufficiently hard to allow the men to come in and set the centres. The concrete was then carefully rammed in behind the centres up to within about 1 foot 6 inches of the top. In the case of the large conduits the key was put in in brickwork, as it was found that by this means better facilities were given for the pounding of the concrete. The centres were allowed to be struck forty-eight hours after completion.

In the case of the egg-shaped sewers, drums were made in 6-feet lengths, to the exact section of the lower half of the sewer. The earth having been got out to the proper extent, a mass of concrete was thrown on the floor and punned, and the drums were then fixed to their right lines and levels; the sides were then filled in in thin layers carefully punned with small iron punners up to the

Mr. Higgin.

level of the top of the drum. When the concrete was sufficiently consolidated these drums were removed; straw was laid along the bottom to protect the outside skin, and the centres were set up. There were also drums in 3 and 4 feet lengths; they were put up one by one, the concrete being rammed in from the end and brought up to a face before the succeeding drum was put up. The concrete when finished had the appearance of a grey sandstone; it became exceedingly hard, and when properly made had a fine smooth texture outside. If the concrete was properly mixed, when punned, a slight moisture came to the surface; if too wet, it could not be punned, as the water spurted in the men's faces.

In using concrete for the caps of columns a cast-iron mould was made with the proper mouldings according to drawings. This was fixed up round the top of the pillar and the concrete rammed in to the top of the mould, the bevelled top being afterwards put on by trowel. The sand used for this purpose was rather finer than usual. When the mould was removed, the cap had the appearance of having been cut out of fine freestone. Difficulty was experienced in using concrete in large masses, exposed to the sun, the great variations of temperature making it expand and contract, and show cracks. To avoid this, joints were made by introducing, at proper distances, strips or sheets of thin plate iron. These were withdrawn when the concrete was partially set, and the joint afterwards made with mortar; this plan was found to obviate the difficulty referred to. In the foundation work, and in the large retaining walls, a mixture of 8 to 12 parts to 1 part of cement was used. In these cases the extra quantities of material were usually broken brick, which made an admirable concrete.

Concrete in the proportion of 4 parts of sand to 1 part of cement was also used for making flags, 3 inches thick; for pipes, 12 inches, 18 inches, and 9 inches in diameter, and in various other ways, and gave unvarying satisfaction. He certainly considered it the great building material of the future, especially in countries where other materials were difficult or expensive to obtain.

Mr. Mann.

Mr. I. J. MANN could not agree with the Authors of the first Paper, that the time had arrived for the authorities in this country to interfere in prescribing any absolute rules or methods of testing cement. He believed that there was need of further investigation, and that the subject was far from being exhausted.

The expediency of bringing the time occupied in setting into specified or standard tests seemed doubtful, as cement could be made to set with any required degree of slowness by the simple process of air-slaking. The degree of fineness proposed by the

Authors was, in his opinion, insufficient. Much could be said in Mr. Mann. favour of the German method of testing, after the admixture of what had been termed normal sand; so far, however, as he had observed, when the density and fineness of Portland cements were the same, the strength of the mortar was, *cæteris paribus*, almost invariably governed by the strength of the neat cement. Sand, particularly when fine, might be considered abnormal in one respect, namely, that the surfaces of the grains bore an exceptional ratio to their weight and cubic capacity. Hitherto attention seemed to have been directed to an examination of cohesive rather than adhesive strength; the latter was, however, probably the more important; the "mechanical agency" of the particles also appeared deserving of closer observation.

The requirements of the specification of the cement used at Chatham seemed to be rather more than moderate; the degree of fineness was apparently omitted, and the specified strain was much too low, the actual breaking strain of $773\frac{1}{2}$ lbs., or about 300 lbs. per square inch, did not compare favourably with the general strength of neat cement, which not uncommonly exceeded 500 lbs., and averaged over 450 lbs. per square inch when seven days old. The Author's method of providing quay walls with a facing, or skin of strong concrete, was an admirable arrangement; but with respect to coping and steps, which were generally subject to rough treatment, he should prefer using the granite unbroken, *i.e.*, in the form of ashlar. The remarks of Mr. Bernays relative to the deposition of liquid concrete *in situ* were entitled to attention, being also supported by those of Mr. Grant on the same subject. It must, however, be admitted that increasing knowledge and experience of the material in question, together with improved methods of submerging plastic concrete, seemed to point to the conclusion that the deposition of liquid concrete *in situ* was destined to supersede, to a great extent, the more costly system of blocks. The use of an excess of water in mixing concrete had at present but few advocates, investigation having abundantly shown that in its early age such excess diminished its strength; in many works it was of importance that the gauged cement should acquire strength as rapidly as was consistent with good material, so as to be better able to resist injury.

Although Mr. Grant had treated the subject exhaustively, and had alluded to many points of great interest, yet he had not shown the relation of the weight of loose cement to its tensile strength. The density of cement might possibly be an important

Mr. Mann.

element, but was, of course, a different thing from the weight as usually obtained. He had recently taken the specific gravity of cement supplied by some of the best English manufacturers, and found that it slightly exceeded 3.0; on separating the coarse from the fine by a wire sieve of 2,900 meshes to the square inch, he found the specific gravity of the coarse particles to vary from 3.08 to 3.13, and that of the fine particles from 2.97 to 3.06. In one or two instances the coarse and fine particles of the same cement had the same specific gravity. Applying this test to a sample of inferior cement, its density was found to be 2.80, and that of the fine sifted portion of the same cement only 2.55.

Referring to the article quoted from the "Thonindustrie Zeitung," given in the Appendix to Mr. Grant's Paper, if the experiments were made on cements of very different qualities, the conclusion arrived at was obvious. The tensile strength of the different cements was, however, not given, and in the absence of this information it was hardly possible to form any definite opinion.

Whether the density of cement had any relation to its strength, or otherwise, it appeared tolerably certain that the specific gravity of good English Portland cement, fairly ground, varied between very narrow limits.

Mr. Meyer.

Mr. C. H. MEYER observed that the date at which the term "Portland cement" seemed first to have been used in the specification for its manufacture was interesting; and though Aspdin might not have been the originator of the term, or have made what was now considered true Portland cement, his name should be mentioned, and also that of his son, to both of whom probably some credit was due for its early introduction, and possibly for its invention. It would seem well, while practical men who had to do with Portland cement from its earliest date might be still living, if a short but complete history of its use and early struggles as against rival cements and limes were contributed by some or one of them, for as yet he believed such a record was unwritten, and this should hardly be the case of the best modern cement.

The progressive steps in improving the manufacture of Portland cement, such as those mentioned in the Papers, were satisfactory so far as they went. They were, however, only such as might have been expected as the use of this cement increased, and there still seemed to be a wide field for the introduction of greater certainty in its manufacture, especially in determining the value of, and proportioning the ingredients of, its composition.

One of the most important of these improvements was doubtless

the greater attention given to the subject of properly grinding the Mr. Meyer. cement, and he would urge the necessity, to all who used Portland cement in any quantity, or took any care or pride in getting it good, to see that it was properly ground; for exactly in the degree that it was not so, was the cost of it, as cement, thrown away. He had seen cement, otherwise good, with $\frac{1}{3}$ of its weight useless, inasmuch as it was not ground fine enough to have any value as cement. This was an extreme case, and one not likely to be often met with; but taking good cements as now ordinarily found, there was still much room for improvement in this direction. There might be practical difficulties in more perfect grinding, but they should not be looked upon as insuperable, and it seemed unreasonable that users of Portland cement should receive what was certainly no better than sand at the cost of cement. Particles of hard cement clinker, that would only just pass through a sieve of 1,600 meshes to the square inch, would give no good result as cement. He considered that the general tests for English Portland cement, proposed by the Authors of the first Paper, rather erred in point of leniency than otherwise in all the conditions; and with regard to that of filling the measure from an inclined plane, care would have to be taken that the stream of cement was constant in volume and velocity. He was in favour of testing cement neat, but this simply on account of the difficulty of getting sand of uniform quality; a "standard sand" wanted as definite a specification as the cement itself; it might be of ground or crushed flints, or some other good stone, sifted so as to be of uniform size, and be of various sizes or grades from the same grinding, but each practically uniform. This would have the advantage of being more sharp and angular than any natural sand, and as the quantity required could not be very great, the cost would not necessarily be so.

He wholly disagreed with the idea that it would be safe under any conditions to use cement directly it was made, his whole experience being opposed to such a view. Almost all Portland cement possessed the property of increasing in bulk in an uncertain degree after it had been ground; this increase sometimes being very considerable, on an average perhaps not less than 5 per cent. after delivery from the manufacturers. Some cements, when first made up into briquettes for testing, cracked and went to pieces; but when thoroughly aired they lost that property, and stood a high tensile strain, the briquettes being kept in air or water from twenty-one days to two years or more. An experiment that was made at Portsmouth with cement supposed to be delivered

Mr. Mejer.

thoroughly fit for use, viz., by filling a strong wooden box, 3 feet square internal measurement, with cement, well shaken down to a depth of 2 feet 6 inches, and keeping it a month in a dry store, resulted in the surface of the cement at the end of that time being found $\frac{3}{16}$ inch higher than it was originally put in; and it could not be said that under the conditions mentioned it had been very fully exposed to the action of the atmosphere; it would probably have increased in bulk considerably more had it been laid out upon a floor. All large users of cement must know the effect of storing cement to a considerable depth in comparatively rigid buildings such as of brick; how, even in a short time, they were sure to be rent by the expansion of the cement. Partly for this reason, but much more for other advantages, strongly-framed wooden buildings, covered say with weather boarding and properly roofed, the floor and lining to the height to which the cement was to be laid being of 3-inch planking, formed far the best stores that could in most cases be adopted.

No doubt the investigations of German engineers and others had already led, and would yet lead, to beneficial results; and it was a question whether it was not time that English engineers should also come to some definite and uniform rules and tests; for as long as so many varying tests were in use, no one could exactly say what progress was being made in the improvement of cement.

One objectionable feature was in some cases coming into practice in the use of Portland cement mortar. It was sometimes specified that the mortar should be ground; this with some cement was objectionable on account of the time that elapsed between the wetting of the cement and its use as mortar, though the grinding itself might perhaps be of great advantage. But when, to secure a supply of mortar early in the day, the mortar was ground in the evening or some time the day before, little could be said in its favour.

In the second Paper, it did not appear how far the consideration of the various circumstances which led to the substitution of Portland cement for other limes and cement named in the contract specifications for the extension of Chatham and Portsmouth dock-yards, went on concurrently or otherwise. As stated by Mr. Bernays in the case of Chatham, so also of Portsmouth, no mention had been made in the contract specifications of Portland cement. Roman cement was specified, and this it was in some measure intended should have been supplied to the contractors by the Admiralty, by utilizing convict labour to make it upon the works at Portsmouth. This was at first in some degree done, but on

the whole it was found that neither the quantity nor quality so Mr. Mejer. produced were all that could be wished.

The substitution of Portland for other cement and limes for the Portsmouth works was chiefly brought about by the efforts of the late Mr. Edward Pease Smith, who, from great experience of its good qualities and high value, was able strongly to urge its adoption. Though acting for the contractors he was able to do this without involving them in greater outlay, partly on account of the smaller quantity of it than would have been required for work performed in lias and other limes, and partly on account of the cost of the carriage of lias lime from Warwickshire, from whence it was specified to come. The adoption of Portland cement, however, had undoubtedly been most beneficial in its results upon both works.

Unlike Chatham, concrete at Portsmouth was not used in places where it would be permanently exposed, the original designs for the Portsmouth works being more strictly adhered to. And the proportion of cement used in the concrete at Portsmouth was rather greater than at Chatham, being 1 part of cement to 11 parts of shingle in all ordinary work, though in special cases it was of 1 part to 9 parts, or 1 part to 6 parts respectively, none of so small a proportion as 1 part to 12 parts being used, except in a few cases where it was adopted in filling in behind walls or other works complete in themselves instead of the ordinary earth filling. The means taken at Portsmouth to apportion the cement to the concrete or mortar, were different to those generally adopted; for having in mind the great variation that might occur in actual quantity, when cement was taken by measure according to the manner in which it was put into such measure, it was agreed that all the cement used should be by weight, and with this view careful experiments were made to determine the average weight of the cement supplied. This was found to be 89·2 lbs. per cubic foot nearly, and upon this datum all the cement used upon the work was taken. During the construction of the works no sufficient variation in the average weight occurred to necessitate any reconsideration of this question.

The shingle and sand, previously mixed in proper proportions, was measured by being put into a box composed of loose sides set upon a floor or platform, one side being easily removable, the internal dimensions being 8 feet by 9 feet by 2 feet = 144 cubic feet capacity. The shingle was struck off to a depth of 1 foot 10 inches, and five bags of cement, each containing 2·4 cubic feet, weighing 1 cwt. 3 qrs. 18 lbs., were equably spread on the top. A little

Mr. Meyer.

cement next the removable end of the box was then transferred to the opposite end, to prevent the prism of shingle that fell upon the floor when the end was removed carrying with it too great a proportion of cement. It was then carefully mixed by hand. Concrete, consisting of 1 part cement to 9 parts shingle, was apportioned in the same way, six bags of cement being used with proportionately less shingle. All mortar used for brickwork was made of 1 part of cement to 2 parts of sand, and for setting masonry in some cases in the same proportion, but in more important masonry equal proportions of cement and sand were used, all joints being grouted with neat cement. After the concrete had been mixed on the floor, always as close to the point of deposit as it could conveniently be, it was put into barrows and dropped into its place, the specified fall of 5 feet not being in all cases strictly adhered to; it was then trimmed and well rammed. He here wished to remark, after taking great care to be well informed on the point, that all concrete made with Portland cement should be deposited as soon after it was mixed as possible, and should be at once thoroughly rammed. No fall or drop was equal in efficiency to this, and granting that it was well rammed, the fall or drop might be dispensed with. He agreed with Mr. Bernays in his advocacy of using the concrete sufficiently wet, one advantage being that it more readily took its densest form under the drop or by ramming than if deficient in water. On the other hand such an excess of water as would carry cement away with it should be avoided. He further agreed with Mr. Bernays as to depositing concrete in such structures as walls, &c., in layers of 18 inches; but he would not advocate their being thinner, for however carefully concrete might be put in, it always possessed a tendency to separate more easily into the layers in which it had been deposited than anywhere else. As at Chatham, so also at Portsmouth, care was taken to guard against this possible want of adhesion, by well wetting and sprinkling with cement any surfaces that had become dry or loosened, before adding another layer. Mr. Woodman Hill, who had had great experience in most kinds of high class concrete work, even took the precaution, in any case where it might seem necessary, to make a rough mortar joint or bed before depositing succeeding layers of concrete. His experience was that without such a procedure, or similar precautions, perfect adhesion could not be ensured. When, however, layers of concrete succeeded each other perhaps on the same day, such measures were not necessary and would be wasteful.

He remarked that concrete of 1 part of cement to 11 parts of Mr. Meyer shingle, used at Portsmouth, did not in any case appear unnecessarily rich, indeed he should have preferred an increase of cement. The shingle was of good quality with a fair proportion of sand, but the result in the work was concrete not looking so rich as that produced by Mr. Bernays at Chatham; indeed, in some cases the shingle used by him looked richer without cement than that used at Portsmouth did with it. He must confess to a feeling of great distrust at the idea of employing shingle containing loam for concrete. He should be much interested in the result if Mr. Bernays would experiment with concrete beams, such as had been mentioned in the discussion, made with the shingle he used, and also with similar shingle washed free from its loamy constituents, both with the same proportions of cement. These should be submitted to transverse strains wet and dry, and if the loamy shingle still gave the best results, the conclusion would almost necessarily follow that the loam mixed with the Medway shingle possessed some inherent cementing property. He did not like the principle of making the mass of such important walls as those at Chatham of a comparatively weak concrete simply faced with a better, as he feared that in course of time the facing might separate from the mass. He should prefer in any work for which he was responsible, and where cement was to be had at reasonable cost, to advise the necessary expenditure for making the whole mass (or at any rate the greater part of it), including the face, of the same uniform quality; for there must be at times in all such works, a fluctuation of pressure, and when this acted from behind, the finer facing, when it existed, offered undue resistance in consequence of its being less pervious than the rest, and was then subjected to the greater tendency to be forced off.

Though concrete was so valuable a cheapener of engineering works, it was necessary to give it fair play, and to guard against carrying its use too far; for no method of construction could well be more expensive or disastrous than one in which the first cost was put so low as to involve failure. The quantities of various items for which Portland cement was used at Portsmouth were approximately as under: Thus, for about 350,000 cubic yards of concrete; for about 30,000 cubic rods of brickwork; and for setting about 2,500,000 cubic feet of dressed masonry.

Dr. MICHAËLIS remarked that if the question were raised as to testing cement neat or mixed with sand, and if it were acknowledged that only one of these two methods was permissible, then there was no doubt that the decision must be in favour of the sand

Dr. Michaëlis.

Dr. Michaëlis. mixture. It was only when mixed with sand that one of the most important properties of cement could be appreciated, namely, its power of uniting other substances. This was totally distinct from its strength, and depended chiefly upon fine grinding, which was of primary importance. Fine grinding was the only rational method of utilizing the cement to its fullest capacity. The absolute weight of 1 cubic foot of cement was again dependent upon the grinding, and it must therefore appear hazardous to fix a weight of 85 lbs. avoirdupois per cubic foot as the minimum for cement loosely filled into the measure, as the most satisfactory cements would thus be excluded. The following results were part of a series obtained with a Portland cement of unrivalled quality. This cement weighed, ground in the ordinary way, as bought in the market, about 90 lbs. avoirdupois to the cubic foot. When, however, it was ground extremely fine, as was now done on a large scale in Germany, so that no residue remained upon a sieve with 32,000 meshes per square inch, its weight was only about 70 lbs. per cubic foot. With this finely-ground cement, which would have been excluded by a rule fixing the minimum weight at 85 lbs., the following figures were obtained—with 3 parts of sand to 1 part of cement in two days the strength was 115 lbs. per square inch, in seven days 338 lbs., in twenty-eight days 457 lbs., in one year 539 lbs. With 6 parts of sand the briquette broke at 170 lbs. per square inch in seven days, 215 lbs. in twenty-eight days, and 284 lbs. in one year. If, as Dr. Michaëlis would certainly not advise, any absolute weight per cubic foot should be adopted, then it ought not, in his opinion, to be higher than 75 lbs.

But what was the object of fixing such an absolute weight? It was evidently intended to exclude lightly-burnt cement. The idea that lightly-burnt cement should be rejected was, in Dr. Michaëlis's opinion, an erroneous one, if the present state of cement-making and testing were considered. No Portland cement was more reliable than one which gave good results, even when lightly burnt. Tested neat, lightly-burnt cement must, of course, fall far behind highly burnt; but the inferiority was not nearly so apparent when examined with regard to its power of uniting or cementing sand. Lightly-burnt cement, as was well known, was the first to show symptoms of "flying." If, therefore, a cement showed no signs of "flying" when lightly burnt, and if it possessed considerable strength when mixed with sand, then it would, perhaps, when heavily burnt, give a still higher strength with sand, and this strength would continue to increase for a longer period. Such a cement would undoubtedly be faultless. That light burning could

not be very injurious to Portland cement was best shown by the Dr. Michaëlis. examination of high-class Roman cements, which were burnt at a low temperature, and yet attained a tensile strength of 112 lbs. per square inch in twenty-eight days when mixed with 3 parts of sand. For the detection of faulty cement sufficient and unerring means of detection were at hand; of all of these the proposed minimum weight per cubic foot would be the least adapted to prevent the use of bad cement. The strength of a sand mixture would clearly indicate whether a deficiency in absolute weight were due to spontaneously disintegrated cement.

A high absolute weight would therefore not only be of little use, but would exclude the most valuable cements. The next question was whether it was right to go from one extreme to the other by giving up the test with neat cement, which had so long been customary in England, and by substituting for it the test with sand. From the commencement Dr. Michaëlis had been of opinion that the proper course lay between the two. It was the test with neat cement alone that indicated what proportion of water was the most favourable for the particular cement under examination. No idea could be more erroneous than that the less the water used the stronger would be the cement. Cement could be spoilt by a deficiency of water as easily as by an excess. While one cement might give the highest results with 18 per cent. (by weight) of water, and was totally destroyed by adding only 17 or 16 per cent. of water; another by no means quick-setting cement might be completely spoilt by adding 22 per cent. of water, because it required 24 per cent. of water to attain a high degree of strength.

It was a mistake to think that the test made with sand, according to the German standard rules, gave more regular and uniform results than briquettes made in the same way with neat cement. A method of carrying out the latter test could quite as easily be prescribed as for the sand mixtures. He would recommend the retention of the test with neat cement. He now, more than ever, advocated the sentence placed at the head of his work (1876), which served as the basis of the standard rules existing on the continent. "Cement should be bought by weight and judged according to its strength, taken in conjunction with the fineness of grinding, as may be done by testing the strength of neat cement and of a mortar of 1 part, by weight, of cement with 3 parts, by weight, of sand." The only alteration the writer would now make would be to prefer a mortar of 1 part cement with 5 parts of sand, more especially if the sand test alone should be adopted. The

Dr. Michaëlis. cementitious value and trustworthiness of cement were more evident with 1 to 5 than with 1 to 3. Among more than 80,000 experiments it never occurred that good results were obtained in seven or twenty-eight days in any case where the cement had a tendency to "blow." This might, however, happen, with the proportion 1 to 3, deterioration taking place subsequently. No cement with any tendency to "blow," however slight, would give a favourable result if tested in seven days.

If the cement showed a high strength neat, it proved that the sample was highly burnt; if the mixture with 5 parts of sand gave high results, it indicated that the cement was faultless and finely ground.

Accurate comparative tests could only be made with cements ground in the same way, and the cement should be reduced by means of three sieves to a uniform grain. One of these sieves should have 32,000 meshes per square inch, the next 14,400 meshes per square inch, and the coarsest 5,800 meshes per square inch. The cement was first passed through the finest sieve, then through the second, and finally through the coarsest sieve. Sixty parts of the powder passing through the 32,000-mesh sieve were well mixed with 20 parts each of the powder passing through the sieves of 14,400 and 5,800 meshes. A preliminary experiment decided what proportion of water was most suitable for the cement under examination when mixed upon a non-absorbent surface. For each part of sand an additional 7 per cent. of water was added. A cement requiring 20 parts of water when gauged neat would therefore, when mixed with 5 parts of sand, take $20 + (5 \times 7) = 55$ parts of water per 600 parts, by weight, of the dry materials, or 9 parts, by weight, of water to 100 parts of the dry mixture. In respect of the time allowed for hardening, the Austrian rules were to be preferred to those of the Germans. The test after seven and twenty-eight days was undoubtedly of more practical value than the twenty-eight-day test alone. There could be no doubt that the results of a test must be the more reliable the longer the period of observation, and a ninety-day test would in its turn be preferable; still more so a test extending over a year or longer. Even the twenty-eight-day test, however, clashed with the practical requirements of the case. A point which had been completely lost sight of in abandoning the seven-day test was its bearing upon one of the most valuable properties of cement, namely, its hardening energy (Erhärtungs-Energie). In this respect Portland cements might vary considerably, especially on the continent, where Portland cement was made from raw materials differing widely from each other. Silica,

alumina, iron, and magnesia, played highly important parts in this Dr. Michaëlis. process, on which subject Dr. Michaëlis now believed himself to be perfectly clear. In England the character of Portland cement varied but little; nearly everywhere there was the same chalk, the same clay. On the continent no better cements were produced than when the raw materials used closely resembled those of the English manufactories. This initial hardening until recently had but little value attached to it, which was in favour of those manufacturers who could never produce a cement of first-rate quality because their raw materials would not permit it, whose cement was therefore for this reason much inferior.

He need only refer to the fact that all cements of first-rate quality were especially prominent in this respect. The value of this setting energy, which must be of great importance in practice, had been ignored to such a point, that quite recently Mr. Henry Faija could suggest that a normal cement should possess, in twenty-eight days, a strength 25 per cent. higher than in seven days. No one can doubt that, all other circumstances being equal, he would attach more value to a cement which attained 90 per cent. of its final strength in seven days than to one which only possessed 50 per cent. of the strength which it would ultimately reach. The latter could easily show 25 per cent. more strength in twenty-eight days, which would be an impossibility with the former. General Scott suggested that cement should leave no residue upon a sieve with $40 \times 40 = 1,600$ meshes per square inch. On this he would observe that if the cement which had passed through such a sieve were further sifted through a sieve of 5,800 meshes (900 per square centimètre), the residue upon the latter would be in conformity with General Scott's stipulation, and yet be absolutely valueless as a cementitious agent.

In Germany, in consequence of his own efforts, cement was being made of which an amount of 10 to 3 per cent. was rejected with a sieve of 32,000 meshes per square inch; in some cases leaving hardly any residue. In this country, where cement has been too cheap to treat it rationally, such a sieve generally left 50 per cent. residue. Might it not be preferable to prescribe a sieve with at least 14,400 meshes per square inch, and a residue upon it of not more than 33 per cent. He had had the honour to express his views and to co-operate in framing the standard rules in Austria, Sweden, and Russia. With regard to the experiments of Messrs. Dyckerhoff, he did not think that the conclusions drawn from them could be applied to German cements in general.

Dr. Michaëlis submitted various printed documents, on the valu-

Dr. Michaëlis. ation of cement;¹ two articles by himself on the same subject;² a copy of the German standard rules for testing Portland cement,³ and of the rules adopted in 1878 by the Prussian Ministry of Commerce and Public Works;⁴ an article on the testing of cement;⁵ suggestions on the testing of Portland cement by several German manufacturers;⁶ description of the apparatus sold by Dr. Michaëlis;⁷ copy of the rules adopted in 1878 by the Austrian Association of Engineers and Architects;⁸ and an article on hydraulic mortars.⁹

Mr. Porter. Mr. WILLIAM PORTER considered the most important point in connection with the subject to be that which related to the breaking tensile strain of Portland cement, considered as a standard of quality. About sixteen years ago the standard of strength required was a tensile strain of from 400 to 500 lbs. on a test-block having a sectional area of $2\frac{1}{4}$ square inches when seven days old. This standard had from time to time been increased, and there were a few cases where it had been placed at the high figure of 900 lbs. upon the same sectional area, and with the time remaining as before. In other cases engineers had advanced with more caution, being satisfied with a less tensile strain. Mr. Bernays, who had an intimate knowledge of the use of Portland cement, specified that test-blocks of the usual sectional area of $2\frac{1}{4}$ square inches should at seven days bear a weight of 650 lbs., and Sir John Coode, who had great experience in the use of Portland cement, required the test-blocks to bear a weight of 750 lbs. upon a like sectional area and at a like age. The following question thus arose: Had the high test of 900 lbs. above named been

¹ Zur Beurtheilung des Cementes. Von Dr. W. Michaëlis. Berlin 1876.

² Zur Werthstellung des Zements. Von Dr. W. Michaëlis. Excerpt 'Deutsche Bauzeitung,' 1876, Nos. 23 and 101.

³ Normen für die einheitliche Lieferung und Prüfung von Portland-Zement. Nach den Beschlüssen des Architekten Vereins zu Berlin, etc. etc. Berlin 1877.

⁴ Normen für die einheitliche Lieferung und Prüfung von Portland-Zement, aufgestellt von dem königl. preuss. Ministerium für Handel, Gewerbe und öffentliche Arbeiten, mittels Erlass vom 10. November 1878.

⁵ Die Prüfung des Cementes. Von Dr. W. Michaëlis. Excerpt 'Baugewerks-Zeitung,' 1878.

⁶ Vorlage zu Beschlüssen für einheitliche Lieferung und Prüfung von Portland-Cement.

⁷ Apparate zur Ermittlung der Zug- und Druck-Festigkeit von Baumaterialien insbesondere der Mörtel und Cemente, &c. Von Dr. W. Michaëlis. Berlin, 1878.

⁸ Bestimmungen für die einheitliche Lieferung und Prüfung von Portland-Cement. Wien, 1878.

⁹ Zur Kenntniss der hydraulischen Mörtel. Von Dr. W. Michaëlis. Excerpt Deutsche Töpfer- und Ziegler-Zeitung, 15. May 1880.

adopted without sufficient justification? It was stated by Mr. Grant Mr. Porter. that great improvement had been made in the manufacture of cement of late years, and that still greater was certain to be effected. This was true only if the fact that a much higher tensile strain had been obtained was considered evidence that a better cement had been produced. Experience led him to say that there was no conclusive evidence of such being the case. The higher tensile strain, obtained to-day as compared with that of past years, as Mr. Grant admitted, was due in a measure to the improved mode of filling the moulds, and to the improved appliances with which the cement test-blocks were broken. Then, he asked, to what was the balance of improvement due? The only possible answer (excepting fine grinding, which was of questionable value beyond a certain point,) was that an extra and possibly undue quantity of chalk or lime had been used in the manufacture of the cement; and it was against this latter point that he desired to protest, as being conducive, not to the improvement of the cement, but to its destruction. The use of chalk or lime in undue quantities, that was in excess of that which the clay could neutralise, was certain, sooner or later, to be productive of the worst results, with which results every manufacturer of cement was fully acquainted. He might add, that if an overchalked cement was not burnt hard, that was to a heavy weight, the results referred to would in all probability appear at an early date. If, on the other hand, the cement was burnt to a heavy weight, such results would show at a later, and probably a much later, date. With neat cement the results would probably appear in one of the following forms. It might be what was called "dust," showing that disintegration had set in, the corners most exposed falling away first, and at last the whole mass being reduced to a powder. Or cracks might be formed on the surface, and become visible at an early period, or they might exist for a long period, and be made visible only by wetting the surface of the cement. Or, again, the surface might become pitted, portions of the surface being thrown off until the whole mass had fallen to pieces; but this latter defect, he might add, might in some cases be ascribed to the cement containing small pieces of lime not properly amalgamated with the clay, and need not necessarily be caused by an undue quantity of chalk or lime having been used in the manufacture of the cement.

It might, he thought, be stated as a fact, that when engineers specified a high standard of strength, such as that of 900 lbs. upon a sectional area of $2\frac{1}{4}$ square inches at seven days, there was but one known course to adopt, in order to bring the cement up to the

Mr. Porter.

required standard, and that was to increase the quantity of chalk or lime used in the manufacture in conjunction with extra-hard burning, so as to produce a heavy cement. It must be borne in mind that as there was often so much difference in the results of the testing of similar cements when done by different men, and under different circumstances, as regarded the nature of the appliances with which the tests were made and broken, that the required test, were it great or little, must be made of a maximum strength, much greater than was required by the specification. The result of this was that a still greater quantity of chalk had to be used, and a quantity which, he believed, approached nearer the point of danger than was advisable.

It was stated in the Paper by Major-General Scott and Mr. Redgrave, that: "Cement mixtures, on the other hand, deficient in clay, and known as 'underclayed,' will stand the highest temperature in the kiln during the firing. When well burned they are extremely hard and difficult to grind; they produce, however, a heavy, dense Portland of a treacherous description, one which, unless it has been properly 'purged,' as it is termed, or exposed in thin layers to the atmosphere, in order to air-slake the particles in which the lime is in excess, is liable to 'blow,' or swell in the work." With this he agreed, excepting that he did not think any cement "underclayed" so as to "blow or swell in the work" could be rendered so that it would not be likely to blow and swell by any reasonable amount of air-slaking, and especially if such cement had been hard burnt; in fact if such cement could be so purged it would become dead and almost useless.

It had been asserted by Mr. Grant that: "The strength of cement depends, in great measure, upon the right proportion between the chief constituents being observed in the manufacture." To this he would object that it could only be true when considered as having reference to the strength of cement at a certain period after having been gauged, because if a moderately overchalked and hard-burnt cement was gauged neat, it would in all probability bear a considerable tensile strain at an early period, but would and must eventually fall to pieces. The truth would, he thought, be better expressed by using the words "ultimate strength."

In conclusion, although he thought the breaking strain of Portland cement would be still further raised by improved methods of testing, and by the utmost care in its manufacture being constantly observed, yet he was far from alone in thinking that it was most desirable to act with the greatest caution in the matter of raising

the standard of strength, otherwise it might be found that the Mr. Porter. high tensile strain required had been productive of a result the opposite of that contemplated by engineers and manufacturers.

Mr. W. F. RED remarked that allusion had been made to the Mr. W. Reid. failure of Hoffmann's ring kiln for burning cement in this country. Mr. White had given one reason why it had not met with success in practice; another reason was the difficulty experienced in regulating the draught. In Germany, where this form of kiln was successfully used, the raw mixture was moulded into bricks previous to burning. These bricks could be arranged in the chambers with great regularity, leaving the necessary interstices for the passage of air and fuel. With English manufacturers the lumps of dried slurry were so irregular in shape that it was extremely difficult to arrange them in the kiln in such a manner as not to interfere with the draught. The extra cost of moulding the raw mixture into bricks would be greater in this country than the economy in fuel effected by this form of kiln. General Scott and Mr. Redgrave suggested stamping the dry powder of the raw materials under great pressure, and burning the bricks or slabs thus obtained. He tried this experiment on a large scale several years ago, but the results obtained were not encouraging. The bricks did not possess sufficient cohesion; they would not bear handling, and "dusted" so much in the kiln that the draught was stopped. The silica and alumina were added either in the shape of powdered shale or of slag sand; the carbonate of lime was pulverised limestone. Under the pressure employed, the powdered shale alone became hard and compact; but with the addition of 70 per cent. of carbonate of lime the particles would not bind. The mixture of comminuted slag and limestone could not be moulded into a brick under any pressure. One point of great importance in the manufacture of cement had not been alluded to in either of the Papers, namely, the testing of the raw mixture as soon as made. The uniformity and reliability of German cement were in a great measure due to the care with which the composition of the slip was checked. The test used was a chemical one, and occupied about fifteen minutes; any error in the proportions of the ingredients could therefore be corrected at once. In some of the German manufactories the slip was thus roughly analysed every hour, so that the risk of loss from carelessness on the part of the workmen was reduced to a minimum. Most British manufacturers still employed the old method of sampling by drying a portion of the slip, burning and grinding it, and then mixing it with water in the ordinary way. At least

Mr. W. Reid. twenty-four hours must elapse before even an approximate idea of the composition of the raw mixture could be obtained in this way; in the meantime the whole day's washing or mixing might be faulty. He had found the chemical test of the utmost value in dealing with materials of varying composition, or which had never previously been used for making cement. With the aid of the new machinery and methods described by Major-General Scott and Mr. Redgrave, engineers could now in many cases make the cement required for works abroad cheaper on the spot than the price it could be exported at from England. Few localities were devoid of the materials for producing a good cement, and in some instances the saving effected in freight would be greater than the cost of constructing the manufactory. One great advantage of having the cement manufactured on the spot was that the quality was completely under control, and could be adapted to the purpose required, while there was no risk of deterioration during transport.

The Authors of the first Paper suggested that a minimum weight per cubic foot should be fixed. Such a coarse sieve as one of 1,600 meshes per square inch would allow a large portion of inert particles to pass, and the adoption of a minimum weight would, as Mr. F. J. Bramwell remarked in 1865, be simply offering a premium to coarse grinding within the limits fixed by the sieve. The present knowledge of the physical properties of cement indicated that the weight of cement had but little influence on its strength when mixed with sand. Numerous experiments had proved that there was no connection between the specific gravity of cement and its tensile strength, and as the absolute weight of a fine powder must depend upon its specific gravity, the adoption of a fixed weight per bushel might be misleading. Major-General Scott and Mr. Redgrave had given the strength specified by the German standard rules as 113·8 lbs. per square inch. This was the strength originally adopted in 1877, but in the beginning of 1878 the minimum was increased to 142·2 lbs. per square inch for a mixture of 1 part of cement to 3 parts of sand. The Austrian rules prescribed a still higher strength, namely, 170·7 lbs. per square inch. Many of the German manufacturers now guaranteed both greater fineness and higher strength than those fixed by their standard rules. These rules were originally framed by the manufacturers themselves, and had subsequently been adopted by engineers and architects throughout Germany. When first proposed, they were accepted by twenty of the twenty-five cement manufacturers of Germany, the five opponents including one of the firms mentioned by Mr. Grawitz and that firm which he represented. This minority,

supported by Dr. Michaëlis, and strong in convictions if not in Mr. W. Reid. numbers, had since waged an unceasing warfare against the standard rules in Germany, and even carried their opposition into this country by taking exception to the results communicated to Mr. Grant by Messrs. Dyckerhoff. These latter gentlemen had done much to extend the knowledge of cement, and the results of their experiments had been accepted, not only by the great majority of German cement manufacturers, but also by the engineers and architects of that country.

Herr STUHR sent a description and drawing of his cement testing apparatus, which had also been used for testing leather, paper and cotton. The briquettes had a breaking section of 5 square centi-

Fig. 1.

mètres, and were fixed in the clips K K, Fig. 1. One of these clips was hinged to the bed-plate of the apparatus; the other was

Herr Studt.

joined to B. The adjusting screw S raised or lowered B as required. The tension to which the briquette was subjected was measured by the point of the adjusting screw compressing glycerine in a vessel. The pressure communicated to the liquid was registered on a gauge indicating the number of kilogrammes per square centimètre of the area broken. The dial of the pressure-gauge was furnished with a maximum pointer, which should be brought back to zero after each experiment. The apparatus was said to work accurately, extensive series of experiments having been conducted with it.¹

Major-General
Scott.

Major-General SCOTT remarked that Mr. W. Porter had expressed a doubt whether cement so underclayed as to merit the designation of being "treacherous" when used fresh, could be rendered absolutely safe by exposure to the air. On this point General Scott was certain that it was possible, with a substance containing enough clay to merit the designation of Portland cement, to destroy all the elements of danger, as stated in the Paper. In fact he had made experiments with most satisfactory results in exposing Portland cement of the above character to the action of steam, which rapidly eliminated all these sources of danger without appreciably deadening the cement. He considered that the remarks of Dr. Michaëlis were entitled to the utmost respect, but he could scarcely follow him in placing the weight of the cubic foot of cement so low as 75 lbs., a weight reached by many of the native hydraulic limes. Whatever might be the degree of fineness in the grinding, he trusted that a standard would be fixed which would enforce the adoption of some mesh leaving no residue. A percentage of residue of coarse particles merely implied a percentage of valueless matter, and he thought the German regulations were defective in this respect. With reference to the double test advocated by Dr. Michaëlis, *i.e.*, neat and with sand, he saw no objection to it, but would remark that too much weight was placed on quick setting by Dr. Michaëlis, and too little weight on the general superiority of heavy cements over light ones; and that it would be quite possible, with a lightly burned cement, to attain to a rapid set without that great degree of ultimate hardness which Dr. Michaëlis believed must follow rapidity of set.

Mr. Grant.

Mr. GRANT, in reply to the discussion and correspondence, wished to state that his Paper had been written chiefly with the view of drawing attention to certain important points affecting the quality of Portland cement, and as a contribution towards the

¹ "Glaser's Annalen für Gewerbe und Bauwesen." No. 76. 1879.

adoption of a more uniform and accurate mode of testing it; and Mr. Grant. though the time which it was possible to devote to the discussion was limited, yet in the course of it, and in the written contributions which had been received, much valuable information had been elicited.

The merits of different modes of dealing with and drying the "slip," and afterwards burning it, were, both as questions of efficiency and economy, very valuable, but chiefly to those engaged in the manufacture. He should have liked to have heard more on the question of fine grinding. For twenty years or longer it had been stipulated that "cement should be finely ground." But the importance of this feature had been clearly demonstrated by the labour and experiments of Dr. Michaëlis, the Messrs. Dyckerhoff, and many other investigators in Germany, and by Mr. Colson, Mr. Mann, and others in England. Perhaps nothing had tended so much to make this, as a practical question, clear to all persons interested in the subject as the adoption in Germany, Austria, and other countries, of the sand-with-cement test, by which alone the cementitious value of cement could be ascertained. By innumerable tests and experiments made by various persons, it had been found that cement manufactured of proper materials, rightly proportioned and well burnt, but coarsely ground, might give the highest results when tested neat, and yet, when mixed with sand, not be one-half of the strength of similar cement more finely ground. The question then was, to what degree of fineness could this be economically carried out? To this the most satisfactory answer would be found in the experience of those manufacturers who had adopted this system of fine grinding. Unfortunately there was not much of this to appeal to in England, but it had been possible for a year or two past to get cement manufactured here that would pass the German standard, and be even so fine as to leave only 10 per cent. on a sieve of 5,806 meshes to the square inch. This latter degree of fineness was now very general with the larger manufacturers in Germany.

After much discussion, the Committee of the German Association at Berlin, in January and February 1877, adopted a sieve of 900 meshes to the square centimètre, equal to 5,806 per square inch, and allowed a residue of 25 per cent. Next year this was reduced to 20 per cent., and the Austrian Association of Engineers and Architects had since adopted the same standard of fineness.

In his communication, Dr. Michaëlis suggested a finer sieve (14,400 meshes to the square inch), with a larger residue of 33 per cent., and stated that in Germany cement was being made which rejected

Mr. Grant.

only from 10 per cent. to 3 per cent., with a sieve of 32,000 meshes per square inch. This degree of fineness must be quite exceptional. The most finely-ground cement which Mr. Grant had ever seen, or had had an opportunity of testing, was a cask which, by the kindness of Dr. Michaëlis, had been sent to him from a manufactory near Hamburg. This, on the sieve of 32,000 meshes to the square inch, left 25 per cent.; on the sieve of 5,806, 10 per cent.; and on that of 2,580 meshes to the square inch, nothing. The "Stern" Company in the north, Messrs. Dyckerhoff in the south of Germany, and many other makers, guaranteed that the cement should not leave more than 10 per cent. on the standard sieve of 900 square centimètres; and though cement could not be too fine, it was difficult to see the practical advantage of using, for testing purposes, a finer sieve with a larger residue. At all events, in this country it would probably take some time for manufacturers to work up to this standard. That which was suggested by the Authors of the first Paper, viz., that the whole of the cement should pass through a sieve of 1,600 meshes to the square inch, was much too coarse, as was pointed out by Herr Grawitz, Dr. Michaëlis, and others, and was proved by various Tables in the Appendix. It appeared that only 75 per cent. by weight of the cement used by Mr. Bernays passed through a sieve of 50 meshes to the lineal inch. The Tables in the Appendix, more particularly the latter part of Table XLVII., proved that the 25 per cent. residue left on such a sieve was utterly worthless, and that the concrete of Mr. Bernays, nominally of 1 to 12, was in reality only 0.75 to 12, or 1 to 16.

Though extremely fine grinding offered a strong temptation to low burning, so as to make grinding easier, there could be no doubt that, however good in every other respect cement might be, it was only when finely ground that its cementitious strength was developed, that it did this at an earlier period, and with greater safety. Briquettes made entirely of the "core," or coarser particles left on a sieve of 2,580, and much of that which lay between this and a sieve of 5,806 to the square inch, would hardly bind at all. If this core was substituted for sand of equal fineness, and mixed, for instance, with a third of cement, the result was not much higher than if sand were used. If, as shown in the latter part of Table XLVII., the 5 per cent. to 15 per cent. of residue on a sieve of 5,806 meshes per square inch was left out entirely, and only the 85 per cent. or 95 per cent. of finer cement mixed with the full quantity of sand, the strength was not only as great as when the coarser part was left in, but greater. This seemed utterly incredible until the experiment had been repeated many times, with dif-

ferent cements and by different operators, taking every precaution Mr. Grant. that the conditions were alike. From this it might be inferred that coarser cement than would pass through the sieve of 2,580 to the square inch was at best no better than sand, and that when it contained free lime it was a source of weakness, if not of danger. Repeated experiments had also shown that if the coarsely-ground part of good, well-burnt cement was well pulverised, it made the strongest of all. These facts showed clearly that the additional cost of grinding fine, estimated by various makers at from 2s. to 3s. 6d. a ton, or say 10 per cent. of its price, would be amply repaid by its strength being doubled, and by its greater safety.

This additional cost, with probably a considerable premium, would be paid when the importance of fine grinding was recognised by engineers and manufacturers; but it was not likely that the suggestion of Herr Grawitz would ever be adopted, that the price of Portland cement should be estimated by its apparent strength, at or near the time of delivery, as if it could be tested like iron or steel. If, at an additional cost of 10 per cent., the cementitious strength when mixed with sand or gravel could be doubled, it was not likely that 100 per cent. additional price would be obtainable. This, however, in any country in which trade was free, might safely be left to settle itself. With all the improvements that had been made in testing cement, it was not now, and probably never would be, possible within a few weeks to test its eventual or ultimate strength with the same degree of precise accuracy that was possible in the case of any finished article requiring no manipulation. As this had been already referred to in some detail, it was unnecessary to say more than that, apart from all other influences, the acquired dexterity of an experienced manipulator would sensibly affect the results. Thus in testing cement neat, if a shallow mould was used, and shaken or tapped whilst the surplus water was being absorbed, the briquettes might be made much denser than by any other means, and give higher results. It would, therefore, be necessary, if this mode were adopted, to make allowance for it. Other means, such as artificially prolonging the time of setting, and having the same effect as storing the cement, added to its density and apparent strength at least for a time. Cements which were slow-setting by nature, or were made slow artificially, and which were also ground extremely fine, showed to great advantage what was called by Dr. Michaëlis their "hardening energy" at the end of seven days, but did not increase so much in strength afterwards. This was confirmed by the strength of No. 14 and several other cements in

Mr. Grant.

Appendix XLVII., at 4, 13, and 26 weeks. Whilst a quick-setting cement was often after twenty-eight days double the strength it showed at seven days, a slow-setting would show only 50 per cent. more. Above all, it would be practically most difficult to determine the time after which it would be fair to compare the ultimate strength of cements of dissimilar character.

One of the benefits which had resulted from the adoption of the mode of testing cement with a mixture of sand was that it had brought out prominently the importance of paying attention to the quality of sand, its mineral character, its coarseness or fineness, and its freedom from extraneous matter.

From the upper part of the Rhine an exceedingly good sand was obtained. The standard sand approved by the German Association was to be had in Berlin, and probably other places, at 4 marks for 50 kilogrammes, or about 4s. per cwt. That sands varied much had been referred to by Mr. Fajja and others. Mr. Grant had recently met with two sands which, though both clean, sifted through the same sieves, and not much unlike each other even under the microscope, gave results that differed by 50 per cent. From this it was clearly as important to test the quality of the sand or gravel used with cement as it was to test the cement itself, and that for testing purposes a sand of uniform character should be used as a standard with which to compare that used upon the works.

With exceptionally thick dock walls, like those at Chatham, the somewhat loamy character of the gravel might not be perceptible; but for thin work, as in sewers, where concrete was used as a substitute for, or in combination with, brickwork, the gravel and sand could not be too clean. Where the proportion of sand in gravel was frequently changing, experience had generally to supply the place of measured proportions, which, however, were useful as checks.

As to the tensile strength of cement, and the mode of testing it, either with neat cement or with cement and sand, by the German rules the neat test at seven days was only used tentatively for controlling purposes; the test with 3 parts of sand after twenty-eight days being the most important. As already stated, this was at first, in February 1877, fixed at 8 kilogrammes per square centimètre. In 1878-9 it was raised to 10 kilogrammes per square centimètre, or 142·23 lbs. per square inch. The Society of Austrian Engineers and Architects, in December 1878, adopted a standard of 8 kilogrammes per square centimètre at seven days and 12 kilogrammes at twenty-eight days respectively, = 113·78 and 170·68 lbs. per square inch. Their seven-days test with sand

was thus apparently the same as the twenty-eight-days test originally agreed upon at Berlin in February 1877, except that by the Austrian rules the average of the six highest out of ten was taken. The standard sand, instead of 60 and 120 per square centimètre = 387 and 774 per square inch as in Germany, was 64 and 144 square centimètres = 413 and 929 per square inch, or almost exactly 20 and 30 to the lineal inch.

Messrs. Dyckerhoff said that the testing of cement, since the introduction of the standard rules in 1877, as well as their own investigations of the influence of the time of setting, on the strength of cement-lime mortars, on the use of slow- and quick-setting cements, on the making of concrete, &c., had been published in the "Proceedings of the Association of German Cement Manufacturers." As regarded the testing of cement, they considered the method prescribed by the German standard rules as the most suitable at present for the valuation of cement, provided the time of setting was also taken into consideration. They guaranteed a strength of 20 kilogrammes for their slowest setting cement; and they voted for a higher minimum strength than that which was subsequently fixed. In 1878 they proposed to the Commission named by the Prussian Minister of Commerce to report on the standard rules, a classification of cement by the time of setting; according to which a strength of 10 kilogrammes should be the minimum for quick-setting cements, 12 kilogrammes for an average time of setting, and 14 kilogrammes for the slowest cements. At present their cement was made of from 12 to 20 and more kilogrammes, according to the time of setting, which varied from thirty minutes to ten hours. It was therefore an error to suppose that the adherents of the rules could not manufacture high-class Portland cements because their raw materials did not permit it. In reply to the remark of Dr. Michaëlis, that the conclusions which had been drawn from their experiments could not be applied to the German cements in general, it might be remarked that the experiments were made with different kinds of cements, among which were the best German, English, and French brands. As, therefore, cements made from very different raw materials were used in the experiments, they were of opinion that the results were applicable, not only to German cements, but to Portland cement in general.

At their meeting in February 1879, the German Association came to a resolution that as "the time of setting" had much influence on the tensile strength, the one should be stated in connection with the other.

Mr. Grant.

High as the standards of strength adopted by the German and Austrian Associations might appear to English manufacturers, the principal manufacturers of Germany, of whom Herr Grawitz's firm in the north, and Messrs. Dyckerhoff's in the south, might be cited as examples, publicly guaranteed a strength for slow-setting cement double that of the standard rules, viz., 20 kilogrammes per square centimètre, or 284·46 lbs. per square inch, with 3 parts of sand to 1 part of cement, at twenty-eight days. Thus it was evident that, although the materials from which their cements were made varied as much as they did in England, the results were as high in the one case as in the other.

In testing the tensile strength of Portland cement, it was pretty generally acknowledged that its cementitious strength could best be ascertained with a mixture of sand of a given degree of fineness, and in a proportion fixed by the German and Austrian Association at 3 to 1. Dr. Michaëlis, in his communication, recommended that the proportion should be 5 to 1, which might or might not be better, but would involve a corresponding alteration in the breaking weight, and would require the most careful manipulation of an expert to ensure uniform results. He also recommended the retention of the neat test at seven days as obligatory, and stated that if the cement showed a high strength neat it proved that the sample was highly burnt. He, however, deprecated the rejection of lightly-burnt cement, and stated that "no Portland cement was more reliable than one which gave good results, even when lightly burnt," though "when heavily burnt it would give a still higher strength with sand, and this strength would continue to increase for a long period." Such a cement, he acknowledged, "would undoubtedly be faultless."

It was agreed that the test with sand was the most important. This was proved beyond doubt by several of the Tables in the Appendix, which showed that the test of neat cement alone would lead to great errors, reduced no doubt, but not eliminated, by coupling with it the test of fineness. Still the neat test had its uses, and he had always retained it, though he no longer depended upon it.

To meet the difficulty, mentioned by Mr. White and others, of giving the time and space required for twenty-eight-day tests, one at seven days with 3 parts of sand, like that prescribed in the 6th of the Austrian rules, might be adopted, though it would not be nearly so trustworthy as the former. The strength required was, as already stated, 8 kilogrammes per square centimètre, equal to 113·78 lbs. per square inch. This, with that for fineness, might be adopted in cases where it was impossible to wait

longer than a week; but in no case should the test with sand Mr. Grant. be omitted, nor that at seven days be preferred to twenty-eight days, wherever possible to wait the longer time. Reference had been made by Herr Grawitz to his having specified so low a test as 170 lbs. per square inch for 3 parts of standard sand with 1 part of cement after twenty-eight days. This, however, was as high as the Austrian standard (practically higher, as it was the average of ten, not of the six highest). His reason for not going higher was, that he had found he could make sure of getting cement of this strength in England; but if a much higher test had been specified, it might have been necessary to import the cement at an additional cost for freight and other charges, of from 33 to 50 per cent. It was as cheap, therefore, to use a greater quantity of cement at a less cost. There could be no doubt that the manufacturers of this country would produce cement of as high quality in every respect as any made elsewhere as soon as there was a greater demand for it.

At present manufacturers of cement objected that the market price was ruled by the quality ordinarily in demand, and that it did not pay to add to their grinding power merely to supply an occasional order. The cement used by architects for plastering and for ordinary buildings was not generally so strong as that required for engineering works. Colour was for plasterers of as much importance as strength. It was desirable, however, that some points should be agreed upon, if only tentatively. No doubt there was yet much to be learnt about cement. If, however, the cement manufacturers of this country were, like those of Germany, to take the initiative and agree upon certain rules, it would be greatly to the advantage not only of themselves, but of those who use their product. These rules need be neither numerous nor complicated, but they should be subject to revision and improvement from time to time. At their annual meetings the German manufacturers, about five-sixths of whom belonged to the Association, discussed suggested improvements, and the results had been highly beneficial to all concerned. Most of those in a large way of business went much above their normal standards, and the character of their cement not only secured their home market, but an increasing export trade. The Association wisely declined to ask for any protective duty.

As to the specific gravity of Portland cement, referred to by Mr. Faija and Mr. Mann, Table XLVII. had been extended so as to show the specific gravity of thirty or forty cements, as well as their weight and their tensile strength, both neat and with

Mr. Grant.

sand. The specific gravity ranged from 3.193 to 3.040. He had not found that "the specific gravity in combination with the weight" gave an accurate measure of the value of the cement. He wished they did, as these two tests could easily be applied. Nor "that a heavy specific gravity and a heavy weight per bushel would indicate a finely-ground cement." For instance, No. 14 in the Table showed a specific gravity of 3.130, a weight of 9.52 lbs. per tenth of a bushel, and a fineness that left no residue on a sieve of 2,580 meshes to the square inch, and only 10 per cent. on that of 5,806 meshes. The specific gravity had evidently no relation to the degree of fineness, nor apparently to the tensile strength. If there were any, the Table in question would give materials to Mr. Mann for further investigating it. But it showed conspicuously that which was illustrated by several other Tables, how much the tensile strength of cement when mixed with sand was dependent on its fineness.

It was considered by Mr. Mann that "the expediency of bringing the time occupied in setting into specified or standard tests seemed doubtful, as cement could be made to set with any required degree of slowness by the simple process of air-slaking," and, he might have added, by other means. But the necessity for taking the time of setting into account had been increasingly recognised in Germany and Austria, both by the Associations and by eminent investigators. An examination of some of the Tables would illustrate this.

The useful remarks of Mr. Colson on the superiority of cement mortar, made with 4 to 6 parts of sand, to any lime mortar, were confirmed by Table XLIV. To remove the harshness in working with mortar made with such large proportions of sand, Messrs. Dyckerhoff found that it was advisable to mix a small proportion of fatty lime, which added to the strength and was preferable to fine sand or loam.

The experiments on the use of salt water by Mr. Cay seemed to answer Mr. Faija's questions. If Mr. Cay continued to specify the weight of cement, he should combine with it the degree of fineness, as the one without the other was illusory.

Before concluding, he wished to say that several of his Tables had been given more to illustrate certain steps taken in the course of his investigations than as the latest and best conclusions arrived at. It was one of the inevitable consequences of an inquiry extending over many years, that much of the work done in its earlier stages was rendered useless by later experiments and further experience. Still it might not be without interest, and might

save labour to other inquirers, to study some of these earlier Mr. Grant. tentative results. He was, perhaps, more sensible than any one else could be of the incomplete character of his investigation; but as it had been begun and carried on for the strictly practical purpose of ascertaining what was best suited for the works on which he had been engaged, the results might be of some use to those who had a like object in view.

In pursuance of the notice on the card of the meetings, it was resolved to adjourn for a fortnight, in order to avoid holding a meeting on Whitsun Tuesday, May 18th.