THE
INSTITUTION OF LOCOMOTIVE
ENGINEERS, LONDON.

The Electrification of the
L. B. & S. C. Ry. Suburban System.

BY
MONTAGUE F. LONG,

Associate, London.

With an abstract of the discussion upon the Paper.

NINTH PAPER
(OF TRANSACTIONS).

SESSION 1912.

*Read on Saturday, 18th May, 1912,
at St. Bride Institute, London,*

*Presided over by Mr. Charles A. Suffield, Chairman
of Council.*

LONDON :
Published by the Institution.

1912.

Price 1/6 net.

The Institution of Locomotive Engineers

PAPER No. 9.

The Electrification of the L. B. & S. C. Ry. Suburban System.

BY

MONTAGUE F. LONG, Associate, London.

Perhaps an explanatory foreword is called for, in introducing the subject of electricity to the members of this Institution. I believe I am correct in assuming that the operations of our organisation are not entirely confined to the steam locomotive, but that nevertheless there is an overwhelming majority of members intimately concerned in locomotive engineering. To the majority, therefore, I must beg for patience in bringing up a topic which cannot be other than distasteful to them. Moreover, in introducing the subject of electric traction, I stand as a pioneer.

There is, in all probability, not a single person in this room who will blindly decline to acknowledge that the progress of electricity, as a motive power, during the last decade has been really astonishing. Electricity is no longer spoken of as a power of greater mystery than the force of gravity or other such phenomena. Electricity for commercial uses is becoming more and more commonplace, and nowadays there are, in fact, very few locomotive works not largely dependent upon this wonderful force for working tools and all kinds of equipment. I am also confident that every engineer realises that the suburban electrifications of the past few years are but the first small instalments of a movement which will eventually result in the entire effacement of steam for passenger work. It is a hard and probably unwelcome fact, but nevertheless abundantly obvious.

Among above-ground railways serving outer Metropolitan London it will generally be conceded that none have grappled more successfully with the alarming problem caused by revenue being filched, by the unfair competition

of rate-aided trams and motor-buses using public roads, than the L.B. and S.C. Railway. Not that the plight of the Brighton Line was one whit more serious than that of most other companies. Nearly all were equally hard hit, but it may certainly be claimed that it remained to the Southern Company's lead and enterprise to demonstrate that by substituting electricity for steam, and thereby rendering a more speedy and frequent service possible, a means was provided, not only of arresting the fall in receipts, but of more than recovering the lost patronage. It was fortunate for the Company, no doubt, that in the South London Line they possessed a route pre-eminently adapted for an experiment in electric traction, but many other London lines were equally well off in this respect, but were contented to watch the result of the L.B. and S.C. Railway equipment.

In the interests of completeness I must briefly venture upon a short historical review of the South London line, which has now earned an epoch-making reputation all its own. Its inception dated from the period when the parent line was rashly engaged in adding to its mileage in sparsely populated districts of Surrey and Sussex. Legislative consent was obtained for the London Bridge to Brixton section in 1862, and as between these stations, a passenger service was inaugurated in August, 1866. Powers for the remaining length from Brixton to Battersea Park were subject to arrangements with the L.C. and D. Company, and were secured in 1864. The whole line was opened throughout on 1st May, 1867. It may be added that the section from Battersea Park to Victoria was the handiwork of an independent concern known as the Victoria Station and Pimlico Railway—and constructed five years before the South London Line was planned. The original work of building the South London Line was seriously hindered in consequence of the Company's financial difficulties at that time, and rigorous economy was enforced in equipping the railway; indeed, even when the line was opened the Shareholders Investigation Committee of 1867 reported the need for an expenditure of £52,000 to satisfactorily finish the work. Approximately the entire cost, including Parliamentary expenses, eventually averaged but £100,000 per mile. The original permanent way was of the lightest character, and its iron rails were, for many years, a source of anxiety to the locomotive department. To this poverty-stricken line, however, we must attribute those wonderful little tank engines best known as the "Terrier" class. This type was evolved in 1872 by the late Wm.

Stroudley with the sole object of coping with the difficult conditions then obtaining. It is not too much to claim for these little machines that they really ensured the South London Line being workable, at a time when the Company could least afford the expense of strengthening the road for heavier engines.

From terminus to terminus this route between London Bridge and Victoria is 8 miles 51 chains long. For the greater part of its length it is carried on a brick arch viaduct, but apart from this peculiarity, there are no engineering features of particular note.

The phenomenal success attending the South London Electrification—it is now ancient history that the passenger traffic doubled in three months—quickly led to extensions. In July, 1910, the conversion of routes to the Crystal Palace, both from Victoria and London Bridge, was decided upon. The lines concerned in the extensions comprising the section from Crystal Palace to Battersea Park, which had been originally opened during the late fifties, and the length from Peckham Rye to Tulse Hill. The latter was part of the line constructed with the object of affording a direct route from London Bridge to Portsmouth and first used for public purposes in October, 1868. In addition, two short connecting spurs at Tulse Hill as well as the lines from Crystal Palace to Selhurst were electrified. The length of the track involved in this electrification was equivalent to 46 miles of single track. Naturally, the experience already gained on the South London Line proved invaluable in facilitating the new work, which, with a view to completion in time for the Festival of Empire traffic to the Crystal Palace, was pushed forward with all possible speed. Contrasted with the four years involved in equipping the South London Line, the nine months which sufficed to instal electricity on the Crystal Palace extensions indicates the value and importance of the problems presented by the difficulties of the original installation, and furthermore constitutes an undoubted accomplishment in the annals of electrical engineering.

The line between Victoria and the Crystal Palace was actually brought into use on May 12th, 1911, and coincided with the King's visit to the Crystal Palace, but the full service was not inaugurated until June 1st following, when, on this section, the steam-hauled train became an exception rather than the rule.

In noticing the general equipment of the lines, it is perhaps fitting to record here the installation at the terminal

stations. At Victoria five platform roads are electrified out of nine, although only three of these are in general use at present, whilst at London Bridge six of the eleven platform roads have been equipped.

It would be difficult, perhaps, within the Metropolitan suburban circle to find more exacting operating conditions than those obtaining on the Brighton Railway's electrified lines. In all there are as many as eleven junctions. Numerous curves of small radius are met with, there being no fewer than 18 curves with a radius of 20 chains or less. The gradients are generally severe. Starting from Victoria there is the famous 1 in 64 climb to Grosvenor Road, and from Clapham Junction the line rises, almost without break, for the $5\frac{1}{2}$ miles to the Crystal Palace. Commencing with gradient of 1 in 87 just outside Clapham Junction, the average ascent to Wandsworth Common is 1 in 85. This is succeeded by sections of 1 : 80 and 1 : 90 to Balham, and thence to Streatham Hill 1 : 100 practically rules. Beyond West Norwood to Crystal Palace is a still more difficult length, such gradients as 1 : 80, 1 : 82 and 1 : 88 predominating. South of the Crystal Palace Station the line falls sharply to Norwood Junction, including nearly half a mile of 1 : 69.

The South London Line, on the whole, is less difficult, for although the gradients are exacting, they are almost evenly distributed, although the journey to London Bridge is rather more severe in consequence of its altitude being 25ft. higher than Victoria. The section from Peckham Rye to West Norwood, which connects London Bridge with Crystal Palace via Tulse Hill, demands hard pulling with the down train. The up grade from the junction at Peckham Rye to West Norwood is continuous and severe, and includes long stretches of 1 : 80, 1 : 91 and 1 : 93, culminating in a final 1 : 62.

Many of the stations are situated in the centre of severe gradients. Instances of this may be found at Wandsworth Road, where the station is half way up a 1 : 96 gradient. Clapham Road is in the centre of 1 : 107 and Streatham Hill 1 : 110. Others again involve starting right at the foot of a steep rise. Falling within this category are Denmark Hill with 1 : 91 for Victoria bound trains, West Norwood 1 : 80 and Gipsy Hill 1 : 88 for down trains.

I refer to these facts in order that the difficulties for either electric or steam operation should be appreciated at their true value. Obviously, if under such abnormal conditions electricity is giving a better service than was possible

with steam, then it is fair to assume that under normal circumstances its successful operation will be proportionately greater. In submitting electricity to such a severe test as a preliminary trial, the Brighton Company subjected the power to the worst working conditions possible on its types which formerly sustained the steam service over the now electrified lines.

Before proceeding with that part of my paper describing the present power, it is perhaps fitting that I should devote a few more moments in recalling the locomotive types which sustained the steam service over the electrified lines.

Until the advent of the late Wm. Stroudley at Brighton it is impossible to designate any type as standard for the suburban service. In those days engines were erected to a new design as required. It remained for Mr. Stroudley to teach the lesson of standardisation and the advantages of providing a number of engines conforming in dimensions and design to a set prototype. His "Terrier" class I have already referred to, but would add that at one time these engines were largely used on the Crystal Palace lines. The second passenger tank locomotives evolved by Mr. Stroudley were the numerous "D" type with the 0-4-2 wheel arrangement, 17in. $\times$ 24in. cylinders, 5ft. 6in. coupled wheels and 1,043 sq. ft. heating surface. Notwithstanding that this class was intended by their designer for loads not in excess of ten coaches, or 120 tons, they have yet been quite successful in dealing with the 25 per cent. heavier steam trains of later years. According to the tradition of all Stroudley engines, they were exceptionally economical, light on fuel and repairs, and possessed extraordinary capabilities for gathering speed from a dead start.

The late Mr. R. J. Billinton, at the outset of his career, built a number of trailing bogie tank engines, but eventually adopted the well-known class of six-wheel coupled engine with trailing radial wheels. The engines in this class were very numerous and generally proved themselves of all round utility. I have known members of the class with a seven-coach bogie train attain a speed of 43 m.p.h. on a level road in $1\frac{1}{2}$ miles, which indicates that their accelerating powers were of no mean order.

Mr. D. E. Marsh in his turn introduced heavy 4-4-2 tank engines of G.N. design, but it cannot be claimed for them that they represented a startling advance on the earlier Stroudley or Billinton machines as regards power. They will probably go down into posterity as the last engines for

suburban work to be built for the L.B. and S.C. Railway.

Turning now to the consideration of the electrical equipment it is undoubtedly a tribute to those responsible for the work, that it was accomplished without any interference with the ordinary train services. This, perhaps, is in these days a commonplace in engineering undertakings connected with railways, but in this instance, considering the wholly experimental character of the work, it is undeniably an achievement of exceptional note. It is true electric traction was not unknown in this country. As far back as 1890 the City and South London Railway, it will be remembered, had taught valuable lessons in the application of electricity for railway purposes. Even the single phase high-tension system was already effectively installed upon the Lancaster and Heysham branch of the Midland Railway. The difficulties were, however, not altogether connected with the system of traction as with the method of its application in the peculiar local circumstances. In any event, the installation of electrical equipment upon an existing steam railway is obviously a more complicated process than on a line specially constructed with a view to the adoption of electric motive power. The difficulties which presented themselves, and were overcome before the actual work of construction commenced, were probably more exacting than any which arose during actual progress. Foremost among these may be instanced the problems presented in order to adequately provide for the constantly varying range in height at which the current collector bow had to work, the distance ranging from as high as 19ft. 9in. to as low as 13ft. 9in. This was caused by low overline bridges and tunnels, station buildings, and the need for considering the safety of railway servants working upon the roofs of vehicles at terminal stations. There was the necessity of adopting every precaution to prevent any accidental contact being made with the high-tension equipment. There were awkwardly curved tunnels at Denmark Hill. Furthermore, in view of the fact that the success of the South London Line experiment would probably lead to the electrification of the entire suburban system, it was essential that the initial scheme should be planned, in order that it might eventually form part of a larger installation. These, however, are but a few of the contingencies it was necessary to provide for. During the course of my paper I hope to indicate others. In all, four years elapsed between the commencement of the initial South London enterprise and its completion. I might mention that the firm responsible for the actual contract of

electrifying the South London Line were the Allgemeine Elektricitäts Gesellschaft of Berlin, for whom Messrs. Robt. W. Blackwell and Co., of Westminster, acted as sub-contractors. In the case of the equipment for the Crystal Palace extensions, Messrs. Blackwell were direct contractors.

Practically the entire overhead work was effected during the early hours of the morning between midnight and six o'clock. The girders and wires being fixed at these hours by the aid of artificial light, the necessary adjustments for correct alignment were carried out, between trains, during the daytime.

Perhaps the most interesting feature connected with the Brighton installation is the overhead work.

To carry the overhead conductor wire, with its supports, a series of steel structures have been erected at intervals of about 50 yards. The type of construction adopted is no doubt familiar to the majority present this evening, and as the method of erection is obvious, calls for little description on my part. Many limitations prevented the adoption of a standard design for these structures throughout, but the principal types are five in number. The most noteworthy are undoubtedly the series of ten between Clapham Junction Station and Pouparts Junction. At this point, lack of room on the up side of line, because of the proximity of the South Western Railway metals, necessitated the adoption of a cantilever, fixed to massive supports for carrying the wires over all four roads—local and main. Between the legs of the supports space has been allowed for the provision of an additional running road. On the South London Line lattice girders were largely used, but on the Crystal Palace extensions, in order to avoid confusion with signals, the N. type of girder is general for large spans. In these girders the inclined member is placed in the reverse direction of signals when in the off position. An example of the most simple type of horizontal is to be found between Streatham Hill and Crystal Palace and in the lines near Tulse Hill, where girders give place to ordinary steel joists. The legs of each support carrying the girders are braced together and bedded on solid concrete blocks, to which they are fixed by means of Lewis bolts. In the Crystal Palace and Streatham Hill tunnels steel joists encased with concrete and taking their bearing on cast iron brackets, which were built into the walls and were also covered with concrete after the cross joists had been bolted in position.

Fixed to the girders and other horizontal bearers are the insulators from which are suspended the whole of the over-

head gear. Each pair of insulators carries its pair of catenary wires, which are thus suspended from girder to girder. The principal catenary wires are fixed quite independently from their respective insulators and fitted with turn buckles for adjustment purposes. At intervals of 10ft. along the catenary wire short steel wires or droppers are suspended, and from these droppers the contact cable is held by means of clips. In order to allow the utmost possible flexibility at each point of suspension, droppers longer than 2ft. 6in. are made in two parts and connected by 2in. links. This gives the contact cable a vertical play of 4in. For the same reason at the terminal stations chains are used instead of droppers with a view to counteracting the jar caused by changing the bows. The catenaries are tied together at intervals, generally at every third or fourth dropper, so that the two droppers with the tie form an equilateral triangle.

The all-important contact cable is of solid copper $\frac{1}{2}$ in. in diameter and has a minimum breaking stress of 22 tons per sq. in. In section the contact cable is circular and has two sharp grooves on either side for the purpose of fixing the clips, to which the droppers are attached. It is of some interest to note that no arrangement for tightening the contact cable is provided. With the object of ensuring even wear of the collector bow and to prevent grooving, the cable is zig-zagged between each pair of insulators and varies 9in. on either side of the centre line. The average height at which the cable is fixed above rail level is 16ft. At the respective termini, however, in order to comply with Board of Trade requirements for head room of 6ft. 6in. above the roof of any coach in service, it was necessary to pitch the cable at what is its greatest height, viz., 19ft. 9in. The lowest points, curiously enough, are encountered among other places at Victoria, where the loading gauge is only 14ft., and in the interests of safety neutral wires have been provided. Through these dead sections the trains are carried by their own momentum. Short neutral sections were originally provided to divide the contact cable in one line section from the next line section, but this arrangement has now been abandoned, and the conductor cables at the end of one section and beginning of another are now merely overlapped in the horizontal plane with an air space between them. The contact cable was supplied in half-mile lengths and was run off drums placed on trucks.

Needless almost to remark, the selection of insulators was a matter of special consideration, and they were objects

for the most searching experiments extending over a long period. All possible patterns were subjected to tests of much greater severity than would be met with under any conditions in actual use. The tests included the suspension of the insulators over the chimney of a boiler, fired so as to produce heavier smoke and hotter gases than would be ordinarily given off by a locomotive, and these experiments demonstrated the desirability of keeping the insulators directly out of line of the exhaust from locomotives. Eventually the porcelain spool type with a corrugation was adopted, and of this pattern, only three sizes have been found necessary throughout the entire installation.

I fear limitations of time compel me to dismiss this part of the subject with the further remark that extreme care has been taken to ensure that this most vital portion of the work should be as perfect as experience could devise. The installation, I might add, has been tested to ten times the working pressure.

Turning now to the means adopted for distribution, it may be briefly described as consisting of distributing by booster cables extending throughout the system.

The power, as perhaps is well known, is supplied at 6,700 volts and 25 periods from the generating station of the London Electric Supply Corporation at Deptford. Formerly many of the machines employed for generating the supply for the South London Line service were used for the requirements of the L.C.C. tramways, before the municipal station at Greenwich was available.

From Deptford the power is supplied to the railway at Queen's Road and Peckham Rye. For the purpose of meeting the original demands of the South London line the current was taken only at Queen's Road, whence it was transmitted by means of two 0.25 sq. in. feeders. The additional supply point at Peckham Rye was required for the largely increased energy demanded on the extensions to Crystal Palace and is fed by a 0.5 sq. in. concentric cable. Provision has been made at Peckham Rye for the reception of additional supply cables as may be necessitated by future extensions. A 0.5 cable has been laid from Peckham Rye to Tulse Hill, where distribution of power for the Crystal Palace Line is effected. The distribution from Peckham Rye suffices for the requirements of the South London Line. It will thus be evident that Peckham Rye is the distributing centre for the whole electrified system. As a safeguard against failure between Peckham Rye and Tulse Hill, the Crystal Palace lines may be fed by an alternative

cable which has been laid from Peckham Rye to Battersea Park. Independent cables have also been provided between the distributing point at Peckham Rye and the repair shops at that place, as well as between Tulse Hill and Norwood Junction Depot.

There is nothing connected with the method of supplying the current to the overhead conductor that may be characterised as remarkable. The equipment varies only in minor details from the usual and well-known arrangements adopted in the single phase system.

The high-tension cable, which is fed in the centre by duplicate cables, is laid parallel with the overhead conductors. From the high-tension cable, tapplings are taken at the switch boxes, and thence the power is transmitted to the overhead conductors by means of rubber insulated cables in the case of the South London Line and bare cables on the Crystal Palace lines. Generally at each switch cabin there are four such cables, one each being connected with the two sections of the contact wire to the up and down lines respectively. The same method applies to all the switch cabins except in the case of the box at Battersea Park supplying current to the Crystal Palace lines, where the contact wires on the Victoria side of Battersea Park Station are fed from the older switch box provided for the South London Line. There are twenty-two switch boxes throughout the electrified system, but of these, one each at Norwood and Peckham Rye Depôts respectively, control power only to the repair shops.

The whole system has been divided so that the equipment between each station is complete in itself; furthermore, the contact wires for up and down lines respectively are independent from one another, except at the terminal stations. At both London Bridge and Victoria, various restricting circumstances necessitated the whole of the conductor cables being connected together to form independent zones. There are a few minor variations to be noted between the original South London cables and the more recent method of distributing power adopted on the Crystal Palace lines.

The South London Line cable is covered with bitumen and paper insulated, and has an inner core of 0.125 sq. in. section and an outer of 0.5 sq. in. The inner of this cable passes into the switch box. The outer, on the other hand, is uninsulated and laid over the bitumen, and it is bonded to each running rail. Between Battersea Park and South Bermondsey a booster cable has been laid equal in size to

the distributing cable ; both the inner and outer of this cable are employed for the booster circuit.

On the Crystal Palace lines the inner core of the distributor cable has been enlarged to .26 sq. in., and the inner of the booster abolished, so that the latter becomes a low-tension return conductor. This modification has been introduced principally with the idea of saving expense. The function discharged by the boosters is to boost the return circuit from the rails and so confine the current to the cable.

The cables themselves are generally carried on stout posts and bearers and enclosed by a wood casing slightly above ground level, but in places are laid beneath the ground.

The switch cabins are simple brick structures nearly square in plan, and may be divided into two classes, viz., those to which booster connections are made and those without booster connections.

Taking the cabins without booster first, the equipment comprises merely a single bus bar. To this bus bar are attached the two incoming circuits from the distributing cable and the four outgoing circuits to the contact conductor. The connection to each conductor cable is carried through an isolating link, thus enabling the conductors to be cut out if required. A further use of the links is the means they provide for connecting any two consecutive conductor sections and putting an intervening switch cabin out of circuit. In the booster cabins, however, the bus bar is in two parts, the booster primary being connected between each part. Both the incoming and outgoing circuits are attached to the bus bar through the medium of a single-pole switch. Automatic trip gear is provided to the overhead contact conductor switch, whereas switches controlling the distributing circuit are non-automatic. It may be added that the boosters are likewise connected to the bus bars through oil switches. In the interests of uniformity, and in order that the electric plant may conform in external appearance as nearly as possible with equipment to which railway employees have become familiarised, the usual railway type handles are fitted to both contact wire and feeder switches. An earth bar is attached to the wall behind the bottom contacts and the switches so arranged that when open they are earthed. The lower contacts of the switches being attached to the contact wire sections, the effect of opening these is to automatically earth the conductor cable. Each switch is interlocked with its corresponding oil switch, and it is impossible to close them whilst the isolating switches

are open. A key comprises an integral part of the interlocking gear, and may be withdrawn only when the isolating switches are open. This safeguard was adopted for the assurance of the foreman in charge of work on the overhead cable, for with the all-important key in his possession he has proof that the section under repair is earthed.

Each switch cabin is divided in vertical height into two parts by a brick wall, on one side of which is located the high-tension gear and on the other the operating apparatus. The switch cabins are not occupied continuously by a member of the staff, and the key to the operating side of the cabins is kept at the nearest signal box, access to the high-tension apparatus being restricted to the qualified members of the electrical staff.

The distributing rooms at Peckham Rye and Tulse Hill, although—by reason of the more extensive gear they contain—more commodious than the switch cabins, are planned and arranged after the same general lines. Each distributing room is fitted with two bus bars, which are divided into sections with isolating links between them. Each section of the upper bar has a connection to the lower bar through an automatic oil switch. Under ordinary working conditions the isolating links of the lower bars are opened while the intercommunicating oil switches are closed. The entire supply of power to any part of the electric system proceeds from its respective section of the upper bar. In the event of a breakdown on any part of the line, the interconnecting oil switch would open, thus isolating the section of bus bar from which the supply to the section of railway involved with mishap is obtained. Furthermore, if desired, the switch may be kept open and the remainder of the line supplied with power, but eliminating the portion of line not in operation.

It may be mentioned that the whole of the switch gear was supplied by the British Thomson Houston Co., of Rugby.

At both distributing rooms wattmeters for registering the consumption of energy are fitted, together with ammeters for each circuit and voltmeters for each section, corresponding with the divisions of the bus bars. Electrolytic lightning arresters are provided to the bus bars at each room. The attendance of a man at each of the distributing rooms is required, but with these exceptions no other employees are necessary for controlling the normal process of distributing power.

The examination of the electrical equipment is the special duty of one man during the day time, and the whole

system is closely overlooked at least once a week. All repairs to the overhead gear are effected at night, after traffic has ceased. Repair gangs working with two special petrol-electric cars, with adjustable working platforms on the roofs, are retained for this duty. These cars, it may be mentioned, were originally built for service between Brighton and Kemptown, but with indifferent results, and until a use was found for them by the electrical department stood in the yard at Brighton. They are now equipped with Daimler petrol engines and electric gear by Dick Kerr and Co. At the present time the whole of the overhead gear is receiving a coating of tar to assist its preservation.

Compared with most electric railways, the rolling stock provided for the Brighton Company's electric lines is quite distinctive. Because the end door type of coach has been invariably adopted for electrically propelled trains it has been generally regarded as the more suitable for use in conjunction with electric traction.

A new departure was, however, initiated on the South London Line by the Brighton Company in adopting the side door vehicle, but with gangways, allowing communication between compartments of the same class. There can be small room for doubt that the success of the electric services has been, at least in part, due to the use of the side door compartment type of vehicle. So far as legitimate seating capacity is concerned, a compartment coach is infinitely superior to the open door variety. This advantage, however, does not apply to standing room, or to borrow the phrase of the man in the street—strap-hanging. It therefore follows that such vehicles as those running on the London Underground Railways lend themselves more readily to overcrowding—and who has not been a victim of the fact?

The original rolling stock put on for the South London Line service comprised eight three-coach trains. The cars at either end were fitted with motor and guard's compartments, and eight passenger compartments with third class seating accommodation for 66. The centre coach was for first class passengers only, with nine compartments and accommodation for 56 passengers. The total number of seats provided in each train was 188. The coaches had open side corridors and were divided into smoking and non-smoking sections, communicating by means of a spring swing door opening either way. The whole of these vehicles were constructed by the Metropolitan Amalgamated Carriage and Waggon Company, Ltd., of Birmingham. Each coach

was 60ft. over headstocks, 9ft. wide and mounted on two pressed steel bogies with 43-in. wheels. The weight of the original three-coach train was 138 tons, and of this total each motor coach accounted for 54 tons, and the first class trailer coach 30 tons. A constructional detail of particular note is the type of underframes. They are of steel plate girder construction, resulting in a very rigid frame with a minimum of weight. The trains are lighted by a double circuit of lights. Each compartment is provided with two Holorane globes containing two 10-candle-power lamps. Two oil lamps are also fitted for emergencies.

Every possible precaution has been adopted in order to minimise the risk of fire. Two mechanical fire extinguishers are provided in each coach, and the roofs, sides and bottoms entirely covered with sheet aluminium. In addition the bottoms are cased with heavy asbestos sheeting, with double floors packed with slag wool. It quickly became evident, however, that the original three-coach trains were not altogether suitable for the South London traffic, the first class accommodation being in excess of requirements and the fixed three-coach train too inflexible a unit for traffic fluctuating extensively according to the hour. In consequence composite first and third trailer coaches provided with driving and controlling gear were adapted for electrical working from the Company's steam stock. Complete units now, therefore, consist of one motor coach and one composite trailer during the less busy hours and two or three motors and two composites for the morning and evening traffic.

The South London motor coaches are 16 in number. Each is equipped with four motors of the Winter-Eienberg compensated repulsion type and give an output of 115 h.p. for one hour and 57 h.p. continuously. One motor is capable of hauling one trailer satisfactorily. The synchronous speed of the motor is 750 revolutions per minute. Each motor has six sets of brushes, four sets being for the short circuit current of the motor and two sets for the exciter current.

The rolling stock in service on the Crystal Palace lines comprises 24 motor coaches and 50 trailers. The whole of the motors and 25 trailers were erected by the Metropolitan Amalgamated Railway Carriage and Waggon Co., and 25 trailers at the Brighton Company's own works. These newer vehicles differ from the earlier productions in the abolition of the side gangway. All are of the usual self-contained compartment type. This modification was

decided upon because it was found on the South London service that, despite the facilities provided by the gangways in enabling passengers to find seats in the trains, it was a case of old customs dying hard, for the public still preferred their perambulations on the platform, resulting in no saving of time at station stoppages. In consequence of the restricted loading gauge of the Crystal Palace Tunnel, the new coaches are only 8ft. instead of 9ft. wide. Their length over headstocks is 56ft. The new motor coaches provide seats to the number of 70 for third class passengers only. The composite trailers accommodate 24 first and 50 third class, there being three first class and five third class compartments in addition to separate motorman's and guard's compartments respectively. Each trailer is also equipped with driving gear. The motors fitted to the Crystal Palace stock are of a more powerful type than those supplied to the South London trains. They are four in number, and although nominally classified as 150 h.p., are capable of a combined output of 175 h.p. for one hour and 90 h.p. continuously. The newer motors have proved to be lighter per unit of output than the original motors fitted to the South London stock. One motor coach is thus capable of dealing with two trailers. Three-car trains are, therefore, run during the slack hours of the day, whilst in the morning and evening each train is made up to six cars—one motor between two trailers in each unit.

The newer stock constructionally differs very little from the South London vehicles. Aluminium sheeting has likewise been utilised for covering the exteriors with a view to safeguarding the coach from becoming charged by leakages. In addition to hand brakes the latest standard application of the Westinghouse brake is fitted, and it should be mentioned that the compressed air is also utilised for the purpose of raising and lowering the collector bows. The weight of the trailer coaches empty is 25 tons, and the whole of the electrical equipment on motor coaches weighs 19 tons.

Measures to protect the motor men from danger have been well considered. The whole of the high-tension driving gear is placed in a separate fireproof compartment. By means of an interlocking arrangement access to this chamber is only possible when the collector bow is not in contact with the overhead cable. As a further safeguard, a contrivance is provided by which the door giving access to the compartment, on being opened, automatically releases the air from the cylinder supporting the bows, causing them to drop from

the conductor wire. Beyond this, too, the gear in the high-tension compartment is earthed upon the door being opened.

The driving and controlling gear is placed round a window on the left hand side of the motor coach. In attention to the customary controller with speed control and reversing barrels, meters, brake and whistle valves and pressure gauges, an arrangement is provided which enables power to be taken from the trailing bow when the front bow is passing over a dead section and vice versa. For use in wet weather a squeegee has been fitted to the front of the motorman's window.

In connection with the master controller it may be mentioned that it is divided into two parts. One part consists of the drum, which operates the contacts and is moved by means of the driving handle, and the other part operating the reversing contacts is moved by means of a small loose handle which can be removed. The two parts of the controller must be held down during the whole time the train is in motion, otherwise the power circuit is interrupted and the train automatically brought to a standstill by the brakes.

Another example of the extraordinary care which has been exercised to eliminate the human element as far as possible from causing danger, is the arrangement by means of which the brake wheel may be manipulated, either from the driver's or guard's compartments respectively, according to the direction in which the train is travelling. The brake wheel is half enclosed by a semi-circular screen. When the motorman is occupying his compartment, as is the case when driving, the screen is adjusted, so as to render the brake inaccessible from the guard's van. When, however, the motorman is at the other end of the train, as he would be for travelling in the reverse direction, the screen or shield is turned round and may accordingly be handled by the guard. Thus the guard, whilst able to control the brake, cannot gain access to the driver's compartment, or the gear it contains.

The collector bows call for special consideration. It will be remembered that the difference between the highest and lowest working level is 6ft. Furthermore, at the lowest point, the clearance is a matter of less than twelve inches. This involved the roof of the motor coaches being shaped to a lower level in order to accommodate the mechanism incidental to the collector bow. The bow, which is 5ft. 2in. wide, is held at its working angle, at a very slight uniform pressure against the overhead cable, by means of spiral

springs, pneumatically controlled. Two bows are fitted to each motor coach, one at a time being used, according to the direction in which the train is travelling. The actual contact slips in the collector bows are 3ft. 7 $\frac{1}{4}$ in. in length and composed of aluminium. There are two contact slips to each bow, the function of the second slip being to ensure a continuous contact and to reduce the current, which would otherwise be carried by one slip alone.* The current collected by each bow under normal conditions has been found to average 30 amperes. The slips are fitted with grooves, which are filled with a mixture of vaseline and graphite for lubrication purposes. Notwithstanding that the entire wear is thus taken by the contact slips, they run an average of 5,000 to 6,000 miles before requiring renewal.

The current collected by the bow is transmitted to the high-tension chamber and thence to the two transformers under each motor coach. From the transformer the current at low pressure is conveyed to the controllers and motors. Each pair of motors works in conjunction with a 220 K.W. main transformer. Mention may be made of the fact that the main transformer steps down from the 6,700 volt supply pressure to a maximum of 750 volts on its secondary side, and by means of contacts connected to form tapplings, the volts supplied to the motor may be 450, 580, 640, or the full pressure 750 volts. The regulation of speed is effected by adjusting the voltages supplied to the stator coils and exciter circuit.

The design of the rolling stock was the joint work of the Company's late locomotive and carriage superintendent, Mr. D. E. Marsh, and Mr. Philip Dawson. The entire electrical equipment was manufactured by the Allgemeine Electricitts Gesellschaft, of Berlin.

It will no doubt be readily realised that the requisite arrangements and conveniences for the maintenance of the electrical rolling stock could not be taken over by any previously existing department of the Company's service, and for the purpose of coping with repairs, special shops have been erected at Peckham Rye and Norwood Junction.

The Peckham Rye Dept was originally equipped for the express needs of the South London Line, and all the more important and heavier work is still effected there. The shed first erected at Peckham Rye answered require-

* The trailing slips have now been removed from the bows.

ments both for repairs and shed purposes, but a separate carriage shed has since been added, and the earlier erection is now utilised exclusively for repairs. The repair shops are divided into two bays. One is used as a workshop, whilst the other, which has two through roads with pits, is reserved for lifting purposes. Contact wires are not fitted in the lifting shop, and vehicles are moved in or out by means of four capstans. In addition to a 20-ton overhead crane the lifting shop is provided with a special contrivance for lifting coaches for the removal of bogies. This device is a large double clamp which is placed round the coach and enables a motor bogie to be replaced and ready for service in a little over three-quarters of an hour. Bogies are transferred from the lifting to the repair shop by means of the traverser and turntables. The repair shop is divided into two sections. In one portion, which is provided with a 5-ton overhead crane, are the various machine tools, and the other portion is allocated to storage purposes and small repairs. The entire rolling stock is subject to constant inspection and is periodically overhauled in rotation during a period of twelve months. The average distance run between successive visits to the repair shops is 60,000 to 70,000 miles.

The new carriage sheds at Peckham Rye possess four roads with examination pits. At present contact wires are not fitted, but this equipment is shortly to be installed. Two 25-ton overhead traversers are provided in these sheds, where, however, only minor repairs, arising in the ordinary course of maintenance, are carried out.

The Norwood Junction sheds have been erected adjacent to the goods yard on the south side of the station. The buildings are more spacious than those at Peckham Rye. The main shed is 401ft. long, and has six through roads, each with an inspection pit. The general equipment very closely resembles that at the older Peckham Rye Dépôt. Contact wires are fitted throughout the six roads. The overhead conductors in the shops comprise a distinct zone in themselves, and are isolated from the wires over the running roads by dead sections. The supply of power is entirely controlled from a sub-station situated in the yard, so that the high-tension current may be conveniently cut off, when required, in the interests of safety. For moving vehicles when the current is not available recourse is made to electric capstans, and four $3\frac{1}{2}$ -ton capstans have been provided accordingly. The work undertaken at the Norwood shops is of a light character and confined to the repair

of such minor defects as are revealed during the course of the ordinary daily inspections.

Turning now to the general topics arising out of the electrification, perhaps most important of all is the question relating to the two leading systems of application. The preference of those responsible for the Brighton Railway equipment, for the single phase system, renders a speedy settlement of the controversy more desirable than ever. The matter has been the subject of discussion for many years, but it must be acknowledged, with little profit. Probably, at the moment, there is no other question before the railway world so fraught with possibilities for the future—either for good or ill. Ill only can come as the result of a passive attitude. The unfettered extension of both the single phase and continuous current systems will surely bring chaos if present principles of railway operation are to obtain in future years. It would appear, at the moment, that the battle of the gauges and the muddle with the brakes has been for naught, the rival camps seemingly being as difficult to conciliate as were Stephenson and Brunel in the early Victorian days.

It is at least surprising that in the controversy which has waged over the present-day difficulty, the all-important statistics which would have put the matter beyond dispute have been generally lacking. It is true that figures bearing upon the cost of one system or the other have been published, but such data has either been unauthenticated or else related to minor details in the expenses of operating. In any event such particulars have a doubtful value if incomplete, and may well be ignored by partisans. Meanwhile, the mileage claimed by either method of traction in this country is rapidly increasing and a few years hence may witness the total extinguishment of the present longer track mileage adapted for continuous current use.

This cleavage in the ranks of electrical engineers, while affording some consolation to their locomotive brethren, is unquestionably the greatest obstacle the progress of electric traction has to encounter.

The particular conditions relating to the Brighton Railway, however, virtually left no alternative than the provision of the single phase system, and the same conditions apply to nearly every other large trunk line. Since the eventual conversion of at least a large portion of the railway was contemplated, if the original equipment proved successful, it was necessary to adopt the system most suited to long-distance high-speed traffic. For this all-important con-

sideration alone the selection made was inevitable. Another serious technical objection to the adoption of the continuous current system was a clause inserted in the Company's Act, authorising the electrification, which enabled the Board of Trade to fix 20 volts as the maximum drop of pressure in the return current. A further local obstacle to the continuous current system, as far as the Brighton Line was concerned, arose from the number and complicated character of the junctions on its network of suburban lines in South London.

That there are weighty objections to the single phase system cannot be overlooked. The method of conduction—both on the grounds of cost and its obstructive features—are typical examples of points in the case against it. Furthermore, such adverse criticism as that levelled against the reduced output of generators and motors, less efficient regulation, and the greater weight of trains compared with the continuous current method must be reckoned with. These and similar objections are the pros and cons of the question. Briefly, I will endeavour to indicate a few equally weak factors militating against the continuous current system. Firstly, it is scarcely suitable for long-distance high-pressure working. This may appear to be a somewhat ambiguous statement, but the fact, I believe, is nevertheless readily conceded by all continuous current advocates. In short runs the energy is not only practically proportional to train weight, but virtually all power is used for the purpose of accelerating. On longer runs, however, the effect of train resistance asserts itself. Secondly, a great point in favour of the single phase system is the ease with which the pressure may be regulated.

An undeniable objection to the continuous current installation is the obvious danger attending the use of the third rail, both from the mechanical and electrical points of view, and the increased difficulties arising from accidents to the third rail or derailments.

To adequately discuss the relative merits or otherwise of either method of traction would amply justify separate treatment, but I hope for present purposes enough has been said to direct some attention to the pressing need for a settlement of this important matter.

The second topic which naturally arises out of the subject matter of my paper is the all-important one as to relative efficiency of electricity for purposes of traction, as compared with steam. Before entering upon a review of actual comparisons in running, it would be well to briefly consider

the time table differences between steam and electricity. I will not venture to suggest that the new power is capable of performing point to point journeys in half the time required by steam. Statements of this character have appeared in the Press from time to time, but there is not the smallest foundation for them in fact. I want to be fair and judge upon the merits of steam and electricity simply as revealed in the time tables. Turning first to the South London Line. It was unofficially suggested that a ten-minute saving in time had been effected by the installation of electric trains between London Bridge and Victoria. Actually, there were a number of steam trains timed to accomplish the complete journey in 30 mins., whilst there were a number of 31, 32 and 33-minute trips. Thirty-four-minute has been taken as the standard steam time, but whilst it is true there were instances of such a schedule, it was by no means standard in the same way that applies to the 24 mins. allowed for the electric trains, and if some steam trains were able to run the distance in 30 mins., stopping at all intermediate stations, it is only logical to assume that all might have done the same. The total number of electric trains between Victoria and London Bridge is now 80; the steam total was 43, and of the latter, 11 ran no further than Battersea Park.

Passing on to the Crystal Palace service, the average time allowed for steam trains for the 8 miles 55 chains from Victoria to Crystal Palace was 31 mins., stopping at all intermediate stations and allowing 1 min. at Clapham Junction for station working. For the same journey and number of calls—but with no time allowance at Clapham Junction—the electric trains are allotted 25 mins. This represents an advantage of 6 mins. for electricity, or conceding to both the same allowance at Clapham Junction, the gain by electricity is reduced to 5 mins. The special non-stop service instituted in connection with the Festival of Empire reduced the advantage of electricity still more, for steam trains were allowed 17 mins. from Victoria to Crystal Palace and electric 16 mins.

In the reverse direction the electric timing, including stops at all stations, is 23 mins.; the steam time was 30 mins., the latter with an extra minute at Clapham Junction. However, as steam was a mere 3 mins. behind its rival at Clapham Junction, it may safely be assumed that the additional 4 mins. required by steam between Clapham Junction and Victoria was allowed for traffic rather than any other purpose such as the inability of steam locomotives

to maintain a harder schedule, particularly when the 15 m.p.h. slack which applies one-third of a mile north of Clapham Junction is allowed for. The advantage of electricity is, therefore, a matter of not more than 5 mins. Yet, despite these facts, it has been freely announced in the Press that the electric trains were performing the journey in half the time required by steam.

The total number of week-day steam trains provided between the Crystal Palace and Victoria was 44 down and 47 up. The figures for electricity are 77 down and 75 up.

With a view to putting before you this evening reliable figures of comparative everyday normal working between steam and electricity, I have been carefully observing the running between Victoria and Crystal Palace. The result of timing a very large number of runs shows that the quickest times actually spent running between stations on the up journey to Crystal Palace was 20 mins. 58 secs. in the case of electricity, and 24 mins. 22 secs. with steam—an advantage of 3 mins. 24 secs. to electricity. On the up journey to Victoria the figures are: Electricity, 19 mins. 15 secs.; steam, 21 mins. 30 secs.—the margin in favour of electricity thus being 2 mins. 15 secs. No account can be taken of stoppages at stations. Invariably the electric trains, thanks to the use of self-acting door locks, spend about 21 secs. at each station, whilst steam trains generally stand 35 secs. This factor, however, has no connection with the motive power, although too often the whole journey time is taken in gauging the advantage to electricity.

But whilst the best times of steam compare not unfavourably with electricity, yet the difference when considering averages is more marked to the disadvantage of steam. For instance, the *average* time consumed between stations from Victoria to Crystal Palace was 21 mins. 53 secs. for electricity, whilst the aggregate for steam was 27 mins. 5 secs., a difference of 5 mins. 12 secs. The figures for the Crystal Palace-Victoria journey yield a like result. Indeed, it is a little remarkable how uniform the electric running is, the starting to stopping time between any two stations seldom varying more than 10 secs. As an instance of this I would mention six consecutive runs from Clapham Junction to Wandsworth Common which were performed in 3 mins. 14 secs., 3 mins. 18 secs., 3 mins. 15 secs., 3 mins. 15 secs., 3 mins. 14 secs., and 3 mins. 15 secs. The distance, I might mention, is 1 mile 29 chains on a fairly heavy up gradient. Selecting six consecutive steam-hauled train runs over the same section the times are 3 mins.

39 secs., 3 mins. 38 secs., 4 mins., 3 mins. 47 secs., 4 mins. 5 secs., and 3 mins. 20 secs.

Of course, I realise that an absolutely fair basis of comparison, such as weight for weight of train and identical weather conditions, is difficult to obtain, but in the examples quoted the circumstances and conditions were as nearly as possible the same.

No doubt the small difference in time between the up and down journeys, notwithstanding the heavy climb involved on the up journey by the ascent to Crystal Palace, will have been noted, but this disparity is due to the careful running enforced after passing Clapham Junction.

Official tests of an exhaustive character have been made on the South London Line. The non-stop journey from Victoria to London Bridge was then accomplished with a train weighing 138 tons in 14 mins. 8secs., representing an average speed of 37 m.p.h., the maximum speed being 50 m.p.h. The consumption of energy recorded at Denmark Hill switch cabin was 42 units, whilst at Deptford 40.7 units were registered, giving a mean total of 41.4 units. In point of time, however, this journey was not exceptional, as the same distance has been run in 12 mins. for the $8\frac{1}{4}$ miles.

The average consumption of energy for the South London Line service from December, 1910, to November, 1911, was 10.6 units per train mile per month, on an average monthly run of 37,021 train miles. For the twelve months ending December, 1911, which from May included the energy consumed on the Crystal Palace lines, 8,219,080 units were used, thus averaging 684,923 per month and 10.4 units per train mile, the miles run per month being 63,580.

I have found the accelerating powers of the electric trains far superior to steam, and the only advantage steam appears to have is on the longer runs or on down grades. Furthermore, the electric trains are 4 to 5 m.p.h. faster on such up grades as 1 : 100.

As an instance of what the electric trains are capable of in the attainment of speed from a dead start, I would mention a personally observed case starting away from London Bridge. The first quarter mile out occupied 44 secs., but the average for the second quarter was 28.5 m.p.h., at the third quarter the average had risen to 39.1 m.p.h., and in one mile 42.8 m.p.h. This performance was accomplished in ordinary working and the train comprised two C.P. motor coaches and two trailers. Over the same section of line, the

best achievement by steam has so far been an average of 7 m.p.h. slower.

The fact that the electric service is being worked as economically as possible must be borne in mind. A series of plates have been fixed for the guidance of motormen, indicating where the current may be cut off and coasting commenced. If it were desired to accelerate there can be no doubt that a further three or four minutes might be safely taken off the present time allowances for complete journeys.

Considering the liberal services maintained, it may occasion some surprise to know that both the South London and Crystal Palace lines are served by seven trains each. The staff required for working these trains is one motorman and one guard in each instance. Even though it were possible to provide an equally frequent steam service with the same number of trains, at least 18 locomotives would be required. The total number of men necessary would therefore be 50 for steam and 28 for electricity. In addition, the greater wear and tear caused by the locomotive and the heavier physical labour in which the enginemen are involved, are surely factors of importance.

All acquainted with the electrical service will readily acknowledge what a boon the absence of smoke constitutes. The compartments are free of the grit which is common to steam-hauled trains, and this point also suggests that the cost of painting station buildings and ironwork will be considerably lessened with electricity as a motive power.

As regards the cost of maintaining electric compared with steam locomotives, it is stated that the agents of electricity are cheaper by 50 per cent. It is also claimed for the electric motor that it is capable of more work than a steam locomotive, because no time is lost in taking coal or water, or in the other preliminaries incidental to the running shed. Furthermore, repairs may be effected more expeditiously, and generally speaking, five electric motors will perform the work for which eight locomotives would be required. That considerable time is saved in terminal working and generally less wear and tear involved is possibly too obvious to need explaining. On the other hand it may be urged that the superior elasticity of working the steam engine is a point in its favour. Steam locomotive engineers have also contended that their motive power, being generated as required and being independent of a conducting medium, has the advantage which no electric locomotive yet designed possesses. As to repairs, it is urged that as the life of the

steam locomotive is much longer than an electric motor, and as far longer periods elapse between successive visits to the repair shop, there is no advantage to the electric locomotive.

Arguments for and against could thus be multiplied, and many will, no doubt, readily suggest themselves to you, but as in the case of the divergence of opinion on the systems of applying electricity, in the absence of reliable figures, the whole discussion must be regarded in the abstract. Points favourable or otherwise to one power may be obvious, but until the all-important statistics are forthcoming the outcome must remain simply a matter of opinion.

It is common knowledge that an enormous increase of passengers has followed the improvements instituted with the provision of the electric service. However, it is scarcely fair to attribute the whole of the wonderful expansion in numbers to the faster electric service. Not only would many of the betterments have been equally feasible under the old conditions, but in the case of the South London service, as I have indicated, many of the trains ran no further than Battersea Park. At the same time there can be no doubt that the public have responded as a result of the Company's enterprise and the accelerated and increased service rendered possible by electricity is largely responsible. During the last year of steam working on the South London Line the number of passengers carried was 3,889,000. In the first complete year of electric working the number had risen to 7,900,000 and 8,941,000 in the second year. On the Crystal Palace Line the increase has amounted to 40.36 per cent.

This brings me to the conclusion of my subject. It remains, however, for me to record that the whole of the work in connection with the conversion has been carried out to the designs and under the supervision of Mr. Philip Dawson, M.I.C.E., to whom I am indebted for information and the drawings exhibited.

In the short space of time at my disposal it has been impossible to enter into much detail. I have, in fact, confined myself principally to the general aspect of the subject, and must express my sincerest thanks for the patient hearing you have accorded me.

DISCUSSION.

Mr. Suffield, after proposing a hearty vote of thanks to Mr. Long, said there were just two points upon which he should like some further information. Was not the overhead part of the undertaking in respect to the design of the overhead equipment and the erection of it not only a source of considerable trouble, but one of such expense as to give generally a very unsatisfactory result from a purely commercial point of view? As regards the live rail system, apart from the initial danger of the live rail, could the author give them any data in regard to the comparative cost and economy of each system and his opinions for and against? The double catenary type system must undoubtedly be extremely expensive and there must also be a sag to take up, for which, the author had told them, no allowance was made. He took it that there must be some arrangement, because as the trolley was travelling it had a tendency to continually stretch the wire, therefore if you were getting that sag you were getting extra resistance and friction. He would also like to know the author's opinion of the relative merits of wood-stick high potential insulators against porcelain. He would like to know what design of insulator they were using and which they found to be the best on the L.B. & S.C.R. He knew for a fact that there was an American firm who had quite recently brought out a new porcelain insulator of a peculiar design which gave a very long life against the wood-stick insulator, the life of which was a problematical one; and if the author would let them know the type of insulator that was being used on the L.B. & S.C.R. and his opinions of other insulators that had been used for this service, they would be glad to hear them.

Mr. Anelay, seconding the vote of thanks, said that this was a most important paper and that it would be a good thing to place the opinions of the members on this subject on record. Quoting a passage which had appeared not so long ago in a certain well-known monthly railway journal to the following effect:—"That it was strange that a Company which had done comparatively so little to develop the possibilities of the steam locomotive should have given itself over so unreservedly to electrification," Mr. Anelay said that immediately he read those words he felt in complete agreement with them as it had never appeared to him that the L.B. & S.C.R. locomotives had had to work

so hard as the locomotives on lines running north and west. That was true, at any rate, as regards the main line, but, of course, not all the railways running into London had such large suburban systems as the Brighton Line; only the L. & S.W.R. and the S.E. & C.R. could compare with them in that respect. But, comparing the locomotive working on the main lines, he thought if you took your stand on any of the platforms of any of the railways running north or west at a station about 15 miles out of London and observed the running of the trains through those stations on the G.N.R., Midland, or L. & N.W.R., and then came to the Brighton line, you would notice a considerable difference in the working of the engines in many cases. In the case of many trains on the L.B. & S.C.R., as you stood on the platform, you would see that the engine was well notched up and the steam would be simply drifting from its chimney in a trailing cloud. But on the northern roads you would hear a fierce blast. Therefore it was his opinion that the Brighton Company's engines had never been worked so hard as the engines on lines running north and west. They had seldom been "extended" to the extent that engines on the other roads had. Consequently, he thought it would have been reasonable, at any rate, in the case of the L.B. & S.C.R., to have made more experiments with steam before adopting electricity even so largely as they had up to now; and he thought that that might have been done something on these lines. The Company possess a very useful class of 0-4-4 bogie tank engines and they also have a very numerous class of 0-6-2 engines. These latter are six-coupled radials with 5ft. wheels, 18in. $\times$ 26in. cylinders, and their boilers carry 160lbs. working pressure. The engines of this type weigh 55 tons in working order, so they have plenty of adhesive weight and can exert a fairly high tractive effort, but to gain greater efficiency and economy in working, ten—or more—might have been equipped with the Schmidt super-heater. We had been told, he believed, in a recent paper read before the institution that a set of super-heater elements cost approximately £80. Therefore, if ten engines had been so fitted, the first cost would have been £800. Adding to this sum, for wages and cost of fitting, £200 to £250, the total charges would amount to about £1,000. He would be surprised to hear that the Company had obtained one of their electric trains for less than twice this amount. An engine of that type with two, three, or four bogie coaches, he would say up to five, according to the hour of the day and the condition of

the traffic, might have been employed over those sections which were now electrified as an experiment, at any rate, before finally abolishing steam. On the South London Line, previous to the electrification, the services, in his opinion, were most unsatisfactory. The Company used to run seven-coach bogie trains to and fro over that section with perhaps a dozen passengers, and some years ago, those trains, weighing 144 tons without a single passenger in them, were being hauled by the late Mr. William Stroudley's "Terrier" engines, and a passenger travelling in those trains would not be able to see what was hauling him. The train completely covered the engine in front. It was an excessive use to make of those small engines; but, of course, when those engines were taken away for other service a larger class were employed. But that service, specially, was a very slow one and the trains were run at long intervals—two trains an hour he thought were the most one got for a considerable period in the day, and, therefore, he thought that that line would have been a very suitable one upon which to have made a further experiment with steam before finally adopting electricity. He also commented on the advantages and improvements in the electric stock compared with the old steam-hauled stock, but complained of the noise of the motors being a nuisance in the motor coaches. Comparing the lighting, he mentioned that in the electric stock four electric lamps were provided in each compartment, whereas in the old steam-hauled stock there were either two gas jets or one electric lamp. He also complained of the way in which the electric trains were handled by the Traffic Department, stating that in the busy hours sometimes it would happen that a three-coach train (one unit) would come into a station where the platform was crowded with passengers, with the result that overcrowding took place. It was, he believed, impossible to add one coach to these units, the train must either be a unit of three coaches or two units, namely, six coaches. The service, of course, was frequent enough; he believed on the Crystal Palace—Victoria service they ran about every 12 minutes, but he did not see himself why a similarly frequent service could not have been given by steam-hauled trains such as he had already alluded to. A tank engine, with three or four bogie coaches could, he maintained, have kept up an equally good service. The chief advantage of the electric service was, after all, its rapid acceleration, and when you had said that, it seemed to him, you had said very nearly all about it. Mr. Long had given some inter-station

timings. Electricity had a little the better of it, but not a great deal. A great point was made of time saved on the suburban system. On the South London Line the terminus to terminus time was, he believed, 34 or 35 minutes with steam and now it was 24. He maintained that a steam service could have been arranged and organised to work that branch in 30 minutes regularly and have given the public every satisfaction. Therefore it was his opinion that the advantages of the electrification were not so great as claimed and there was not the slightest question that they would prove much more expensive. Mr. Long had not given them any figures of cost—possibly he was not in a position to do so—though they would have been very interesting, but he felt no doubt, in his own mind, that the electrical working would, in the long run, prove to be much more expensive than working with steam locomotives.

Mr. Fullagar said there were one or two points which had been raised in the course of this most interesting paper on which some light could be thrown by experience on the N.E.R. One was the relative effect on the traffic. As Mr. Anelay had just said, the railways down south had gone in for electrification without, in the first place, making the best use of steam trains. These were not anything like up to the standard of electric stock, and the N.E.R., who happened to be the first line to open a big electric system in England, had made very careful experiments and they had found out the comparative effect of electric and good steam trains. On the north side of the Tyne they had electrified 50 miles of line and on that they ran quarter hour trains each way and expresses at important times. They had been entirely successful and had recovered a large amount of traffic previously lost to trams. Their electricity was obtained from one of the chief power supply stations in the world, which was an advantage. This was the third rail system. Another advantage was that there were trains every quarter of an hour and no time tables were necessary. Quite good stock was run. The traffic on the north side of the Tyne was very heavy and on the other side it was similar. There were a good many difficulties in the way of electrifying this side at the time, one being that the power station could not take it at the moment and another was that they had to get over the high level bridge. So they electrified the north side first. They had now instituted on the south side a service of steam trains every twenty minutes, which ran equally as regularly, with expresses at important times, as the electric trains on the north side.

0-4-4 tank engines were employed with seven bogie cars of good stock. For the present they did not think of extending electrification. They probably would in time. Traffic on the south side was entirely satisfactory, which was, evidently, very largely due to the regularity and frequency of the trains and to the fact that passengers travelled at a reasonable speed in comfortable vehicles. These other companies had neglected small points. The time taken in closing a train with ordinary locks might be anything up to half a minute, but for a train with Kay's locks, all that was required was for one porter to put his hand out. Details like that had nothing to do with electrification, but they made a very considerable difference in the running of the trains. There was just the usual reference in the paper to the two methods of traction, and the question of the supposed danger of the third rail had been brought up. He would like to say that, up to a few months ago, there had not been a single employee killed in the discharge of his duty owing to the third rail on the N.E.R. They had killed a large number of dogs and a certain number of trespassers, but nobody whose business it was to be there at the time. The most serious trouble they had was with the injectors of the tank engines—the waste pipe used to drip water on the third rail and several firemen had had shocks; also, sometimes, owing to something being dropped on the third rail, a short circuit was caused. The only other drawback to the third rail suggested was the frequent junctions. Probably some of them would remember what the east side of the Central Station at Newcastle was like for junctions. A very large proportion of these were electrified. The train had always got two motor cars, and if it should be stopped at a signal, one or the other was always in contact. They could afford to leave out the live rail. There were great drawbacks to the single-phase system, one of them being the difference of 24 tons weight between the motor bogie and the trailer and the actual weight of the motor equipment—19 tons. This was a very serious matter besides the loss of efficiency of a single-phase motor. It all wanted power to move it and general wearing expenses were caused by this weight. He was not quite clear about it, but thought that Mr. Long had said there was no alternative to single-phase working for the Brighton Line. He would rather like to know the determining reason, because it was the opinion of some that single-phase working was adopted on the Brighton Line because Mr. Dawson, who had probably done more than

anyone else towards perfecting this particular system, was their engineer. It did not appear that there was any absolute necessity for it, because, as Mr. Long had mentioned, there were extreme difficulties in fitting up the overhead system. One other point that occurred to him was that Mr. Long had said that the continuous system was obviously unsuited for long distances. Of course, the great advantage was more apparent for short distances, but, at the same time, they had electrified sections at Buenos Ayres at the present time, on the Southern and the Western and the Pacific Railways, which extended to very considerable distances—to what we should call long distances. Mr. Long had also said that as electrification had proved so extremely successful where working was very difficult, it would be more successful where working was easier. The advantage of electric over steam working was most apparent where there were great difficulties in steam working, steep gradients, and a frequent and rapid service required. So many things threw steam working out, different conditions of weather, variety of steam locomotives and their lesser reserve, owing to slower acceleration, to deal with any delays. A great point was that the same speed could be maintained with motors, which speed was determined when the motors and resistances were made. They were fairly independent of weather conditions and therefore much more adapted for maintaining a regular service. If the conditions were easier for steam traffic, the advantage was very largely decreased. The matter rested, of course, with the question of cost.

Mr. Garratt said it appeared that the whole question of electrification or of running a railway by steam was what it was going to cost and what it worked out at per ton hauled. Now if Mr. Long would give them some information as to what it cost to run an electric train per mile, they would be getting a definite basis for comparison. What did it cost? Because if steam was cheaper than electricity, there was no doubt we should run our railways by steam. If electricity was cheaper than steam, we should run our railways by electricity. He thought the ordinary average train cost about 10d. to 12d. per mile to run, for locomotive purposes, all included, wages, coal, etc. If Mr. Long could give them some general figure which would compare with that, he thought it might lead to a practical discussion.

Mr. Dearberg thought there was one fact quite clear, and that was that these railways that had taken up electrifi-

cation had not made the best use of locomotive engineering in its latest phases. For instance, the Brighton Railway did not have tank engines which were really accelerating engines. Mr. Holden, when he built his Decapod, got acceleration, and, by slight alterations in other engines, was able to get increased acceleration. But, in the speaker's opinion, by far the most useful type of engine for heavy morning and evening suburban traffic was the 0-8-2. These engines not only ran at a fairly high speed, but could accelerate and get away, and if all the latest improvements were put into one of those engines with a good train with all the latest ventilation, lighting, etc., he thought it would be successful. As regards the Brighton electrification; they had heard a good deal about acceleration. Personally, he had never found the acceleration to be anything near what the District gave with continuous current. What he had seen on the Brighton could be done by one of Mr. Ivatt's 0-8-2 tank engines. He had recorded far better acceleration with these engines when they were in London a little while ago. About the cost, if they could prove that electrification was really cheaper, of course, then it would be adopted. He thought, in fairness, however, the steam engine should be given the best trial possible. Then, if it were given a fair trial and it went under, adopt the other. There was something to be said for the steam engine yet.

Mr. Bassett said that Mr. Long's paper was particularly interesting to him, because, in his profession of gas engineering, he was brought face to face every week with the competition and the methods of electricians. His experience had taught him the fallacy of looking at things from the point of view that whatever was electric was up to date. He regarded it almost as an intellectual exercise to devise means of doing things by mechanical devices which could be done, no doubt efficiently, by electrical devices. Referring to the electrification of this line, it might have been a success, but he thought it had very largely caught on with the public because they could call it an electric line. In his opinion, to some extent, it was a question of catch-words. One saw these advertisements of "Elevated Electric." Probably if they had got up a similar thing for steam—"Slippery Steam"—with an up-to-date service, as far as the traffic results were concerned, something very nearly approaching the electric results would have been obtained. He thought Mr. Garratt and Mr. Dearberg touched the vital point when they had said it was really a question of cost, and, as far as that was concerned, per-

haps Mr. Long would be able to give them some information. He was rather doubtful because he knew how the department responsible for these returns could very often "manipulate" them. Ultimately, he thought, it came down to the question of steam generation in the power house and steam generation on the locomotive—as to which method was really the more economical.

He should like to ask Mr. Long if he could tell them anything about the losses from the high tension wires, particularly in foggy weather. He knew that static discharges occurred, having seen them himself.

Another question for Mr. Long related to a purely local affair. Perhaps he could tell them something about West Norwood Station. Why was it necessary to have a very annoying dead circuit on the up line while there was no dead point on the down line? These dead points were a considerable annoyance, especially at Victoria.

With regard to acceleration; he left Victoria every evening by the 5.35 and there was a train at 5.36 on the Chatham Line which got away smartly, and the trains came out side by side. By the time, however, they had reached the top of the bank that train was out of sight. It was worked by a Belpaire engine. The engine was worked hard and the men on her worked hard too.

Of course, much had been said about the advantages of electricity as regards speed. He had heard that they were going to get to Brighton in 45 minutes as a regular thing. The speaker understood that it had been done in 47 minutes with steam trains. He should like to know at what speed these electric trains could run and also whether Mr. Long could tell them anything about the revolutions of the motors. Judging from the sound they were running fairly fast.

With regard to safety; suppose a train came off the line—not perhaps a very serious accident to a steam train—but supposing an electric train came off and ran into one of those posts and brought it down, what was going to happen then to the train, to the passengers, and the generating station? He knew that they had a bad time at the sub-stations when these things happened.

Why was it necessary to keep so clear of the bridges and so on in the stations? There was an enormous waste of room at West Norwood. The Brighton Company seemed to like their passengers to walk 40 yards going to the train and coming away from it.

Then Mr. Long had said that he had given time tables

as examples of the improvement that had taken place. The speaker thought that was a very wrong thing to do, because time tables might mean anything or nothing. He had lived in West Norwood all his life, and no one had said a truer word than those people who said the Brighton Railway had totally neglected the suburban service. As far as the Crystal Palace Line was concerned, he had never met anyone who had a good word to say for them in the matter. His opinion was that had they had energy on the part of those responsible with a real desire to get the best out of steam, with new stock, a little paint and electrification of the station staff, as far as the engines were concerned Stroudley's engines could have done it. If they had these things with a revision of the services and a determination to see what steam could do, then he believed the same results could be obtained as were being obtained now on the Great Eastern or on the Chatham Railway, and that electrification—although it might perhaps come ultimately—would be put off for a long time.

With regard to the simplicity of the work of the motor man, the small amount they had to do; personally, he always thought that he would rather be a locomotive driver than sit still and move a handle over a quadrant, and now we saw correspondence in the newspapers *re* the question of monotony of work—why labour was dissatisfied—whether men took an interest in their work or not. He had never yet met a driver who was not interested in his engine, but he doubted whether as much interest was shown by the motor men in their motors. Although sentiment did not rule the world, he thought it played a large part in it.

Mr. Burtt thought the most important question had not been dealt with, and that was this. They were talking about electricity—who was going to pay for it? That he considered was an all-important question. It was all very well to start with a new electrical railway, but when you had got a steam railway and had to convert it, it had got to be paid for. It had to come from the dividends or else fresh capital had to be created. If they did that, that meant less dividends, and he very much doubted if the extra profits were going to pay dividends on the original stock and on the new stock. With reference to Mr. Anelay's remark about the Company not being more progressive in their Locomotive Department, this was a very serious statement to make, as during the last five years large Atlantic type engines had been constructed, also powerful 10-wheeled

tanks, superheating had been adopted, and latterly the famous 4-6-2 engines, "Abergavenny" and "Bessborough," had been built. Also the rebuilding of the smaller 4-4-0 and 0-6-0 types, these engines being provided with increased boiler pressures.

Mr. Gosden said he was connected with the Traffic Department and had been with this electrification from the start—from the commencement of the trial trips. He was entirely in favour of the new kind of traction. He had travelled on the trial trips and one of the great advantages was from the point of view of greater acceleration. They were able to deal with traffic now that they could not have dealt with a few years ago. Then they could not carry the traffic and had delays outside the terminal stations. Now they could deal with much more traffic and many more people and they found the chief advantages in the terminal stations. In the old days one generally found that the engine wanted coal and water. Now you reversed and went right away and another train could come in at once. One of the advantages was that you did not get any dead centres on the electric trains. On some engines, especially on the South Eastern, they nearly always had to reverse before they could get away. The electric trains were always ready under the wires if they wanted a train sharp, and all they had to do was to put the bow up and off they could go, while a steam engine very often had to be got ready. Then, again, there was the reduction of haulage; with steam trains at one time, they were dragging some trains of seven bogies about all day long. They adopted the system with steam trains of dividing them up in units of two. They had a number of divisible trains on the Brighton Railway and they could leave a half at one station and pick it up later on in the day. On the electric trains, however, there was this advantage, that each unit was able to move itself, and, when the busy traffic was over, it was easy to divide them up and run a lighter train.

As regards the speeds attainable by these trains, it was certain that they could go considerably faster with the electric trains if they liked. The question of current consumption was just as much a matter of economy as coal consumption. When he went round with a trial trip before they started the service, they were only twelve minutes from London Bridge to Victoria with four stops. On May 17th they had taken round some of the representatives of the engineers and contractors. They went from the

Crystal Palace to Victoria in 13 minutes. They could have done it in less.

With a steam engine, if it broke down, you had generally to get another engine to run it home. There had only been two occasions when an electric train had not been able to get home by itself. There were four motors, and at least one out of the four would probably be available to haul the train home.

There was one thing which used to happen when the electrification was first started; it was difficult to get the public or the staff to realise the greater speed of the electric trains. If one got to the junction at the same time as the steam train the steam train was given the preference. The difference in the speed was easily noticeable if you were in an electric train and were following a steam train or vice versa.

Mr. Wardlaw said that he had been very much interested in the paper and the discussion generally. Probably there was no one in the room who had had more experience with electric railways than he had. It was over 30 years ago since his experience started with the original railway erected by Mr. Edison in the United States, and followed afterwards up to the installation of electricity for heavy traffic, particularly in the keen competition they had with the steam locomotive on the Baltimore and Ohio Railway. It was well known among electrical men that the locomotives were totally unfit to pull the trains through the tunnel, and they filled the tunnel with obnoxious gases and smoke, whereas the electric system not only pulled the train through, but pulled two locomotives through as well—pulled both engines and the train itself. That was afterwards followed by quite an extended experience in connection with the keen competition between the New York Central and the New York, Newhaven and Hertford Railway, and he wished he had the figures to give them as they would be the very figures Mr. Long in his paper suggested were lacking. One put in the direct and the other the alternating system. Both lines operated through practically the same territory with the same conditions of traffic, and practically the same number of trains per day; and it would be most interesting if he could give them those figures, but he was, unfortunately, never able to get them.

As regards general electric traction, he did not think there was any doubt, for local and suburban traffic, i.e.,

within 20 to 25 miles of any great city, as to the superiority of electricity over steam. For long-distance traffic and heavy freight work, the heavy steam locomotive would always have its place and hold its own. For local traffic there were many reasons why electricity was better—it was much cheaper. It was much easier to burn 5,000 tons of coal in a day in a power station with one or two gangs of men under proper supervision than it was to burn the same quantity of coal divided up all over the line. You could get much more efficiency per pound of coal burnt in a power house than on the locomotives outside. The weather conditions were better dealt with in generating stations than on locomotives, especially in very severe temperatures as experienced in the northern part of the United States. In addition to that, less repairs were necessary with an electric service than with a steam service. You did not have to have the same number of men or the same extent of shops that you had with steam locomotives.

The third rail question had been brought up. The third rail could be so thoroughly protected that there was practically no danger whatever from it. It was not necessary to lay the third rail open as you did the running rail. It could be covered with a hood, and so covered it was in work to-day; and it was impossible to short that rail by throwing a crowbar on it. Even in the event of a coach derailing and falling over, that guard was still strong enough to support the coach and hold it up. There was no danger of killing people from that.

With reference to the alternating current system, the present one as described by Mr. Long—he remembered distinctly when that was brought out by the Westinghouse Co. and largely advertised. With this single phase system you were carrying current at very high tension and the overhead work was very unsightly. In this country it would not be subjected to the same difficulties that it would in the very cold countries, i.e., the ice, snow and sleet of winter, when you would get the lines breaking down.

With reference to the relative costs of the two, it was much more expensive to construct the outdoor work on the high-tension alternating current system than it was on the direct current system. The direct current system could be used for long-distance work very easily by means of high-tension main lines or feeders coming from the power house and sub-stations changing the current from them into low-tension direct lines. There would be no difficulty in doing that.

Mr. Long, replying to the discussion, said he must thank them for the way in which they had received his paper. He had to candidly confess that he thought his arguments and his paper would be torn to pieces in such a hotbed of the steam locomotive as that Institution was. They were proud of the fact that it was, but, none the more for that, he thought they must acknowledge that, for suburban work at any rate, as one or two of the speakers had said, electricity probably would soon become the standard operating power.

To consider the criticisms and queries of the various gentlemen who had taken part in the discussion. To Mr. Suffield he could only say that with the overhead system installed on the Brighton Line the cost of maintenance had so far been comparatively small. It had given practically no trouble whatever, but they must quite understand that, at present, as the Company had published no official figures, it was impossible for him to furnish any such details. He had been in correspondence with Mr. Dawson on that point and he had no doubt that, when the paper was published, an appendix, at any rate, might be attached, giving some figures on the subject, but, until official acquiescence was forthcoming, then, manifestly, it was not for him to make any announcement in regard to it. He knew, however, that the cost of operating the electric service had been found to be very considerably below that of steam. They must take that as a general statement, but, nevertheless, it was a fact.

With regard to the question of insulators, there was, perhaps, no other detail of the equipment which had been subjected to such searching experiment. By suspending the insulators over the chimney of a steam boiler stoked to produce heavy smoke flash-over tests to 20,000 volts had been effected. The insulators are of porcelain and are subject only to the stress of compression. All types of insulators were tested, and the pattern adopted was, he thought, well known, being solely the corrugated spool type, and of that only three sizes were necessary for the whole of the electrical equipment. In the circumstances no comparison in general use could be mentioned. He might, however, add that the live and earthed parts are connected through the centre of the insulators.

Mr. Anelay happened to have quoted a criticism of his (the speaker's) in regard to what the Brighton Company had done—the words which that gentleman repeated from the magazine—being a commentary he himself had written in the preliminary stages of the electric developments. As

a brief rejoinder to Mr. Anelay's remarks he could think of nothing better than to repeat the words of an official of the Brighton Railway's Traffic Department. He put it to him (the official) as to why it was the electric service was being extended so soon after the original installation. The reply was, in a few words, simply this, "We can get the Electrical Department to do anything in the matter of timing, but we cannot get it from the Loco." If there was any fault at all, it rested with the Locomotive Department of the Brighton Company. They could not deny the fact that the exceptional accelerating power and the general adaptabilities of the electric service were undoubtedly superior to steam. By the figures he had given them he hoped some indication of this fact had been made quite clear. They were, however, merely observed in the course of ordinary working. The special tests which the Company had made on the South London Line were more or less privileged, but he understood the results were far superior to any figures he had given them.

Now as regards the noisy motors, there was no doubt that when the service was instituted, reasonable complaint might have been made with regard to the noise made by the motors, but Mr. Anelay must surely have been frightened away from the motor coaches during that period and not tried them since. Their newness was partly a contributing factor, but the attention they have since received had considerably improved their running, and there was little difference at the present time between the running of the motor coaches compared with the trailers. He avoided the motor coaches himself for some considerable time, but he now made no distinction in choice, whether he travelled in a trailer or a motor coach.

As to the lighting in the electric stock, each compartment is provided with four 10-c.p. lamps, and the lighting of the Company's steam trains was in many cases equal in this respect with the electric stock, and, moreover, they were not liable to the disadvantage of occasional darkness.

He was really glad to hear from Mr. Anelay that there was some advantage in the accelerating power of the electric trains. An admission like that confirmed much that he had said, and was, indeed, the advantage which electrical engineers were most insistent about.

Mr. Fullager had asked the reason for the adoption of the single phase system. There was no doubt at all that the eventual outcome intended was the electrification of the main line to Brighton. It was a matter of perhaps only a

few short years now, and, for that reason, the advisers of the Company felt that there was no alternative. He did not think anyone in that room would contend that the continuous current system would be economically or practically capable of the high-speed work necessary for a 40-minute run from Brighton to London. He believed that was the hoped-for schedule to be maintained by the electric service when instituted.

The disadvantage arising from the application of the single phase system because of the weight of the coaches was an obvious one, but the electrical equipment itself was not a serious dead-weight—only 19 tons—compared with a locomotive, when you had anything between 40 and 60 tons on the metals. He believed the latter was less than the weight of Mr. Marsh's latest suburban tank engine.

The remarks he had made with regard to cost must satisfy Mr. Garratt for the time being. It was all very well to argue that steam trains could be run at a cost of 10d. per mile, but if you were running those trains empty, what was the good of them? They were earning nothing. Assuming the electric trains were costing 1s. 8d. per mile—a statement, however, he was obliged to controvert—and you had a full complement of passengers, which was better? There was no doubt that the electric service had a big advantage in the nett result financially.

He really could not agree with Mr. Dearberg that the Brighton Company did not possess suitable engines for accelerating. He regarded the late Mr. Billinton's 0-6-2 type as ideal engines for such work. It was certainly significant that those 0-8-2 engines Mr. Dearberg had referred to, and designed for the purpose of quick acceleration, which were tried by the Great Northern, had all been withdrawn from the London suburban service. If they had fulfilled their mission in suburban London, why had they sent them down to the country for the haulage of heavy coal trains? It was obviously impossible to suggest that success had attended the use of these engines. They weighed somewhere between 70 and 80 tons, and surely this was one reason they were withdrawn by the Great Northern from the London district, apart from the fact that in accelerating qualities they had not come up to expectations. It required much strengthening of overline bridges to carry engines of that description, and if they were going to improve the steam service by such means, they must also reckon the cost of strengthening the road as against installing a light

electric train and its necessary equipment. Mr. Dearberg had also stated that the acceleration was not satisfactory on the Brighton service. Well, the electric trains were not being pushed for all they could do. "Economy in working" was a guiding principle with the Electrical Department. They were running the trains as cheaply as they could, consistent with efficiency, and any disposition on the part of the men to waste the current was strictly discountenanced. Certainly, further acceleration would be possible if desirable, but the trains were quite fast enough to render the railway journey times immeasurably superior to the tram and motor-bus times. He had estimated that the present journey schedules could be cut from three to four minutes from what he had personally observed. The synchronous speed of the motors is about 750 revolutions per minute. A derailment was at any time inconvenient, and although, unhappily, such events were to be anticipated with the best managed railways, the electric train was no worse off than the steam, and because of its weight less difficult to handle. In the event of mishap the current was automatically cut off, and safeguards against danger existed at all sub-stations, as he had pointed out.

Referring to the dead section on the up line at West Norwood and the live line on the down side, he thought Mr. Bassett would find a difference in level between the up and down lines. It was a matter of inches, but still it was there, and it enabled a live line to be got in with the requisite head room on the down side. Efforts had been made to lower the up road sufficiently, but without success. Mr. Bassett mentioned a comparison of the running of the 5.35 p.m. Brighton and the 5.36 p.m. Chatham out of Victoria. Well, he did not think there was very much in that, as the gradients on the South Eastern side were rather easier than the Brighton, and the South Eastern trains 50 per cent. lighter. Only last Thursday he happened to go down by the 3.10 p.m. electric from Victoria. They started from parallel platforms with the 3.10 p.m. ("Southern Belle"), which had about five seconds start of them. The "Southern Belle" was drawn by the latest production from Brighton, No. 326, and they simply walked away from it and were standing in Clapham Junction 15 secs. before the main line 3.10 p.m. passed. He thought that might help them to decide between the relative merits for accelerating and climbing steep gradients. (Mr. Garratt here inquired as to the weights). The comparative weights, he thought, were in favour of the electric train, because the "Southern Belle"

only had four cars on, say 160 tons, whereas there was the full six eights on the electric train.

The highest officially recorded speed at present by the electric trains, he thought, was 50 miles an hour on the South London Line. They must realise that the lines on which running tests had been made were not suitable for fast working, but undoubtedly, if it were desired, even with the present stock—although not suitable itself for high-speed traffic—they could exceed the maximum he had mentioned. The approximate consumption of energy during 1911 had been 8,220,000 units for a train mileage of 762,000 miles. At a measured test on the South London Line the non-stop run from terminal to terminal was performed in 14 mins. 8 secs., and the energy recorded at Denmark Hill as having been used was 42 units.

He had been found fault with for producing the time-tables as a test. Well, he hoped he had been impartial. He had endeavoured to be strictly fair, and had indicated where steam had the advantage or the disadvantage, compared with electricity.

The capital which Mr. Burt mentioned as being necessary was all new so far as the Brighton Line was concerned. None of this work had been paid for out of revenue, and the fact that the dividends were in no way diminished by the new issues demonstrated the fact that from the shareholders' point of view as well as that of the general public the experiment had been crowned with success.

He must really thank Mr. Gosden and Mr. Wardlaw for their remarks. He thought they bore out very largely what he himself had attempted to explain. There was much more to be said for the electrical service. He could not go into further details, as time was already pressing, but in conclusion he could not help venturing to express a hope that the Brighton Railway authorities would see their way to apply the same creditable principles of operation of their lines still worked by steam, as applied to the electric sections, and he felt sure the result would abundantly justify the experiment. He must again express his thanks for the patient hearing with which his remarks had been received.

CRYSTAL PALACE—VICTORIA (L.B. & S.C. RAILWAY).

AVERAGE ELECTRIC AND STEAM TIMES BETWEEN STATIONS.

	Distance.	Electric Time.	Steam Time.
	MLS. CHS.	MINS. SECS.	MINS. SECS.
Crystal Palace—Gipsy Hill ...	59	1 49	2 20
Gipsy Hill—West Norwood ...	74	2 5	2 16
W. Norwood—Streatham Hill	1 23	3 11	3 23
Streatham Hill—Balham ...	1 4	2 20	2 35
Balham—Wandsworth C. ...	48	1 33	1 52
Wandsworth C.—Clapham J.	1 27	2 51	3 1
Clapham J.—Battersea Park	1 34	3 2	3 19
Battersea Park—Victoria ...	1 24	3 25	3 27
		20 16	22 13

NOTE.—Only Station to Station runs, free of signal checks and P.W. delays, are included in foregoing table.

STATION WORKING.

Station.	Electric Average time.	Steam Average time.
	SECS.	SECS.
Battersea Park	23.01	30.1
Clapham Junction	40.9	69.04
Wandsworth Common	20.0	39.08
Balham	24.1	41.3
Streatham Hill	30.9	44.8
West Norwood	19.0	30.9
Gipsy Hill	20.7	36.4

NOTE.—Delays arising from signals at stations not included in above table.

STEAM AND ELECTRIC WORKING (L.B. & S.C. RAILWAY).

VICTORIA TO CRYSTAL PALACE.

(Typical Examples observed by the Author.)

STEAM.

Engine : 0-4-2 tank ; weight 38 tons 10 cwt.
 Load : 7 eights ; 145 tons.

ELECTRIC.

Motors : Large Type, 38 tons.
 Load : 6 eights, 150 tons.

RUNNING TIME.

RUNNING TIME.

	Between Points. mins. secs.	Point to Point tms. secs.	Between Stations. mins. secs.	Station working. secs.	Between Points. mins. secs.	Point to Point secs.	Between Stations. secs.	Station working. secs.
Victoria dep.	0 0				0 0			
Platform End	0 52				0 43			
Grosvenor Bridge (North End)	2 5	73			1 39	64		
(South End)	2 31	26			2 1	22		
Battersea Park arr.	3 36	65	3 36	34	3 4	63	3 4	20
1 m. 24 chs. dep.	4 10				3 24			
Mile post $1\frac{1}{4}$ pass	5 7	57			4 4	30		
„ $1\frac{3}{4}$ „	5 41	34			4 28	24		
„ 2 „	6 5	24			4 51	23		
„ $2\frac{1}{4}$ „	6 28	23			5 14	32		
Clapham Junction arr.	7 25	57	3 15	60	5 46	32	2 22	30
2 m. 58 chs. dep.	8 25				6 16			
Mile post 3 pass	9 31	66			7 10	54		
„ $3\frac{1}{4}$ „	10 8	37			7 40	30		
„ $3\frac{1}{2}$ „	10 42	34			8 6	26		
„ $3\frac{3}{4}$ „	11 15	33			8 32	26		
„ 4 „	11 47	32			9 0	28		

Wandsworth Common ...	arr.	{ 12 0	13	3 35	28	{ 9 17	17	3 1	21
4 m. 7 chs.	dep.	{ 12 28				{ 9 38			
Mile post $4\frac{1}{2}$	pass	{ 13 15	47			{ 10 18	40		
" $4\frac{1}{2}$	"	{ 13 59	44			{ 10 50	32		
Balham ...	arr.	{ 14 33	34	2 5	26	{ 11 19	29	1 41	19
4 m. 55 chs.	dep.	{ 14 59				{ 11 38			
Mile post $4\frac{3}{4}$	pass	{ 15 27	28			{ 12 1	23		
" $5\frac{1}{4}$	"	{ 16 12	45			{ 12 31	30		
" $5\frac{1}{4}$	"	{ 16 52	40			{ 13 0	29		
" $5\frac{1}{2}$	"	{ 17 29	37			{ 13 31	31		
Streatham Hill ...	arr.	{ 17 59	30	3 0	62	{ 14 0	29	2 22	23
5 m. 59 chs.	dep.	{ 19 1				{ 14 23			
Mile post 6	pass	{ 19 22	21			{ 14 30	7		
" $6\frac{1}{4}$	"	{ 20 1	39			{ 15 58	28		
" $6\frac{3}{4}$	"	{ 21 3	62			{ 17 6	68		
West Norwood ...	arr.	{ 21 17	14	3 16	31	{ 17 23	15	3 0	15
7 m. 2 chs.	dep.	{ 21 48				{ 17 38			
Mile post $7\frac{1}{4}$	pass	{ 22 47	59			{ 18 34	56		
" $7\frac{1}{2}$	"	{ 23 12	25			{ 19 4	30		
" $7\frac{3}{4}$	"	{ 23 44	32			{ 19 26	32		
Gipsy Hill ...	arr.	{ 24 18	34	2 30	26	{ 20 1	25	2 23	17
7 m. 76 chs.	dep.	{ 24 44				{ 20 18			
Mile post 8	pass	{ 25 4	20			{ 20 33	15		
Crystal Palace ...	arr.	{ 26 46	102	2 2		{ 22 17	104	1 59	
8 m. 55 chs.									

VICTORIA & LONDON BRIDGE (SOUTH LONDON LINE) SECTION.

DIAGRAM OF LINE CURVATURE
Figures refer to Radii of Curves (in Chains)

DIAGRAM OF LINE CURVATURE
Figures refer to Radii of Curves (in Chains)

VICTORIA STATION.

PECKHAM RYE REPAIR SHOP.

LONDON BRIDGE YARD.

OVERHEAD CONSTRUCTION, STREATHAM HILL STATION.

MOTORMAN'S DRIVING GEAR.

BETWEEN BALHAM AND STREATHAM HILL.

CANTILEVER CONSTRUCTION, POUPART'S JUNCTION,

THREE-COACH TRAIN.