Associate Members—continued.

DOUGLAS SINCLAIR SHAW.	WILFRED THOMAS WALKER, Stud. Inst. C.E.
FRANCIS STAFFORD SMITH, B.Sc. (Engi- neering) (<i>Lond.</i>)	EMRYS JOHN WHELDON, B.A. (<i>Cantab.</i>)
STANLEY PARKER SMITH, D.Sc. (<i>Durham</i>).	WILFRID EDWARD YOUNG, Stud. Inst. C.E.
NEWBOLD CROFTON STAVELEY.	AUGUSTUS JULIUS RANELAGH DE ZOYSA.
ANDREW LOWE THOMAS.	
ROBERT URE, B.Sc. (<i>Glas.</i>)	

Associate.

JOHN SYMONDS.

(Paper No. 3962.)

“Reinforced-Concrete Wharves and Warehouses at Lower Pootung, Shanghai.”

By SOMERS HOWE ELLIS, M. Inst. C.E.

THE works to be described are situated on the Whang Poo River, close to Shanghai, in Northern China. Shanghai itself lies entirely on the north-west bank of the Whang Poo, which is, properly speaking, a tidal creek, about $\frac{1}{2}$ mile wide at this point—15 miles from the River Yangtze and about 50 miles from open sea. The district of Pootung lies on the opposite side of the river, and consists merely of a line of detached wharves with sheds or warehouses on the strip of bank between them and the cultivated land behind, having no land communication except by native footpaths. All goods have consequently to be lightered to and from the wharves.

The property in question belongs to Messrs. Alfred Holt and Company, of Liverpool, and the wharves and warehouses constructed thereon are for the use of their steamers plying between England and the Far East, Shanghai being an important port of call and of transhipment for the North China coast and the River Yangtze.

The works consist of, first, a reinforced-concrete skeleton wharf on piles of the same material; secondly, a reinforced-concrete quay-wall alongside a tributary creek; and thirdly, two four-story warehouses constructed in reinforced concrete with brick panel walls. There are in addition a three-story building for offices, staff quarters, etc., three single-story steel sorting-sheds, and finally a power installation of gas-producers, engines, and dynamos, for providing light and power throughout the property. These are all shown in Fig. 1, Plate 1.

The only real difficulty in connection with the works arose from

the nature of the foundations. The whole neighbourhood of Shanghai is founded on river-silt, deposited in past ages by the Yangtze, and extending to an unknown depth. Borings more than 400 feet deep have been made, which have penetrated nothing but mud of various degrees of solidity, except for layers of impure sand at irregular intervals, a thin intermittent bed of gravel at about 300 feet, and a more regular bed of gravel at a little more than 400 feet from the surface. The top layer of ground, averaging 25 feet in thickness, may usually be reckoned upon to form a solid crust of stiff, sandy clay, though rendered irregular on its surface by the presence of old creek-beds, filled with softer mud. Dependence must therefore be placed on this upper layer of firm ground for bearing superincumbent loads.

The means adopted in the works under consideration were of two kinds; in the case of the wharf, quay-wall, and lighter buildings, the load was borne by groups of piles, supported by skin-friction of the mud on their sides; in the case of the warehouses a raft of reinforced concrete covering the entire area of the foundations carried the weight of the building without assistance from piles.

WHARF.

The wharf, 1,160 feet long on the face and 174 feet wide, has on the river side 21 feet at low water of ordinary spring-tides (Figs. 2, Plate 1). It is assumed that the frontage can be dredged to a slope of 3 to 1 from the face of the wharf down to 24 feet 6 inches, when required.

The piers of the wharf are 15 inches square and spaced 15 feet from centre to centre in each direction: each is supported on a group of four 14-inch piles. Girders run across the wharf from side to side over each row of piers, and support a system of cross beams, spaced 5 feet apart between centres, and a continuous reinforced-concrete deck 5 inches thick. At the front of the wharf two heavy longitudinal beams run from end to end, to carry the rails of a standard-gauge road for a 5-ton crane. The pier-bases (or pile-caps) are connected both longitudinally and transversely by horizontal members, the wharf being further stiffened by a system of diagonal bracing from front to back at each row of piers, and also longitudinally for the last two bays at each end.

Over the greater part of its length the wharf is covered in up to 52 feet from the face, by sheds of steel and corrugated iron, the piers which carry the stanchions for these being borne by a larger number of piles. In line with the front of the shed a training-wall of reinforced-concrete sheet-piles is provided through-

out the length of the wharf, and is continued upwards to above high-water level by a curtain of reinforced-concrete slabs; this acts as a retaining-wall to the silt.

The deck of the wharf is designed to carry a load of 500 lbs. per square foot (so as to bear safely heavy concentrated weights), and the general structure a deck-load of 350 lbs. per square foot. This brings an approximate maximum load of 11 tons on each pile. It was realized from preliminary tests that according to no recognized formula for pile-driving could an apparent factor of safety be obtained, as the set of the pile under each blow of the hammer (provided that driving was continuous) lessened very little after an average penetration of 15 feet, and sometimes tended to increase after a penetration of 25 feet. The Author was convinced, however, that the supporting power of the mud was comparatively high when time was given for the film of water between it and the pile to escape and conditions of true skin-friction to obtain; and an arbitrary figure of 5 cwt. per superficial foot of the pile, exclusive of its own weight, was fixed as its maximum bearing-capacity.

The piles were driven by a steam pile-driver, which gave a rapid succession of blows with the falling weight of a $3\frac{1}{2}$ -ton hammer dropping 6 to 8 inches. The weight of the cylinder, etc., rested on the pile in the meantime, with a steady weight of $1\frac{1}{2}$ ton. A final set of 1 inch per blow was usually obtained, and no anxiety was felt as to the future stability of the majority of the piles. In some places, however, much softer mud was encountered. As an extreme case, in one pier the piles sank rapidly under the steady weight of the hammer and cylinder, without any driving, and had to be checked by holding up this dead weight when they were at the required depth. This was naturally felt to be unsatisfactory, and after a lapse of 1 month the four piles of the group in question were tested with the maximum load of 45 tons, under which they settled $1\frac{3}{4}$ inch in a fortnight, coming to rest at the end of that time. They were afterwards lengthened 8 feet and driven further. For the first eighty blows of the hammer, at the start of this operation, the pile struck did not move. After this, when the adhesion between the mud and the pile was broken, it went down with ease, though not actually without driving, as it had done before. A subsequent test on the group of piles showed a total settlement of $1\frac{1}{2}$ inch under the load of 45 tons, so that it was decided not to be worth while to lengthen and redrive any more piles. This group showed results worse than any other, both while driving and under the test-load; and as the

actual conditions of loading, when the wharf was finished and braced together, would be much less severe on any one pier, there was not felt to be much cause for anxiety.

The most favourable anticipations have so far been realized by the behaviour of the wharf in practice, when it has been subjected to the test of having considerably more than the estimated maximum load stacked upon it locally, without any appreciable settlement or sign of distress in the superstructure.

The piles shown in Figs. 6 were moulded in a horizontal position, and a period of 2 months was specified for maturing, but in warm weather some were driven 6 weeks after being moulded, without ill effect.

No iron or steel helmet was used for driving. A thin piece of pine board was placed directly on the head of the pile; on this a $\frac{3}{8}$ -inch steel plate, and above that again a piece of hard wood, 4 inches thick. An ordinary short timber dolly received the actual blows of the hammer. Great care was taken to keep both the pile and the guides of the driver in an absolutely vertical position, so as to strike each blow squarely on the pile-head. The pile ran in the guides between rubber-covered rollers packed with thin pine battens which travelled downward with it, and prevented any lateral movement. The heads of the piles were in most cases unbroken by driving; and in no instance did the damage exceed a chipping off of the top corners.

With the exception of the pile-caps, beams, and deck, all the wharf-members were moulded on shore, thereby avoiding for the most part the unsatisfactory operation of concreting below high-water level. For erection, a timber platform was clamped firmly on to the heads of each group of piles at the level of the base of the caps, allowing the heads of the piles to project through, from which the concrete was then cut away, leaving the steel rods bare. The horizontal bracing running parallel to the length of the wharf was then laid in position, the ends of these longitudinals resting (on packing-pieces) on the timber platforms clamped to the pile-heads. The longitudinal members then served as a support for the whole of the temporary staging from which the rest of the superstructure was erected.

The steel rods projecting from the ends of the various horizontal, diagonal and vertical members overlapped or were hooked round each other within the area of the pile-caps, which were then concreted in situ, forming a rigid connection to the piles, bracing, and columns. This concrete was run into place down inclined shoots at low tides, and was well worked among the reinforcement with steel

rods. At neap-tides on the Whang Poo River the ebb lasts for about 8 hours, and low water for 3 or 4 hours, so that there was ample time to concrete six to eight caps during a daylight tide; and, when covered with mats, the partially-set concrete suffered no damage from the next flood.

When a quarter of the length of the wharf was so far completed in this way, wooden moulds for the girders, beams, and deck were set over the entire area of one-eighth the length of the wharf—about 26,000 square feet. The reinforcement was then placed in position for successive strips two bays (30 feet) in width across the wharf, and concreting was carried on so as to complete this section of the structure entirely in a continuous series of working-days. The surface of the deck was sloped downwards towards the centre of each square 15-foot bay, where a drainage-hole and grating were provided. The wharf was completed for use by the provision of a system of creosoted Oregon-pine fender-piles, walings, and caps along the face, bolted into the concrete at deck and lower-boom level.

The moulding of piles for the wharf was commenced on the 16th January, 1908: driving was begun on the 2nd April and completed on the 31st December of the same year, 4,023 piles having been driven in that period. Some delay was then caused by the driving of sheet-piles for the training-wall, and the first pile-caps were not concreted until the 20th March, 1909. Concreting of the deck was commenced on the 10th June and completed on the 20th July, 1910, a period of $2\frac{3}{4}$ years being thus occupied in the whole construction. The fitting of fenders, bollards, etc., was finished 3 months later, and the erection of the sheds about the same time.

The climate of Shanghai is marked by extremes of temperature, from tropical heat in summer to frequent sharp frosts in winter.

The part of the wharf-deck which was concreted during the summer of 1909 developed a series of hair cracks along the centre of each alternate bay (i.e., 30 feet apart), across its full width, during the succeeding winter; the positions of the cracks coinciding roughly, though not exactly, with the places where work had ceased for the day. Many of these cracks went through to the underside of the deck, and water was observed to ooze through them after rain. They were subsequently cut out, $1\frac{1}{2}$ inch deep, and a straight open joint was formed in the concrete surface which was run with hot asphalt. The reinforcement, where exposed by this operation, was nowhere corroded; indeed, at the end of 1911 no signs of rust-stains were visible anywhere on the superstructure or pile-heads of the wharf.

QUAY-WALL.

The bank of a tributary creek forms the eastern boundary of the property, and berthage-space for lighters was required here.

The present wall, 495 feet in length, was constructed of concrete throughout (Figs. 7 and 9, Plate 2). It is founded on cross rows of three 12-inch square piles, of which the front row serve as king-piles to a continuous line of sheet-piles (Figs. 6, Plate 2), which forms the face of the wall up to a height of 12 feet below quay-level. The heads of the piles are connected by a deck 14 feet wide, above which the wall consists of a nearly vertical slab tied back to the deck by a series of triangular counterforts.

Stability against overturning is secured by the weight of the filling—dry earth, rammed in layers—on the deck, plus the anchoring hold of the back piles, it being assumed in the calculations that the cross-sectional area of the earth and concrete within the limits of the piles and counterforts may be taken as one solid mass, with their combined weights acting together in one vertical plane determined by their several positions.

The original design for the wall showed a series of anchor-ties from the coping back to the foundation-piles of the shed immediately behind it. Before these were put in, however, it was necessary to back up the wall, and for this purpose earth was removed from the front down to low-water level. Just as this operation was completed a slight forward movement of the wall was detected, amounting to a maximum of $2\frac{1}{2}$ inches at coping level at the centre of its length, and apparently extending downwards to the piles without much diminution. The earth backing was at once taken out and dumped again in front of the wall, which went back in the course of a few weeks to within $\frac{1}{2}$ inch of its original line. A crack in the ground had also appeared, about 40 feet behind the coping-line; and as it was evident that the whole stratum behind the wall was in an unstable condition, it was decided to put in anchorage-ties, attached to the wall at deck level, instead of coping level, and extending back to the foundation-slab of the warehouse, where they were held by the ends of the foundation-beams. These ties are formed of four steel rods, $1\frac{3}{8}$ inch in diameter, overlapping 2 feet 6 inches at the joints, bound with wire ties and struts, and encased in concrete to a finished size of about 15 inches square. The attachments at either end are made by the hooked ends of the rods fitting round links of $1\frac{5}{8}$ -inch bars, securely fastened into the wall and the warehouse foundation. A flexible joint at these places is secured by encasing

the steel in a 1-to-1 mixture of asphalt and sand, instead of the usual concrete protection.

Before replacing the backing to the wall a continuous rubble drain was formed behind the back of the deck, and no further movement of the wall has been detected.

After completion of the reinforced-concrete work, creosoted Oregon-pine fender-piles and walings were bolted to the face opposite each counterfort. Cast-iron mooring-posts in concrete blocks were also provided about 60 feet apart.

WAREHOUSES.

The two warehouses (Fig. 1, Plate 1, and Figs. 8, Plate 2) have four stories and a flat roof, each floor being designed to carry a superficial load of 500 lbs. per square foot throughout its area. The entire structure is of reinforced-concrete except the panel walls, which are of brickwork 15 inches thick. The roofs have an external waterproof covering.

Two pairs of electric lifts are installed on the outside of each warehouse. In the alley-way between the two a system of stairways is provided up to each floor, in view of the prevailing Shanghai practice of carrying goods by means of coolies up to any height or to any distance. The stairways lead to cantilever landings which afford access to both warehouses at the one level. The effect is that of bridges at the head of each stair; but, in order to allow for unequal settlement of the warehouses, the landings are cut at the centre and supported on brackets, which are a continuation of the floor beams on either side.

The chief point for remark in the design of the warehouses is the foundations, wherein special measures had to be taken on account of the heavy load and the yielding nature of the ground. Assuming the floors to be all fully loaded—an extremely unlikely contingency, but one which was reckoned on in calculating the maximum loads—the interior columns, spaced 20 feet from centre to centre in each direction, would bring a load of about 400 tons on to the base of each. Considering the small load which piles can bear safely in this ground, their provision in sufficient numbers to be of much service would have involved unjustifiable expense. Under favourable circumstances the ground around Shanghai will bear a maximum load of 1 ton per square foot without undue settlement; and weighting tests, carried out on the site of the warehouses, tended to show the correctness of this estimate locally. The expedient adopted in order that this figure should not be exceeded was

to form one foundation-slab extending over the whole area of each building, and some distance (actually 7 feet from the column-centres) outside it reinforcing the slab to such an extent that the space between the various points of bearing should be capable of resisting the upward thrust of the ground; also that in the event of any isolated tendency to excessive settlement the load should be distributed between any three adjacent bays to an extent sufficient to prevent cracking of the concrete. This raft is shown in Figs. 8 and 10, Plate 2.

In the neighbourhood of Shanghai settlement occurs in all structures of any weight, and the buildings under consideration are no exception. Taking the pair of warehouses together, they form one block 314 feet by 239 feet in area, with their foundation-slabs so near together as to act as one in affecting the stratum of ground at the depth (probably up to 50 feet) where compression takes place. The total settlement during the last 6 months of construction and the year after completion of the buildings has amounted to about 14 inches at the two centre points of the area (half way along each warehouse on their inner sides), and 10 to 12 inches at the four outside corners: showing clearly the wave-like subsidence of the strata compressed.

Owing probably to the strength and elasticity of the foundation slab, no cracks or other sign of distress have appeared anywhere in the concrete structure. The inward tilt of the buildings has not exceeded 1 inch in a height of 64 feet. It is probable that settlement, though now nearly stopped, may continue for some years; but it is not anticipated that practical inconvenience will be caused thereby.

One curious feature of the movement is that the buildings have closed bodily together, to the extent of about 1 inch, probably owing to alternate expansion and contraction on a base not now truly horizontal.

OFFICE BUILDING.

Near the warehouse is the office building (Fig. 1, Plate 1), a three-storied structure of similar character to the warehouses but on a lighter scale. It is carried on piling, a maximum load of 11 tons per pile, as in the wharf, being allowed. There is, in addition, the bearing-capacity of the concrete slab, which is a more indeterminate quantity.

In contrast with the behaviour of the wharf, some subsidence of this building has taken place, amounting to about 3 inches in all, and a slight irregularity of settlement of the wave-like character already referred to, though not sufficiently marked to cause anxiety.

CONCRETE.

The concrete throughout is composed of 1 part Portland cement, 2 parts sand, and 4 parts beach-gravel, except for the foundations of the buildings, where the proportions are 1 : $2\frac{1}{2}$: 5.

The cement was obtained chiefly from Heidelberg, about 2,000 tons only being supplied from England in the early stages of the work. In all cases it was tested on the site for tensile strength, etc., according to the British Standard specification, to which all consignments were found to conform without aeration.

A number of compression tests were also carried out on 8-inch cubes of concrete taken from the mixer on gauging, so as to obtain a periodical record of the material actually used in the work. The following results were obtained from three series of successive tests on concrete of 1 : 2 : 4 mixture :—

Series.	Number of Samples.	Average Crushing-Strength in Lbs. per Square Inch.				
		28 Days.	56 Days.	84 Days.	168 Days.	1 Year.
1	45	2,165 (26 tests)	2,581	2,811	3,070 (19 tests)	..
2	56	1,923	..	2,540	3,333	..
3	32	2,251	..	..	..	4,137

In the second series the cubes were kept covered with damp sand, in the others they were exposed to the air (in the shade).

The gravel was screened twice, so as to exclude all material retained on a $\frac{3}{4}$ -inch sieve or passing through a $\frac{1}{8}$ -inch sieve. The large stones were afterwards broken by hand, and mixed with the selected material. Fine material obtained from the screenings of the gravel was mixed with the sand in the ratio of 1 to 2, as this mixture was found to give a higher compressive strength than when the normal sand was used alone.

Two mechanical mixers of a German type, installed side by side, coped with the whole work. Each charge contained a weighed portion of cement and corresponding measured volumes of sand and gravel (the actual proportions for 1 : 2 : 4 concrete being 188 lbs. of cement, 3·76 cubic feet of sand, 7·52 cubic feet of gravel), so as to make up the contents of a Decauville skip, in which it was afterwards conveyed to all parts of the site. Revolving arms in the barrel of the machine stirred the materials, at first dry, and then with the admixture of sufficient water (varying with the temperature) to

produce a concrete which would just flow when tipped on to the wooden platforms close to the work. It was conveyed from these by hand in rectangular buckets. All labour was performed by Chinese coolies, under the supervision of German foremen on the part of the contractor, and English inspectors on that of the engineer. When trained to the work the Chinese became thoroughly competent, and the concrete was, as a whole, of a highly satisfactory appearance when stripped of the moulds.

REINFORCEMENT.

The greater part of the steel in the reinforcement is in the form of plain round bars and wire ties. Expanded metal, of $\frac{1}{4}$ inch by $\frac{3}{16}$ inch section and with a mesh 3 inches across, is used for all floors of buildings, and for the deck of the wharf; and a certain proportion of angle-bars, flat-bars and Kahn bars in the wharf-girders and beams, as shown in Figs. 4-6, Plate 1, and Figs. 9-14, Plate 2.

The steel was specified to be capable of bearing a tensile stress of between 60,000 lbs. and 70,000 lbs. per square inch, with an elongation of not less than 20 per cent. in a length of 8 inches. In making the calculations¹ a working-stress of 16,000 lbs. per square inch was allowed in tension, and in compression fifteen times the stress on the concrete with which it was in contact, up to a maximum of 12,000 lbs. per square inch. A maximum stress of 530 lbs. per square inch in compression and 55 lbs. per square inch in shear was allowed on the concrete of girders and beams, and a compressive stress of 450 lbs. per square inch on the concrete of columns with plain-tie reinforcement, taking into account the whole cross-sectional area. In the case of the hooped warehouse-columns shown in Figs. 13, Plate 2, a maximum stress of 1,200 lbs. per square inch on the concrete within the hooping is calculated upon, neglecting that outside. It was important to keep the size of these columns within moderate limits; and, in view of the heavy load on those from the ground to the first floors, the only alternatives were to have steel stanchions encased in concrete, or to adopt this system of hooped reinforcement, with heavily stressed concrete confined within it. As described hereafter, five experimental columns, 10 inches in diameter, were made in accordance with this design, and tested to destruction before the warehouse-columns were actually commenced;

¹ The methods of working out the details of design are those given in Messrs. Marsh and Dunn's work, "Reinforced Concrete."—S. H. E.

and it was apparent from these tests, as from those made elsewhere, that a sufficient factor of safety was obtained.

The interior first-floor columns (Figs. 13) are designed to carry a maximum load of 376 tons. They are octagonal in section, and the $2\frac{1}{4}$ -inch vertical bars are kept in place by a series of inner circular bands to which the vertical rods are fastened by means of U bolts. The outer hooping is a continuous rod $\frac{1}{2}$ inch in diameter, wound spirally with a pitch of $2\frac{3}{4}$ inches. The operation of winding was effected by fixing the skeleton of main bars (bolted on to the spacer bands) in a horizontal position, free to revolve about its axis, with the end of the hooping fastened to it at one extremity. It was then turned by hand-bars inserted in the skeleton, while the $\frac{1}{2}$ -inch rod was fed forward through a check which left the requisite tightness on the finished hooping.

The second and third floor interior columns are similar in design, but of lighter section and reinforcement. The roof-columns are of ordinary rectangular section, with wire ties 6 inches apart.

All exterior columns above the first floor are reinforced in the latter method, continuous spiral winding, with its accompanying high unit stress on the concrete confined within it, being only necessary here below this level. The interior columns of the first three floors are protected from accidental injury by being encased in $\frac{1}{8}$ -inch steel plates up to a height of 6 feet. The roof-columns are fitted with angle-bars at the corners for the same purpose.

In calculating the strength of beams and girders partial continuity was assumed, the positive bending-moment for inner spans being taken as $Wl/12$, and that for outer spans as $Wl/10$, compared with $Wl/8$ for freely supported beams. Care was taken to reinforce amply those parts of the structure in which a negative bending-moment due to continuity might involve high stresses.

All steel was covered with $1\frac{1}{2}$ inch of concrete, except in the case of floors, where this dimension was reduced to 1 inch. In structural members exposed to the weather a cover of 2 inches was given in almost all instances. The absence of rust-marks on the concrete surface of the wharf, and the fact that wherever bared the steel is clean, seem to show that this coating of good dense concrete is an entire preventive of corrosion, even when the structure is alternately wet and dry. The Whang Poo River at Shanghai, however, is of fresh water, not salt, though under tidal influence.

Especial care was taken, both in designing the systems of reinforcement and in preparing the steel skeletons, to ensure that all steelwork was rigidly fastened together, and in its proper position with reference to the moulds, before concreting was com-

menced, with no loose parts to be omitted by accident, or knocked out of place during the process of ramming the concrete. With this end in view, the wharf-girders, which run across the structure every 15 feet, are reinforced with what is in effect a pair of light skeleton girders, built up of $2\frac{1}{2}$ -inch angle-bars at the top, and of $2\frac{1}{2}$ by $\frac{5}{8}$ -inch flat bars at the bottom, shear members being riveted to them, as shown in Figs. 6, Plate 1. The additional steel required in tension is supplied by two $1\frac{1}{4}$ -inch round bars, one turned up over the points of support, and the other bent down to reinforce the concrete in compression at the same points.

For convenience in working, the contractors assembled and riveted together on shore the whole 168-foot length of each of these framed skeletons, afterwards carrying them bodily by a line of coolies into place on the wharf. Under other conditions of labour, it would be easier to build them in short sections, riveting up the cover-plate joints (which are spaced at points of minimum stress) after erection in situ.

This system of reinforcement, though not so suitable for heavily loaded beams of limited depth, as in the warehouses, was found to be convenient and economical for the wharf-girders; and, being self-supporting across the full spans, it might be useful in positions of less accessibility, as the moulds could, if necessary, be hung from the reinforcement.

A corresponding system of rigidly-fixed shear members was obtained in the wharf deck-beams by the adoption of double Kahn bars, 4·8 lbs. per lineal foot, in conjunction with a single round bar at the top and bottom (Figs. 4, 5, and 6, Plate 1). These beams being shallow and lightly loaded, Kahn bars were suitable and practically convenient, though somewhat costly—the contract price being 2·49d. per pound, as compared with 1·56d. for round bars and ties—owing to the cheapness of the labour which was saved by their use.

In the more heavily loaded beams and girders of the warehouses, therefore, nothing but plain round bars and wire ties were used, as shown in Figs. 10–12, Plate 2. The greater part of the shearing stress was taken up by the tension-bars, which are bent up at intervals to pass along the top of the member over the points of support. To resist the remaining shear, to confine the concrete, and also to link together the main reinforcement, three rows of stirrups were employed. These are made of two wires, either $\frac{1}{4}$ inch or $\frac{5}{16}$ inch in diameter, twisted together, with their free ends clenched tightly round the longitudinal bars at top and bottom. The sets of bars are tied together horizontally with wire links, and

the whole skeleton is tightened and stiffened by struts $\frac{1}{2}$ inch in diameter, at intervals of 3 to 5 feet, the final introduction of which converts the assemblage of bars and ties into a rigid framework.

TESTING.

It was not thought advisable to subject any part of the finished structures to test loads greatly in excess of the maximum safe load allowed for. At an early stage of the work, however, tests to destruction were carried out on one experimental wharf-beam of full size, including a deck-slab 5 feet wide and reinforced according to the final design (Figs. 5 and 6, Plate 1); also on one warehouse-beam of similar character (Fig. 11, Plate 2), and on five columns designed to represent to a reduced scale the lower warehouse-columns (Figs. 14, Plate 2).

The beams were both made of such a length as to project half a span on each side of the supports, and were loaded in such a way that, when the full (safe) load came on the (centre) span to be tested, the cantilever ends were weighted to a sufficient extent to give the effect of a continuous beam with one span loaded and the two adjacent spans light. This outlying weight, however, was not increased with the subsequent loading to destruction.

Wharf-Beam.—For example, the wharf-beam (Figs. 4 and 6, cross section BB), which was calculated to bear a distributed load of 1,750 lbs. per lineal foot, was loaded with a maximum of 400 lbs. per lineal foot on the projecting arms.

This beam measured 14 inches from the top of the deck to the centre of the reinforcement; it was 11 inches wide, and carried a deck-slab 5 feet wide by 5 inches thick. The results of the test were as follows:—

WHARF-BEAM, AGE 3 MONTHS, SPAN 15 FEET.

Date, 1908.	Super-Load.	Total Load.	Deflection.	Remarks.
August 8 .	Tons. 11·7	Tons. 14·6	Inches. 0·062	Calculated super-load.
„ 11 .	11·7	14·6	0·081	After 3 days.
„ 17 .	22·8	25·7	0·112	
„ „ .	34·0	37·0	0·162	
„ 18 .	34·0	37·0	0·174	After 24 hours.
„ „ .	45·0	48·0	0·310	{ First crack appeared (in underside). Beam suddenly collapsed, as described overleaf.
„ 20 .	90·0*	93·0	..	

* $7\frac{2}{3}$ times calculated super-load.

The beam tested on the 20th August first began to fail by diagonal tension near the supports; the concrete then stripped from the under-side of the tension-bars, which drew, fracturing the diagonals of the Kahn bars at their points of junction. The concrete then crushed at the inner edges of supports (as the beam sagged), and finally at the surface of the deck-slab, while cracks opened in the beam below it.

Warehouse-Beam (Figs. 11, Plate 2).—In testing the warehouse-beam sufficient precautions were not taken to prevent settlement of the points of support, which subsided unequally. The deflection readings were, in consequence, not accurate enough to be of value. The beam failed under a distributed load of 169 tons—about $7\frac{1}{2}$ times the calculated safe load—on a span of 20 feet.

Experimental Columns.—These were tested at 15 months. They were octagonal in shape, 10 inches across, 6 feet 3 inches in length. The reinforcement consisted of eight rods $\frac{3}{4}$ inch in diameter, with $\frac{1}{16}$ inch helical hooping at 1 inch pitch, enclosing an area 8 inches

Concrete.	Load when First Crack appeared.	Final Load.	Calculated Safe Load.
1 : $1\frac{1}{2}$: 3 {	Tons. 132·2	Tons. 170·4	Area of steel in compression 3·53 square inches. Area of concrete inside hooping 50·27 - 3·53 = 46·74 square inches. Safe load in lbs. = 3·53 × 12,000 + 46·74 × 1,200 = 44 tons.
	132·2	171·8	
	Average 132·2	171·1	
1 : 2 : 4 {	139·1	155·8	
	132·2	172·5	
	146·1	167·0	
Average	139·1	165·1	

in diameter (Figs. 14, Plate 2). These columns all failed by bending, although the length was only nine times the diameter of the area confined by the hooping. Actual failure did not take place until considerably after the maximum loads were recorded. A slight bending at this stage, accompanied by cracks in the surface concrete at one end, reduced the pressure indicated on the (hydraulic) testing-machine gauge. As further pressure was applied, the column bent increasingly, gradually scaling off the outer coating of concrete, and finally breaking a strand of the wire hooping at the point of greatest tension, while the inner core of concrete was to all appearances still intact.

By way of comparison with these reinforced columns, some of a similar section, but unreinforced, were made and broken at the same time, with the following results.

Concrete. Age 15 Months.	Load applied when First Crack appeared.	Final Load.	Equivalent Load on Full Area.
	Tons.		Lbs. per Square Inch.
1 : 1½ : 3	90·4	111·3	3,040
	97·4	107·8	2,945
	130·8	130·8	3,573
Average	106·2	116·6	3,186
1 : 2 : 4	86·3	86·3	2,357
	100·2	106·4	2,906
	76·5	80·7	2,204
	97·4	109·9	3,002
Average	90·1	95·8	2,617

These all crushed in the normal manner, with the formation of a conical fracture at one end.

In addition to the tests to destruction, test working-loads (about 72 per cent. of the maximum calculated safe load) were imposed on four ground-floor columns of the warehouse first constructed, before completion of the building. In order to effect this, 300 tons of steel bars were piled on the first and second floors around the column to be tested—bringing about 270 tons load upon its ground-to-first-floor length. In the ordinary working of the warehouses this is as much as can be brought to bear upon them. This loading brought on to the floor-beams and girders concerned a load about 25 per cent. in excess of their maximum calculated load. No sign of weakness or distress was perceptible anywhere, nor was there any observable compression of the columns.

EQUIPMENT.

Owing to the prevailing practice in Shanghai of carrying all loads up to 4 cwt. on bamboos between two coolies, the only equipment provided on the wharf consists of two 5-ton steam cranes, to travel on a standard-gauge track along the front and beside the creek. These are for the purpose of lifting into lighters weights of more than 1 ton, which cannot easily be handled by coolies. The vessels of Messrs. Holt's "Blue Funnel" fleet are exceptionally well provided with gear, discharging their cargo as fast as it can be coped with on shore.

The power installation consists of a suction-gas producer-plant, two gas-engines of 150 B.H.P. each, linked with dynamos, and a third of 25 B.H.P. for night use when no cargo is being discharged.

Overhead cables convey the current to a main switchboard in the office, and thence to the warehouse lift-motors, and electric lights throughout the site.

COSTS.

Owing to the wide fluctuation in exchange, there is a difficulty in stating the costs of the work exactly in English currency. When the contract was let the value of the Shanghai tael was approximately 3*s.*, but soon afterwards it fell rapidly to a minimum of 2*s.* 4½*d.* Taking into account the material ordered from Europe at varying exchanges, and the practically uniform rates for labour, a value of 2*s.* 8*d.* per tael represents fairly the actual cost of the work. On this basis the unit costs of the chief items are:—

WHARF.

Item.	Unit Cost.	Unit.	Percentage of Total Cost of Structure.
	<i>s.</i> <i>d.</i>		
Bearing piles	3 7·4	Cubic foot	40·2
Sheet-piles in training-wall . . .	4 5·4	„	6·5
Superstructure	3 5·1	„	51·0
Timber fenders	3 1·3	„	2·3
			<hr/> 100·0

Amounting to 8*s.* 7*d.* per square foot of deck area.

QUAY-WALL.

Item.	Unit Cost.	Unit.	Percentage of Total Cost of Structure.
	<i>s.</i> <i>d.</i>		
Excavation (including front of wall) . {	<i>s.</i> <i>d.</i> 6·4 to 1 7·2 }	Cubic yard	} 13·0
Filling	6·4	„	
Bearing and king-piles	4 4·0	Cubic foot	19·7
Sheet-piles	4 3·8	„	23·3
Superstructure	2 2·0	„	25·6
Anchor-ties (including excavation and attachments) }	10 0	Lineal foot	12·9
Timber fender	3 1·3	Cubic foot	6·5
			<hr/> 100·0

Amounting to £13 11*s.* 7*d.* per lineal foot of wall.

WAREHOUSES.

Item.	Unit Cost.	Unit.	Percentage of Total Cost of Structure.
	<i>s.</i> <i>d.</i>		
Excavation	4 8	Cubic yard	} 3·6
Lime concrete	10 8·0	„	
Reinforced-concrete foundations and ground floor	2 3·4	Cubic foot	24·4
Reinforced-concrete superstructure .	3 0	„	55·7
Brickwork in walls	1 8·0	„	6·7
Waterproof roofing	5·3	Square foot	1·6
Doors, windows and steelwork in roof over alley-way	..	..	8·0
			100·0

Amounting to 5·17*d.* per cubic foot of content, exclusive of lifts and electric light installation.

The cost of unskilled labour in Shanghai varies from 10*d.* to 1*s.* per day.

The Contractors for the work were Messrs. C. Vering, of Hamburg, who carried it through without the intervention of sub-contractors, except for brickwork and excavation, but were not in any way responsible for the design.

The Author was Engineer, in company with Messrs. Davies and Thomas, Architects, of Shanghai. The Resident Engineer was Mr. Guy Magee, who was also largely concerned in getting out the details of design. Mr. Magee's health having broken down towards the close of the work, he was succeeded in charge by Mr. A. J. Wynne, formerly his chief assistant.

The Author desires to express his appreciation of the ungrudging services rendered by these gentlemen, and by the other members of the staff.

The Paper is accompanied by five tracings, from which Plates 1 and 2 have been prepared; also by a number of photographs.

REINFORCED - CONCRETE WHARVES AND WAREHOUSES, SHANGHAI.

DECK - BEAM AT PILES

INTERMEDIATE DECK - BEAM .

CROSS SECTION

GENERAL DETAILS
OF WHARF.

LONGITUDINAL SECTIONS OF WHARF

DETAILS OF WHARF REINFORCEMENT.

CROSS SECTION A A
(Ref C)

CROSS SECTION OF BEAMS B B (Fig. 4)

CROSS SECTIONS OF				
FACE COLUMN.	INNER COLUMN.	FACE PILE.	INNER PILE.	SHEET PILE.

PLATE 2.
REINFORCED-CONCRETE WHARVES
AND WAREHOUSES, SHANGHAI.