THE INSTITUTION OF CIVIL ENGINEERS.

SESSION 1895-96.—PART IV.

SECT. I.—MINUTES OF PROCEEDINGS.

14 April, 1896.

SIR BENJAMIN BAKER, K.C.M.G., LL.D., F.R.S., President,
in the Chair.

It was announced that the several Associate Members hereunder mentioned had been transferred to the class of

Member.

JAMES HENRY ANDERSON.	ERNEST JAMES RUMSBY.
CORNELIUS EDWARD CARDEW.	GEORGE THOMAS SIBBERING.
CHARLES CLAUDE CARPENTER.	HERBERT BLOMFIELD SMITH.
EDWARD ELLIS.	

FREDERIC JOHN RAMSBOTTOM SUTCLIFFE.

And that the following Candidates had been admitted as

Students.

THOMAS CONYNTHAM BRUTTON ANDERSON.	JOHN HOLLIDAY.
FRANCIS JAMES BROADBENT.	PERCY NICHOLAS HOOPER.
HERBERT JAMES BUBB.	GEORGE PASCOE MAIR.
ALFRED DOVER DELAP, B.E.	EDWARD THOMAS EVERY MILLER.
ALFRED TOMLIN EAST.	EDWARD ERNEST PEARSON.
HENRY CHARLES DIGBY FEARON.	ADRIANO SALDANHA.
JAMES HERMANN FIELD.	CHARLES MONTGOMERIE SMYTH.
WALFORD HENRY GALE.	JOHN HORATIO TRENNERY.
SPENCER OSWALD HEINEMANN.	JOHN ATKINSON TUZO.
	JOHN HERBERT VEASEY.

LEWIS PHILLIPS WINBY.

The Candidates balloted for and duly elected were : as

Members.

EUGENE GRIFFIN.	WILLIAM HENRY LE QUESNE.
	JOHN WALKER.

Associate Members.

HERBERT JEFCOATE ATKINSON, B.E.	ERNEST NEWTON BOWDEN, Stud. Inst.
NORRIS GARRETT BELL.	C.E.
WILLIAM MURRAY BINNY.	EDWARD BOX.
ROBERT BLEAZBY, B.E.	ANDREW BOYD, B.E.

[THE INST. C.E. VOL. CXXVI.]

B

Associate Members—continued.

PATRICK JOSEPH CORBETT, Stud. Inst. C.E.	FREDERICK SAUNDERSON.
WILLIAM CRAIG.	ALEXANDER SMITH.
GEORGE BELBEN CRESSWELL.	FREDERICK HENRY SMITH.
WILLIAM ROBERTSON LIDDERDALE	MAURICE AMBROSE VILLIERS-STUART,
FORREST, Stud. Inst. C.E.	Stud. Inst. C.E.
THOMAS GILBERT JONES, B.Sc., Wh.Sc.,	RICHARD WALTER WALSH.
Stud. Inst. C.E.	CYRUS JOHN RICHARD WILLIAMS.
ALEXANDER LADE, Stud. Inst. C.E.	WILLIAM RICHARD WILLIAMS.
CHARLES JULIUS ALFRED MITTEL-	ARTHUR WOOD - HILL, Stud. Inst.
HAUSEN.	C.E.
HERBERT EDGAR PECK.	FRANK WORRALL.
	ADAM FREDERIC TRAMPE WORSÖE.

Associates.

BERTRAM BLOUNT.

| EDGAR CHARLES SPILSBURY, *Major R.E.**(Paper No. 2913.)*

“ The Thirlmere Works for the Water-Supply of Manchester.”¹

By GEORGE HENRY HILL, M. Inst. C.E.

THE city of Manchester and the surrounding districts were, previously to the auxiliary supply being obtained from Thirlmere, wholly supplied with water by gravitation from Longdendale, a valley situated about 18 miles east of the city, down which flows the River Etherow, one of the principal tributaries of the River Mersey. The drainage-area contributing this supply is 19,000 acres, the area of the reservoirs being 855 acres and their storage-capacity about 6,000 million gallons. The quantity of water available, exclusive of that delivered as compensation to the river, is about 25 million gallons per day. The works, including the service-reservoirs, mains and piping, have cost up to the year 1894 about £3,150,000.

In the year 1875 the consumption reached about 17 million gallons per day, having increased from about 8 million gallons per day in 1856. It became evident therefore, in view of the period which must necessarily elapse before any material extension of the supply could be completed, that the time had arrived when the question of providing for the future needs of the city and district must be fully considered. The Corporation, after an

¹ The discussion upon this communication was taken in conjunction with the following one by Mr. Deacon descriptive of the Vyrnwy supply to Liverpool.

examination of various sources, determined to adopt the scheme for obtaining an additional supply of water from Thirlmere, one of the lakes in the English Lake District, and the Act of Parliament authorizing this scheme was obtained in May 1879. The first contract was let in December 1885, the works being opened and the supply of water to Manchester from Thirlmere commenced on the 13th of October, 1894.

GENERAL DESCRIPTION.

The natural drainage-area of Lake Thirlmere is 7,400 acres; but the scheme includes the water from a further area of 3,600 acres, which will eventually be diverted into the lake. The total drainage-area included in the scheme is therefore 11,000 acres. The geological formation of the drainage-area is Lower Silurian, the rock being very near to the surface. There is scarcely any peat, the water which flows from the drainage-area, even in times of heavy flood, being therefore almost as clear and free from turbidity as in ordinary weather. The mountains surrounding the lake are very precipitous and are used as sheep pastures, the highest point of the watershed being Helvellyn, which is 3,118 feet above the sea, or 2,585 feet above the natural level of the lake.

The rainfall in the Thirlmere district is very large, a portion of the drainage-area being only about 4 miles to the east of Seathwaite in Borrowdale, where observations have shown the rainfall to be one of the highest in Great Britain, amounting in some years to as much as 243 inches. On the Thirlmere watershed it varies in wet years between about 100 inches in the valley and about 137 inches on the hills on the west side of the lake, and in dry years between about 60 inches and about 80 inches at the same places, *Fig. 1*. In 1878, when the Bill was before Parliament, there were no records of the rainfall upon this drainage-area, it therefore had to be estimated by the examination of the returns in other parts of the Lake District. The quantity of water obtainable for the city was, after allowing 5,500,000 gallons per day as compensation water to the river, assumed at about 50 million gallons per day. The average rainfall at Thirlmere for the three dry years 1887, 1888 and 1889, was 71 inches, as compared with 40 inches in the mountain district of Longdendale, the source of the present supply, *Figs. 1 and 2*. From the almost entire absence of peat, and the precipitous and rocky character of the Thirlmere area, the yield is largely in excess of that usually obtainable from drainage-areas in this country.

The area of the lake, Fig. 5, Plate 1, in its natural condition, and at its normal level of 533 feet above sea-level, is $328\frac{1}{4}$ acres. By the Act of 1879, the Corporation is prohibited from abstracting any water from the lake when it is below this level; but powers are given to raise the natural level 50 feet. The area of the lake when so raised will be 793 acres, and the capacity of the raised portion will be 8,130,686,693 gallons, equivalent to a depth of $32\frac{2}{3}$ inches on the total drainage-area. The water is conveyed from Thirlmere by an aqueduct (Figs. 3 and 4, Plate 1) having a total length of $95\frac{7}{8}$ miles, consisting of tunnelling, cut-and-cover, and cast-iron pipes, which terminates at a new reservoir at Prestwich, 4 miles from Manchester. The aqueduct passes through various geological formations, beginning in the Lower Silurian

Fig. 1.

Fig. 2.

and ending near Manchester in the Coal Measures. The whole of the storage is above the level of the aqueduct.

The tunnels and cut-and-cover portions of the aqueduct, about 51 miles in length, together with some of the bridges, valve-houses, and other special works which could not conveniently be enlarged hereafter, have been constructed of the full size ultimately required when the whole quantity of 50 million gallons per day is being drawn from Thirlmere. In the case, however, of the cast-iron pipes, only one of the five lines, each of which is 45 miles in length, has been laid, as the city does not at present require a supplemental supply of more than 10 million gallons per day.

WORKS.

The water of the lake is impounded by a masonry dam, Figs. 12 and 13, Plates 1 and 2, which has been constructed across the outlet at the north end of the lake. The dam is divided into two portions by a small isolated hill, the summit of which rises to about the same level as the top of the dam. The foundation is everywhere sunk into the solid rock, and at the river reaches a maximum depth of 50 feet below the bed. The dam is constructed of concrete gauged 5 parts of broken stone and sand to 1 of cement; large blocks of rock being embedded in it, sufficiently far apart to be properly surrounded with concrete. These blocks were not allowed to be placed within about 7 feet of the inner face. All the fine material for the concrete was produced by grinding the stone of the district. The dam is faced on both sides with heavy chisel-bedded and jointed masonry, of an average thickness of about 2 feet, well bonded into the concrete of the dam. The batter on the lake side is $1\frac{1}{2}$ inch to a foot, and the outside is curved to a radius of 100 feet. The dam is finished at the top of the outer face by two courses of ashlar 18 inches thick, and on the inner face by one course of the same thickness. The top of the dam carries a roadway 16 feet wide.

Surplus water and compensation water are discharged from the lake by pipes laid in a tunnel driven through the isolated hill. The tunnel is 12 feet wide and 9 feet high; the portion on the lake side of the dam is lined with blue bricks in cement, the outer portion being in strong rock is left unlined. The tunnel, which was used for the passage of the water from the lake during the construction of the dam, is closed on the centre-line of the dam by a brickwork stop, through which two cast-iron pipes 3 feet in diameter and one cast-iron pipe 18 inches in diameter are laid. The larger pipes are used for discharging surplus water, and the smaller pipe delivers the compensation water to the gauge-basin.

A shaft, 10 feet in diameter, is sunk on the line of the tunnel a short distance outside the centre-line of the dam, and is lined with blue bricks faced with white glazed bricks. The working arrangements for the valves on the cast-iron pipes are placed in this shaft. Two valves, Figs. 20, Plate 3, are placed tandem on each of the large pipes, one being worked by hydraulic power and the other by hand-gearing. The hydraulic power is obtained through a 6-inch pipe fed from a small tank situated on a stream on the hill-side above the south end of the dam. The tank is so

arranged as to intercept all sand or earthy material and prevent its passage into the pipe. At the valve-house which covers the shaft, the 6-inch supply-pipe is reduced to a copper pipe 3 inches in diameter made of copper. This pipe is carried down the shaft to a point near the valve at which it is reduced to two $\frac{3}{4}$ -inch pipes of the same metal which are connected respectively with each of two hydraulic cylinders, Figs. 17, 18 and 19, Plate 3. The $\frac{3}{4}$ -inch pipes which supply the cylinders are each controlled by a four-way cock worked by a lever. For the purpose of raising this lever, a chain is attached to the end of it and passes up to a hand-wheel in the head-stock fixed in the valve-house. To lower the lever, weights hung to it come into operation when the hand-wheel chain is slackened. There is also fixed in the valve-house a graduated indicator connected with each valve, which shows the exact position of the door of that valve.

Each hydraulic cylinder is placed immediately above the valve, the piston being connected by a cross-head to two lifting-rods attached to the door of the valve. The diameter of each cylinder, which is lined with gun-metal, is 30 inches, and a pressure of 40 lbs. per square inch can be applied to them. All rods and working parts are of Delta metal. A valve worked by hand is placed at the bottom of the valve-shaft on the 18-inch pipe. The shaft at the level of the ground is covered by a valve-house in which the headstocks of the valves in the tunnel are fixed, and it is from this building that the waterman controls the discharge of water through the tunnel.

The waste-weir is constructed in solid ground, and is entirely unconnected with the masonry of the dam. The water, after flowing over an ashlar crest, 100 feet in length, is gathered into an artificial swallow-hole, 20 feet deep, from the bottom of which it passes through a tunnel about 25 yards long into the waste-watercourse, and so to the river. The width of the waste-watercourse varies between 12 feet at the end of the tunnel and 40 feet where the fall is less considerable. For the present supplementary supply of Manchester, it is not necessary to retain a greater depth of water in the lake than 20 feet. An overflow and tunnel through which the water may pass has therefore been provided at the 20-foot level, immediately under the overflow already described, communicating with the tunnel and waste-watercourse. This overflow is of course only temporary, and will be closed when it is found necessary to impound a greater depth of water in the lake.

A gauge-basin has been constructed to receive the compensation water delivered by the 18-inch pipe laid through the discharge

tunnel. The water is discharged into a basin where it is stilled; it then enters a second basin, in the walls of which, there are ten orifices exactly alike in all respects. Arrangements are made by which the water from one of these orifices can be discharged into and measured in a test basin. By this means the quantity delivered to the river can at any time be accurately ascertained.

The raising of the lake necessitated the diversion of the main coach-road between Windermere and Keswick for a length of about 2 miles. An entirely new road about $5\frac{1}{2}$ miles long has been constructed on the west side of the lake, and also a new road over the top of the dam, which forms a connection between the roads on the two sides of the valley. In consequence of the precipitous character of the country and the large rainfall, the construction of these roads was very expensive, requiring heavy retaining-walls, masonry bridges and culverts, &c., across the various streams, much in excess of ordinary requirements.

THE AQUEDUCT.

The length of the aqueduct is $95\frac{7}{8}$ miles, $14\frac{1}{8}$ miles being in tunnel (for 50 million gallons per day), $36\frac{3}{4}$ miles in cut-and-cover (for 50 million gallons per day), and 45 miles in cast-iron siphons (for 10 million gallons per day). At a distance of about 100 yards from the lake on the line of the aqueduct a straining-well, Figs. 6, 7, Plate 2, is sunk in the rock to a depth of about 65 feet. This well is circular, and is lined with concrete; the diameter at the bottom is 37 feet 6 inches, increasing by two set-offs to 40 feet 6 inches at the surface of the ground. On the lake side of and adjoining this well a rectangular valve-shaft, also lined with concrete, is sunk to the same depth as the well. The water is drawn from the lake by a tunnel of the same size and shape as the aqueduct to be described. The invert of this tunnel is 6 feet 3 inches below the original normal level of the lake, the limit fixed by Parliament below which no water may be withdrawn. This tunnel ends at the valve-shaft, the water being conveyed through the valve-shaft to the straining-well by a pipe 42 inches in diameter. This pipe is commanded by two valves, one being worked by hydraulic power and the other by hand-gearing, as in the case of the valves in the tunnel at the outlet of the lake. Provision has been made in the lining of the valve-shaft and the straining-well for drawing off the water from the lake at a higher level whenever the requirements of the city necessitate the further raising of the lake. The

water is delivered into the straining-well on the outer side of an octagonal screen of strainers 22 feet in diameter and 16 feet high. Seven sides of the octagon are formed by strainers, two of which, one above the other, occupy each side. Each strainer is 7 feet 4 inches wide and 8 feet high, framed in oak and divided into six compartments, each compartment being filled by a small frame (which can be removed as required) holding copper-wire gauze of 900 meshes to the square inch, the gauze being supported by strong copper wire of larger mesh. The strainers are fitted into grooved cast-iron columns 21 feet high, the difference in height between the top of the strainers and that of the columns being made up by stop-planks. These columns, which are stayed to the walls of the well and to a centre column 36 inches in diameter, support two wrought-iron platforms or galleries, enabling the workmen to obtain access to the strainers. Each column is cast with two sets of grooves, one behind the other, so that when it is desired to take out and wash any strainer, a spare strainer can be inserted into the hinder groove and left there until the other is replaced. The eighth side of the octagon is open and is opposite to the entrance of the aqueduct to Manchester. Stop-planks are inserted between the octagon and the walls of the well on both sides of this entrance, so that the water, after passing through the strainers to the centre of the well, flows to the aqueduct. A small hydraulic pump fixed to the wall of the valve-shaft keeps it free from water. As water accumulates a float rises and opens a valve, which admits the pressure-water to work the pump.

To lift the strainers for washing and other purposes, a hydraulic travelling-crane is placed in the building over the straining-well. This crane is attached to and revolves round the column in the centre of the well. The arm of the crane is horizontal, and is supported at the outer end by a triangular frame, which travels round the inside of the building on a rail fixed at floor-level. This frame carries a winding-drum and hydraulic-engine. The engine has two 6-inch cylinders driving direct on to the drum on which the chain lifting the strainers is wound. The power is sufficient to lift a strainer weighing $8\frac{1}{2}$ cwt. from the bottom of the well, a distance of 65 feet, in two minutes. The framework of the crane is of steel, the travelling gear being worked by hand.

At the top of the well the centre column carries radial girders, the outer ends of which rest upon the walls of the well. Upon these girders and around the circumference of the building over the well there is a gangway, $7\frac{1}{2}$ feet wide, formed of cast-iron

plates chequered on the surface, with a guard-rail at the edge. The rail on which the hydraulic crane travels is also fixed to these girders. Wrought-iron ladders are fixed to reach the different floors in the valve-shaft, and a wrought-iron spiral staircase is provided in the straining-well down to a platform above the mouth of the aqueduct, on which a cylinder working the sluice which governs the water sent to Manchester is fixed. The straining-well and valve-shaft are covered by a castellated building with two wings, in one of which the strainers are washed; in the other stores and tools are kept. The centre column of the straining-well assists in carrying the roof of the building. The supply of water for washing the strainers and working the hydraulic machinery is taken from a small tank constructed on the hillside, and fed from a neighbouring stream. The invert of the pipe at the tank is 61 feet above the floor of the building over the straining-well.

Figs. 8.

SECTIONS OF AQUEDUCT.

Through the wall of the straining-well is laid a short length of pipe 42 inches in diameter, which delivers the water into the aqueduct. This pipe is commanded by a 42-inch sluice, also worked by hydraulic power.

The aqueduct, Figs. 3 and 4, Plate 1, from the straining-well commences with the Dunmail Raise Tunnel, 5,188 yards in length. Some of the other long tunnels are, the Moor Howe 3,040 yards, the Nab Scar 1,419 yards, the Skelgill 1,243 yards, the Grizedale 910 yards, and the Chapel Green 604 yards; and there are many others between 400 yards and 900 yards in length, the total length of tunnels being $14\frac{1}{2}$ miles. The greater part of the long tunnels was driven by machinery worked by compressed air.¹ The tunnels, Figs. 8, are for the most part lined with 5 to 1 concrete. Where a segmental arch is used, the sides are 5 feet high, and in such

¹ Minutes of Proceedings Inst. C.E., vol. cxvi. p. 162.

cases the arch has a rise of 2 feet. The width of the aqueduct is 7 feet 1 inch, and the general height is 7 feet. The thickness of the concrete varies according to the nature of the ground passed through. In the floor it ranges from $4\frac{1}{2}$ inches in close rock to 18 inches in bad ground, and in the walls from 12 inches to 18 inches according to circumstances. The depth of the arch is 15 inches. In special cases, however, it was found necessary to adopt stronger sections. A considerable portion of the long tunnels in the Lake District is unlined, with the exception of the concrete floor, which is never omitted; in such cases the width of the aqueduct is 8 feet 6 inches, to meet the increased friction in the passage of the water caused by the irregularities in the rock.

The cut-and-cover, Figs. 3, 4 and 8a, portion of the aqueduct was constructed to the same internal dimensions and shape as the tunnels which are lined, the thickness of the lining varying according to circumstances. Manholes with ventilators are provided at intervals of about $\frac{1}{4}$ mile. The bridges over streams on the cut-and-cover portions are in all cases of masonry, and provision is made at these and other places for the overflow and discharge of the water in the aqueduct. Throughout the tunnels and cut-and-cover sections the fall in the aqueduct is 20 inches per mile.

Wherever the hydraulic gradient is intersected by valleys too deep to be crossed by the concrete aqueduct, the latter terminates in rectangular chambers, described as north siphon wells, Figs. 9, 10, 11, Plate 2, from which the water passes direct into cast-iron pipes laid across the valley, terminating in chambers, described as south wells (see Appendix). There are thirty north wells on the line of aqueduct, the two first in the Lake District being somewhat larger than the others, in consequence of the works in these siphons being designed for three lines of pipes 48 inches in diameter, while in the case of the others there will be five lines 40 inches in diameter. The Act of Parliament provides that within a distance of 9 miles of Thirlmere each pipe shall be capable of delivering not less than 14,000,000 gallons per day. The object of this provision is to reduce the number of pipes, so as to minimise the disturbance in the Lake District which might be caused from time to time by laying additional lines of pipes whenever it should be found necessary to increase the supply to the city.

In each of the north siphon wells there is a valve which, in the event of a pipe bursting, closes automatically, thereby cutting off the supply. This well has been constructed sufficiently large to contain the valves which will be required on the other lines of

pipe. The arrangements in the wells at the head of the two 48-inch siphons are identical with those for the 40-inch siphons, with the exception of the diameter of the valves and floats, which is 8 inches greater, to correspond with the increased size of the pipes. The well is divided into two main compartments. One of these, the valve-well, which receives the supply from the aqueduct, contains the valves, together with the necessary overflows for dealing with the water coming from the lake when any valve is closed. The other compartment, the float-well, is sub-divided into smaller wells, one for each line of pipes. Each of these wells contains a float, by which the valve commanding that line of pipes is set in motion. The pipe at present laid draws its supply from the centre float-well. The water passes from the valve-well to each float-well separately through cast-iron tubes, one to each line of pipes, set in the concrete floor. The end of the tube in the valve-well is turned up so as to present a horizontal circular orifice 56 inches in diameter, which is faced with gun-metal and upon which the valve closes; the other end in the float-well is turned up in the same manner, and is provided with vertical guides, in which the float rises and falls. The sides of the tube in this well are cast with seven circular orifices, each 15 inches in diameter, through which the water passes to the siphon-pipe. The valve consists of two concentric bell-shaped vessels, the outer of which is 56 inches in diameter and the inner 20 inches in diameter, the latter being only used in charging the pipes. The outer bell is of cast iron and the inner one is of Delta metal. The tops of both bells stand above the surface of the water, so that they form equilibrium valves. The float is hung from a lever 18 feet long, having the fulcrum at one end and the float at the other, the bell-valve being suspended between the two, and distant 4 feet 6 inches from the fulcrum. The fulcrum end of the lever is attached by a Delta-metal pin to a cast-iron box built into the roof of arched recesses in the side of the well, the float end being slung in a guide by chains which pass over pulleys and carry the counterbalance weights. The float, which is made of copper, is 52 inches in diameter, and is connected with the lever by a rod. Passing horizontally through the centre of the large bell, about 6 inches above the seating, there is a rectangular tube, 12 inches by 6 inches, open at the ends; in the middle and on the upper side of which there is a circular orifice $19\frac{1}{2}$ inches in diameter, with a gun-metal seating on which the smaller bell-valve rests when closed. This small valve is connected by a rod through the top of the large bell with a canoe-shaped casting working on

trunnions on the top of the lever. In this canoe casting, which is 58½ inches long, there is a cast-iron ball 9 inches in diameter, weighing 80 lbs., the rolling of which tilts the canoe and so opens or closes the small valve. The trunnions are not placed at the centre of the canoe, but nearer the valve end, giving a leverage of about 3 to 1. In the event of a burst occurring on the pipeline the level of the water in the float-well falls, and the float falling with it closes the large bell-valve. The supply to the siphon is by this means cut off, and the water coming from the aqueduct goes to waste over the overflows provided in the valve-well; thus further damage by the burst is prevented.

When the repair on the piping has been made, in order to re-charge the pipe slowly and to give the air time to escape, the small bell-valve is opened by rolling back the ball to the end of the canoe nearest the float; the canoe is thereby tilted on its trunnions and raises the small valve. The water, which has always free access to the rectangular tube in the larger bell-valve, now escapes through the orifice thus opened in it and falls into the tube in the floor, by which it passes to the float-well, and so to the siphon. When the pipe across the valley is fully charged, the water begins to rise in the float-well and lifts the float, thereby gradually opening the larger bell-valve. Meanwhile, the raising of the lever by the float causes the ball in the canoe to roll to the end nearest the valve, thus tilting the canoe to its normal position. This has the effect of closing the small inner valve which is no longer required, the water being now admitted to the siphon through the large bell-valve. The valves are now again in position to cut off the water should another burst occur. Thus the apparatus requires no further attention after the re-charging has once been commenced by rolling over the ball. The arrangement is on the same principle as a ball-tap, but with the supply being shut off instead of admitted by the falling of the float.

The siphon pipe terminates in a chamber on the south side of the valley from which the concrete aqueduct again begins. There is no special feature in this chamber, the end of the siphon pipe, which is bell-mouthed, merely turns up through the floor. For a distance back from the north siphon wells the aqueduct is in many cases made 9 inches higher than usual, in order to give a greater head upon the pipes when the full quantity is passing. All the siphons, with the exception of the first two, are composed of five lines of cast-iron pipes 40 inches in diameter; but for about the last 13 miles of the aqueduct between Hulton and the Prestwich

reservoir, which consists wholly of piping, the diameter is 36 inches as the fall is greater. The total weight of one line of pipes, 45 miles long, is about 52,000 tons. The pipes were cast by the Staveley Coal and Iron Company, and Messrs. Macfarlane, Strang, & Co., of Glasgow. The 48-inch pipes are 9 feet, and the 40-inch pipes 12 feet long, and vary in thickness between 1 inch to $1\frac{3}{4}$ inch. They are coated with Dr. Angus Smith's composition. They were cast socket downwards with an extra head of metal 12 inches deep at the upper or spigot end, which was afterwards cut off in the lathe. While in the lathe all socket-pipes had the outer rims of the sockets turned down until they projected exactly $2\frac{5}{8}$ inches beyond the body of the pipes, to receive wrought-iron hoops subsequently shrunk on. The pipes were then thoroughly cleaned and gauged to see that they conformed to the specified dimensions. Any pipe varying more than $\frac{1}{8}$ inch in any of the internal diameters, or in thickness in any part, was rejected. Two test bars 1 inch wide, 2 inches deep, and 40 inches long, were cast with each pipe, and were numbered to correspond with the number on the pipe. These were required to carry, without breaking, a weight of not less than 28 cwt. applied at the centre between two supports placed 36 inches apart.

The pipes when tested were filled with coal-tar oil under a pressure equal to a head of water 100 feet greater than that to which they would be subject in work. They were then weighed, the date, number, diameter, length and thickness being entered in a book kept for that purpose. It may be here stated that the position of every pipe on the work is also registered, together with the date on which it was laid, the name of the man who laid it, and the time occupied in running the joint. After the weighing, a wrought-iron hoop, 1 inch thick and $1\frac{1}{2}$ inch in width, and of such a diameter that when uniformly heated to a dull red heat it would just pass on into its place, was shrunk on to the socket. The pipe was then taken without delay to a stove to be heated, preparatory to being dipped vertically into the composition. All the operations described, from the time when the pipes were withdrawn from the moulds to the time when they were dipped, were performed under cover, care being taken to protect the castings from damp and from cooling winds. In the length of 45 miles of pipes, six bursts have occurred, three of which were due to the settlement of the ground in the coal district near Manchester, where there is but little pressure; and the other three were caused by some accident, undetected at the time, having occurred to the pipes in transit between the operations of

manufacture and laying. In these cases the automatic valves hereafter described came into operation and satisfactorily fulfilled the purpose for which they were provided by cutting off the supply when the burst occurred.

Three types of pipe-joint were used, *Figs. 31*. It was considered that plain cylinders, joined with collars 6 inches wide, were less liable to be in a condition of internal stress than ordinary socket-pipes, where the mass of metal in the socket is considerable compared with the section of the barrel. This pattern of pipe-joint was therefore used in moderately flat ground. On sloping ground,

Figs. 31.

SECTIONS OF SOCKETS AND COLLARS FOR 48-INCH, 40-INCH AND 36-INCH PIPES.

where some difficulty might have occurred in making collar-joints, socket-pipes were used—the socket varying in depth between 3 inches and $3\frac{5}{8}$ inches according to the thickness of the pipe. In colliery districts, the collars used were between 8 inches and 12 inches wide, and the sockets were 5 inches deep. In all cases the joints were run solid with lead, no yarn being used; a spring ring inserted in the pipe while the joint was being run, prevented the lead from entering. In all cases the sockets and collars are designed so that the lead may be $\frac{3}{8}$ inch thick at the face and $\frac{1}{2}$ inch thick at a distance of $1\frac{1}{4}$ inch from the face, tapering to $\frac{1}{8}$ inch at the end. By this means blown joints are avoided.

For turning angles, whether in plan or section, double-socketed bevel castings were used, ranging in length up to $13\frac{1}{2}$ inches measured on the axis. The angles to which they were cast varied between 1° and 10° . Where larger angles than these occurred on the pipe-line, as many bevels were used as would give the required angle, and were connected by spigot pipes 3 feet long. In the case of most of the angles the bevels were surrounded with concrete.

The longest siphon, Figs. 3, 4, Plate 1, is that across the valley of the River Ribble, and is $9\frac{1}{2}$ miles in length. The greatest head of water, 427 feet, is on the siphon across the valley of the Lune near Lancaster. Wherever the cutting for the pipes exceeded 12 feet in depth, they were surrounded with concrete to a height of 12 inches above the pipe. In cases where the pipes were laid to an extremely steep inclination, in order to prevent movement, thrust-rings having an external diameter of about 54 inches were placed against the sockets at suitable intervals and surrounded with concrete. With few exceptions the pipes are carried over rivers, the longest bridges being those over the rivers Lune and Ribble, Figs. 15 and 16, Plate 3. These two bridges are alike, except that the former is on the skew; the following description therefore applies equally to both. Although only one line of pipes is at present laid, these bridges are made the full width for the five lines. There are three 70-foot spans, and the pipes are primarily carried by three cast-iron arched ribs, each in three sections 2 feet deep, spaced 13 feet 9 inches apart. These ribs spring from cast-iron bed-plates let into the masonry piers and abutments, and they are connected together at a distance of 12 feet on either side of the middle of the span, by steel cross-girders 20 inches in depth with a plate web $\frac{3}{8}$ inch thick, each flange being composed of two angle-bars, 4 inches by 4 inches by $\frac{5}{8}$ inch. At a distance of 22 feet $7\frac{1}{2}$ inches on each side of mid-span the arched ribs are again connected by a cast-iron girder 2 feet deep. Six longitudinal rolled-steel girders, 14 inches by 6 inches, are carried at their outer ends by the masonry and by the two steel cross-girders near the middle of the span. The four girders nearest the centre-line are 5 feet 3 inches apart, the distance between the outer girders being 4 feet $11\frac{1}{2}$ inches, and the six lines are connected by transverse steel beams 6 inches by 5 inches by $\frac{3}{8}$ inch. Upon the upper flange of each of the longitudinal girders, and 1 foot $7\frac{3}{4}$ inches on each side of the middle of each pipe, are bolted a pair of castings which form the paths of two rollers $4\frac{3}{4}$ inches diameter; these rollers span the distance between the two longitudinal girders, and carry a cast-iron seat, 4 feet by 1 foot 2 inches, upon which the

pipes rest. Upon each of the two middle longitudinal girders, five columns, formed of steel angle-bars, are carried, and support two longitudinal gangway girders 10 inches by 6 inches; upon these two girders rests the footway formed of bar-iron gratings, on either side of which is a handrail. The arched ribs on the outside have moulded flanges, and carry cast-iron spandrels and parapet of an ornamental character; the top of the parapet in the centre of the bridge is 6 feet 3 inches above the top of the arched rib, and the ornamental facework is supported by steel angle-bars riveted to the gangway girders. The piers and abutments are of blocking-faced masonry with dressed ashlar mouldings; and where vertical angles occur at the ends of the bridges, each pipe is anchored to the masonry by wrought-iron straps and bolts. On the upper flanges of the gangway-girders are bolted bridge-rails, on which travels a set of shear-legs for lifting out and replacing a pipe in case of burst, spare pipes being always kept conveniently near the bridge.

There is a third bridge, also of three spans, of the same type, over the River Irwell at Agecroft, near Manchester. In the coal district, for crossing railways, &c., there are seven plate-girder bridges, Figs. 21 and 22, Plate 3, with closed floor and ends; so that in case of a burst the escaping water is retained in the bridge and flows away by a waste-pipe provided for that purpose. There is no special feature in the design of these bridges, which are constructed of mild steel. Where the pipes pass under railways, subways are constructed into which access is obtained by a manhole at each end. These manholes are covered by bar-iron gratings, so that, in the case of a burst occurring in the subway, the water can flow out at the gratings and escape by a channel cut in the ground for that purpose. As in the case of the pipes, so with the other ironwork contracts, the greatest care was required in every step of the manufacture.

The number of valves upon the 45 miles of main pipe is very large, including stop-valves, self-acting valves, reflux-valves, air-valves, and mushroom-valves. The largest stop-valves, Figs. 30, Plate 3, ten in number, are those on the 40-inch pipes, the thickness of metal in the casing varying according to the pressure to which they are subject. The casing consists of three flanged castings strongly bolted together, the lower part being in two portions surmounted by a cap. The waterway of each valve is divided into three openings, the centre one being of a clear width of $5\frac{1}{2}$ inches. The division is formed by two vertical cast-iron ribs, bolted at the bottom to fins cast on the inlet and outlet castings. At the upper

end each rib is flanged out until it touches the sides of the vertical portion of the casing, thereby forming a diaphragm which completely closes in the top of the waterway, except that part required for the free passage of the doors. A lead joint is made round the edges of the diaphragm. Above the flanging out, the ribs are continued as far as is necessary to form guides for the doors. There are three stuffing-boxes in the cap, one for the lifting-rod of each door. The lifting-rods are formed of gun-metal tubes turned to an outer diameter of $5\frac{1}{2}$ inches and $\frac{3}{4}$ inch thick. The thickness of the upper end of these tubes is $1\frac{1}{2}$ inch, and upon the inside of this portion a square screw-thread of $\frac{1}{2}$ -inch pitch is cut, in which the gun-metal lifting-screw works. The entablature, which supports the screw-spindles and the gearing, is carried by four cast-iron pillars standing on bosses which are cast upon the cap of the valve-casing. The entablature is secured to the bosses by long bolts cottered into them, passing through the pillars and held by nuts at the top of the entablature. The centre spindle is worked by worm-gearing. These valves are anchored by a pair of steel anchor-rods in order to prevent any movement in the pipes, Fig. 14, Plate 2. The rods are $4\frac{1}{2}$ inches wide and $2\frac{1}{4}$ inches thick, and have an eye on their upper ends through which pass the trunnions of a heavy cast-iron thrust-ring. This ring is bolted round the pipe and abuts against a heavy casting attached to the valve; to the other end of the rod is fastened a cast-iron anchor-plate buried in concrete.

Self-acting valves, Figs. 27 and 28, Plate 3, are fixed on the northern or Thirlmere sides of the longer siphons; there are seven on the 40-inch pipes and two on the 36-inch pipes. Should a burst occur on the pipes below the level of these valves, the water is automatically cut off and damage to lands, &c., avoided. The body of the valve consists of two tubular castings forming the water-way. In the flanges by which these castings are bolted together, sockets are formed for the reception of the Delta metal stuffing-boxes in which the trunnions of a cast-iron disk-valve revolve. This disk-valve is hollow, of double convex shape, and forms one casting with the trunnions, which are also cast hollow, the thickness of metal being $2\frac{1}{2}$ inches in each case. The distance between the outer surfaces of the disk at the vertices of the convex curves, is 10 inches, diminishing to $\frac{3}{4}$ inch at the edge of the disk. The outside diameter of the trunnions, where they pass through the stuffing-boxes, is $7\frac{1}{4}$ inches, and they are cased with gun-metal $\frac{3}{8}$ inch in thickness. The touching-surface at the edge of the disk is truly faced, and comes to rest against gun-metal stops, which are sunk

$\frac{3}{8}$ inch into the cast-iron body and fastened by gun-metal screws $\frac{1}{2}$ inch diameter, $1\frac{1}{2}$ inch apart. The distance between the ends of the trunnions is 6 feet 5 inches; at the ends they are reduced in diameter to 6 inches and receive two cast-iron pulleys, the outside diameter of which is 1 foot $11\frac{1}{2}$ inches. These pulleys are actuated by chains, to the ends of which weights are attached. In the case of one pulley, the chain, after passing round it, is attached to the rod of a piston working in a horizontal cataract cylinder $10\frac{1}{2}$ inches in diameter and 2 feet long, bolted to the longer of the two castings forming the body. This cylinder contains a mixture of glycerine and water in the proportion of one part of the former to two of the latter.

The exhaust from the cataract-cylinder is regulated by a lever attached to a small cock placed on a line of copper pipe communicating through Delta metal T-unions with each end of the cylinder, and operated by a Delta metal grooved stud, attached to the side of the chain-wheel. The lever has two arms of unequal length. The free end of the longer arm rests in the groove of the stud on the chain-wheel, the shorter arm being attached to the spindle of the cock. The centres and lengths are so arranged that the throttle-cock is very gradually closed towards the end of the stroke of the piston, without being quite closed when the main-valve is shut. A small Delta metal vessel, holding a reserve of liquid, is supported on an iron bracket on the edge of the body casting, and is connected by a short length of copper tube to a T-union fixed over the end of the cylinder farthest from the chain-wheel. A small force-pump is placed over the cataract-cylinder, by which the disk-valve is brought back to a horizontal position. The longer of the two castings forming the body of the valve has a branch 15 inches in diameter, to which is bolted an air-vessel 7 feet 6 inches high, 2 feet 11 inches in diameter, and 2 inches thick. Two hollow tapering bosses, cast diametrically opposite on the inside of the air-vessel receive the shaft, which carries a malleable cast-iron lever hanging down into the water-way, its range of motion being limited by two spurs. To the end of this lever is riveted a plate-iron disk $21\frac{1}{2}$ inches diameter. To one end of the shaft is fixed a lever, from which weights are suspended sufficient to balance the normal pressure of water against the disk, and to hold the lever firmly against the upstream side of the branch which carries the air-vessel. Should, however, a burst occur on the line of pipes, the weights are no longer able to balance the pressure on the disk, which is moved by the water until the spur touches the opposite side of the air-

branch. The lever which carries the weights is thus lifted, and the upper end of another lever, which has been resting against a stud upon it, falls until it rests on the shaft. The lower end of this second lever which has been retaining the chain-pulley in position, then releases the chain-pulley, and allows the weights which it carries to set the disk-valve in motion.

For charging the air-vessel, a small Delta metal domed cylindrical vessel is bolted to a bracket cast on the body of the valve immediately below the air-vessel, and connected at the bottom by short copper tubes with the air-branch, and at the top with the main air-vessel. A three-way cock is placed on each of the tubes, and linked with the others. When it is desired to increase the quantity of air in the main air-vessel, the two cocks are, by a hand-lever, closed to the air-vessel and to the water in the air-branch, but are open to the atmosphere and the subsidiary vessel; thus any water contained in that vessel flows out to waste through the lower cock, while air enters through the upper cock. The cocks are then set so as to be closed to the atmosphere, and open to the water and main air-vessel. The charge of air contained in the subsidiary air-vessel then bubbles up into the main air-vessel. These valves are anchored similarly to the others, but in one direction only.

The reflux valves, Figs. 29, Plate 3, are placed on the ascending or southern ends of the long siphons, and are ten in number. Each is made up of three castings, an inlet, a centre or valve casting to which the doors are attached, and an outlet. The centre casting is divided into five openings by strong horizontal division-bars forming a part of the casting. The middle opening is 9 inches in height and 4 feet 1 inch in width; the two openings adjoining the middle one are 9 inches in height and 3 feet 6 inches in width; the upper and lower of the five openings are $4\frac{1}{2}$ inches in height, and 16 inches in width. Each of the five openings is covered by a cast-iron door, $1\frac{1}{4}$ or 1 inch thick according to size (the larger doors being strengthened by ribs on the back), hung by two hinges cast on the division bars and on the body of the casting. All meeting faces are lined with Delta metal, 1 inch wide and $\frac{1}{4}$ inch thick, attached by screws $\frac{3}{8}$ inch diameter and $1\frac{1}{2}$ inch apart. Each door is hung with two wrought-iron straps to turned and grooved Delta metal axles, the eyes of the straps being bored and bushed with Delta metal. These valves are anchored in one direction only.

The air-valves, Figs. 31, Plate 3, are of the ball type, but a variation in the usual design is introduced in order to shut off the water

from the balls, whenever it is desired to remove the latter for repair. This is effected by an inverted mushroom valve, placed in the main air-passage from the pipe, just below and between the balls. The spindle is carried up between the balls, and passes through a stuffing-box in the cover.

Valve-houses have been built over the large stop-valves and self-acting valves. They are large enough to cover the five lines of pipes in the complete scheme. The roofs are of glass, fixed in wrought-iron framing. Wrought-iron girders are fixed in the houses, capable of carrying blocks and tackle for raising any parts of the valves which may require repair. Wicket gates have been placed in every fence crossed by the line of aqueduct between Thirlmere and Prestwich. Watchmen are stationed at intervals along the line, and arrangements are in progress for telephonic communication between Thirlmere and Manchester, and between the men on the line of works.

RESERVOIR.

The Prestwich reservoir, at the end of the aqueduct near Manchester, has an area of $4\frac{1}{2}$ acres, and contains 21 million gallons. It is lined throughout; where clear of the embankments the lining is composed of a course of 3-inch bricks set in asphalt, founded on 15 inches of concrete; on the centre-lines of embankments the usual puddle-wall is used, the puddle being taken under the inner slope and tied into the concrete and brick lining. The water from Thirlmere is admitted by the cast-iron pipes into a masonry inlet-well, built on the centre-line of the embankment, from which it flows over a weir 21 feet wide into the reservoir. The outlet to the city is formed by a group of four wells, and a cleansing- or waste-well on the centre-line of the embankment. The first or outlet well, which communicates freely with the reservoir, contains the vertical overflow standpipe, 42 inches in diameter, from the foot of which a pipe, 27 inches in diameter, passes under the floors into a circular cleansing- or waste-well 15 feet in diameter. From the outlet-well the water flows right and left through two cast-iron pipes, 30 inches in diameter, respectively 12 feet and 23 feet 6 inches below top water-level. These are commanded by sluices and deliver into two circular straining-wells 32 feet in diameter. Each straining-well contains a ring of strainers, as at the straining-well at the lake, from the outside of which the water flows into the middle; whence it is withdrawn into the fourth, or supply well, by a pipe 36 inches in

diameter. Each straining-well has a scour-pipe delivering into the cleansing-well. Any strainer which it is desired to wash is lifted from the straining-well and lowered into the cleansing-well, in which there is an open floor 9 feet below the surface. All the wells are connected for scouring purposes to the waste-pipe from the reservoir, and are covered with cast-iron plates.

The works comprised in the Thirlmere undertaking were let in nine contracts, and the ironwork in eighteen contracts, with separate contracts for painting. Portland cement concrete was used throughout the works, the quantity amounting to more than 100,000 tons.

COST OF THE WORKS.

The character of the country through which the aqueduct passes is so varied and so differently affected by local circumstances that it would be impossible to state an average price per lineal yard for the work. The aqueduct begins at the lake at an elevation of 527 feet above Ordnance Datum, and for a considerable portion of its length is much above the general level of the country, the cost of construction being thereby materially increased. In the case of tunnels, the contract price paid for driving ranged from £7 to £10 15s. per lineal yard; and for the concrete lining, where 15-inch side-walls and arch and 9-inch invert have been used, from £3 10s. to £4 18s. per lineal yard. In cut-and-cover, the price paid for the construction of the aqueduct in concrete for the same section of work as in the tunnels, ranged from £5 5s. to £8 10s. per lineal yard.

The contract prices for the pipe-laying were as follows:—

		Per Lineal Yard.		
		£	s.	d.
48-inch pipes		6	15	0
40	„	{from 4 to 5	0	0
36	„		10	0
			3	15 0

These prices are average prices for the various thicknesses of pipes and the different kinds of joints used. They include the cost of the pipe, the laying and jointing and incidental expenses connected with the trench, valves and discharge-pipes; but they do not include the cost of valves, bridges, wells and similar special works.

The total cost of the works up to the date of the opening was about £2,800,000. This sum includes parliamentary expenses (which were exceptionally heavy, in consequence of the deter-

mined opposition to the scheme and expenditure of every kind. The four lines of pipes yet to be laid, together with diversion of drainage at Thirlmere, will cost about £1,600,000, bringing the cost of the complete undertaking to about £4,400,000.

Up to the time when the Act of Parliament was obtained Mr. J. F. L. Bateman, F.R.S., Past-President Inst. C.E., was the Engineer-in-Chief to the Corporation of Manchester. The preparation of the Thirlmere scheme for Parliament was entrusted by him to the Author, who had been in his office from the year 1843, and who having acted for many years as his representative in the North of England, subsequently became his partner. In the year 1885 the Author was appointed Engineer-in-Chief by the Corporation to design and carry out the works now described.

The Paper is accompanied by twenty-five drawings and cartoons, from which Plates 1, 2 and 3, and the *Figs.* in the text have been prepared.

APPENDIX.

SIPHONS.

No.	Name.	Length.	No.	Name.	Length.
		Yards.			Yards.
1	Scandale	280		Brought forward .	32,519
2	Stock Gill	558	17	Street Brook . . .	720
3	Holbeck	312	18	Holmewood	208
4	Troutbeck	904	19	Grizedale	323
5	Kent	887	20	Calder	1,078
6	Sidehouse	570	21	Brock	984
7	Mint	5,752	22	Ribble	16,600
8	Singleton	584	23	Whaves Brook . . .	879
9	Beehive	5,218	24	Black Brook	224
10	Sillfield	380	25	Heapey	1,120
11	Warth	261	26	Yarrow	506
12	Lupton	2,067	27	Shaws	222
13	Keer	7,857	28	Douglas	767
14	Lune	4,762	29	Pearl	720
15	Conder	218	30	Middle Brook . . .	22,189
16	Wyre	1,909		Total length . . .	79,059
	Carried forward .	32,519		or 44 miles 1,619 yards.	

PLATE. 1.

Figs: 4.

LONGITUDINAL SECTION

THEOS. KELL & SON, LITH. 40 KING ST. COVENT GARDEN

STRAINING WELL AND HOUSE AT LAKE.

Scale for Fig. 6 and 7.
Feet 5 10 15 20 25 30 35 40 45 50 55 60 Feet.
Scale for Fig. 9, 10 and 11.
Feet 5 10 15 20 25 Feet.

SECTION THROUGH NORTHERN WELLS SHEWING AUTOMATIC VALVES IN ELEVATION AND CLOSED.

SECTION THROUGH NORTHERN WELLS SHEWING AUTOMATIC VALVE OPENED.

SECTIONAL PLAN OF NORTHERN WELLS SHEWING AUTOMATIC VALVE.

LONGITUDINAL SECTION OF DAM.
Scale 80 Feet to 1 Inch.

MANUAL STOP VALVE IN HOUSES ON 40 INCH PIPE LINE. SHEWING STEEL ANCHOR RODS.

Scale for Fig. 14.
Feet 5 10 15 20 25 30 35 40 45 50 55 60 Feet.

CROSS SECTION OF DAM.

Scale for Fig. 13.
Feet 5 10 15 20 25 30 35 40 45 50 55 60 Feet.

Fig 15.

Fig 16.

Fig 17.

Fig 18.

Fig 21.

Fig 27.

Fig 28.

Fig 29.

Fig 30.

Fig 19.

Fig 20.

Fig 22.

Fig 23.

Scale for Figs 17, 19, 20, 27, 28, 29, and 30.
Inches 12 10 8 6 4 2 0 1 2 3 4 5 10 15 Feet.

Scale for Figs 18 and 31.
Inches 12 10 8 6 4 2 0 1 2 3 4 5 10 15 Feet.