THE
INSTITUTION
OF
CIVIL ENGINEERS.

SESSION 1920-1921.—PART II.

SECT. I.—MINUTES OF PROCEEDINGS.

22 February, 1921.

JOHN ALEXANDER BRODIE, President,
in the Chair.

The PRESIDENT said that since the last meeting The Institution had sustained the loss of an old Past-President, Mr. John Clarke Hawkshaw, whose death removed from the Roll a very distinguished name in Civil Engineering. Although, owing to ill health, Mr. Hawkshaw had been unable in recent years to take an active part in The Institution's affairs, many members would remember with pleasure his kindly and sympathetic personality. The Council had passed the following resolution, in which no doubt the members would concur, and which would be conveyed to Mr. Hawkshaw's relatives:—

“That the Council record the deep regret with which they have learned of the death of Mr. John Clarke Hawkshaw, a Past-President of The Institution, and that their sympathy and condolence be expressed to the members of his family.”

(Paper No. 4302.)

“Port Improvements at Newcastle, New South Wales.”

By PERCY ALLAN, M. Inst. C.E.

NEWCASTLE lies at the mouth of the Hunter River, about 72 miles north of Port Jackson. It is the principal coal port of Australia, and in 1913 no less than 5,236,621 tons of coal were shipped from it in 1,874 vessels having an aggregate register of 3,619,603 tons.

In addition to the Newcastle coalfield, extensive developments have been made within recent years in the Maitland fields, situate at a distance of from 22 to 27 miles by rail from Port Hunter, Newcastle.

The Greta seams are receiving special attention, and are now being extensively worked between Maitland and Cessnock, a stretch of country covering a length of about 15 miles, and stated by the New South Wales Government geologist to be the most important coal-mining district in Australasia. The seams vary in thickness from 14 to 32 feet, a typical section of the Aberdare seam being given in the Table on p. 2.

[THE INST. C.E. VOL. CCXII.]

B

VERTICAL SECTION OF ABERDARE COAL SEAM.

	Ft.	In.		Ft.	In.
COAL	1	3	Brought forward	12	0
Fireclay	0	6	COAL	1	0
COAL	4	6	Band	0	2
Band	0	$\frac{3}{4}$	COAL	3	0
COAL	2	0	Band	0	1
Parting	0	$\frac{1}{2}$	COAL	3	3
COAL	3	6	Shale	1	0
Band	0	2	COAL (now being worked)	12	0
Carried forward	12	0	Total	32	6

In the Stanford Merthyr Colliery at Kurri Kurri, near Maitland, a seam of first-class coal having a thickness of 22 feet without a band is found, and in several of the collieries the coal is met so close to the surface that only inclined tunnels are needed in order to reach the face. The Greta coal measures near Kurri Kurri and Cessnock are thought by Professor David to contain 1,893,000,000 tons of workable coal within a depth of 4,000 feet over an area of 158 square miles.

The Hunter River has a catchment-area of 8,269 square miles (*Fig. 1*)—somewhat more than the surface area of Wales. The average rainfall is 30 inches per annum, and the river is subject to exceedingly heavy floods rising at West Maitland—about 41 miles by river from Newcastle—to a height of $37\frac{1}{2}$ feet above L.W.S.T.

In time of high flood the water fills the Maitland Valley to a width of about 8 miles, the river having a mid-stream surface velocity of 12 miles per hour. Down-stream the water spreads out into the Hexham Swamp and other low-lying country, which acting as balance reservoirs, allows the water to run off gradually without flooding Newcastle Harbour. The gauge at the Pilot station during the period of maximum flood registers about H.W.S.T., whilst the tide at the entrance is ranging between high and low water. The current at this point has a maximum surface velocity of $7\frac{1}{2}$ knots. At such times a large amount of debris is brought down and is carried as far north as Morna Point, where large quantities of drift-wood, deposited by successive floods, remain embedded in the sand beach, which has come forward materially.

Fig. 2 shows the port, with Morna Point to the north and Redhead to the south, the embayment accounting for the absence off the entrance of the prevailing southward ocean current.

On an ordinary ebb-tide the soiled river water runs straight out (*Fig. 3*), the boundary shown having been determined by actual survey in June, 1916.

Shortly after April, 1908, when the Author took charge of the

Public Works in the Newcastle district, representations were made as to the necessity of increasing the depth of the port entrance, it being pointed out that in the preceding 12 months forty-five vessels had to leave Newcastle but partly loaded on account of the insufficient depth.

At that time, although there was a narrow channel available on the Green Beacon line carrying 22 feet 6 inches at L.W.S.T., this was not recognized by the Navigation Department, the depth of

20 feet advertized being that obtaining in the channel marked by the main-fairway leading towers.

A complete survey was determined upon, and, to enable the effect of dredging and extension of breakwaters to be ascertained from time to time, the entrance was divided into compartments and permanent marks were placed at every 100 feet on either breakwater.

Fig. 4 shows soundings taken in September, 1908, and clearly indicates the necessity for removing the "Regent Murray" wreck, which protruded so far into the channel as to throw the ebb-tide over towards the centre of the fairway, thus assisting in the formation of the spit towards the end of the north breakwater.

Fig. 2.

NEWCASTLE BIGHT.

Fig. 4.

enabled to get full sand loads in shorter time, whilst drawing sand away from, instead of towards, the fairway line. This dredging resulted in the spit being so far removed, early in 1909, as to warrant the Navigation Department in advertizing an additional 2 feet 6 inches depth of water at the entrance.

With the removal of the sand on the fairway line an examination of the bottom was made by divers, and upon boulder formation instead of supposed solid rock being reported, clam dredgers were set to work. Up to October, 1912—when the Author relinquished the position of Chief Engineer for Public Works at Newcastle to take up that of Assistant Director-General in Sydney—38,700 tons of boulders and rock had been removed from the entrance, resulting in the advertised depth of the port being further increased to 23 feet 6 inches at L.W.S.T.

This additional 3 feet 6 inches has enabled in the succeeding 6 years, all vessels, with seventeen exceptions, to leave the port fully loaded, whilst the removal of a small remaining patch of solid rock to give a depth of 25 feet at L.W.S.T. will, it is anticipated, entirely meet the requirements of the port for some time to come.

As showing the desirability of using a sweep to determine minimum depths where boulder or pinnacle formation obtains, the Author records that although soundings had been taken week in and week out for many years by very experienced officers of the Public Works and Navigation Departments, with agreement as to a minimum of 20 feet at L.W.S.T., yet in March, 1909, the diver, in making a special survey of the bottom, discovered a large firmly-embedded boulder showing but 18 feet at L.W.S.T. This boulder, lying about 50 feet to the south of the fairway line on section "21," had fortunately, so far as is known, not been struck, the deep-draught vessels generally keeping to the north of the fairway line.

Expansion of Trade and Port Improvements.—During the 12 years ended December, 1908, the number of vessels entered inwards had increased from 1,185 to 1,900 per annum, whilst the registered tonnage had risen from 1,478,746 tons to 3,429,552 tons. There was also an increase of 145 per cent in the quantity of coal exported.

This large expansion in trade, with anticipated further increase in the near future, rendered port improvements imperative, and it was decided that the following was the order of urgency :—

- (1) Extending breakwaters and increasing depth of entrance to port.
- (2) Providing extra wharfage and mooring accommodation.
- (3) Providing additional coal-shipping appliances.

In the State of New South Wales all works estimated to cost over £20,000 are referred by Parliament to a Standing Committee

on Public Works—consisting of four members of the (elected) Legislative Assembly, and three members of the (nominated) Legislative Council—for inquiry and report. If the report be favourable an Authorizing Bill is submitted and has to be passed by both Houses of Parliament before work can proceed.

Fig. 5.

The question of the expediency of extending the northern break-water by 1,170 feet at a cost of £102,500, having been referred by Parliament to the Standing Committee, an inquiry was opened in March, 1909.

At that time the southern breakwater had an overlap of 1,170 feet, the northern breakwater having been carried out a distance of 3,330 feet (*Fig. 5*), or within 420 feet of the finished point recom-

mended by Mr. C. W. Darley, M. Inst. C.E., formerly Engineer-in-Chief for Public Works in New South Wales.

The Author, in giving evidence before the Committee, pointed out that the relative positions of the ends of the breakwaters as then existing were ideal, and that an extension of only 420 feet of the northern breakwater was required to minimize the inflow of sand during the flood tide from the "Oyster Bank." This sand formed a spit at the end of the breakwater, and necessitated constant dredging—573,000 tons having been removed by the trailing dredger "Jupiter," during the year ended 30th June, 1909. It was also considered that the simultaneous extension of the southern breakwater for a corresponding distance was desirable in order to provide shelter from south and south-east seas. If the northern wall were lengthened without a corresponding extension on the southern one, vessels entering the port would be subject to greater risk, as the seas which spent themselves on the Stockton Beach, would be caught and deflected into the harbour. This, it was pointed out, would so increase the range at the entrance as to necessitate a greater depth to allow for scend, and would also make mooring at the nearby wharves a matter of great difficulty.

In effect the Author advised that, unless the Committee was prepared to recommend the simultaneous extension of the two breakwaters by, say, 420 feet, nothing should be done. At the same time he pointed out that the cost of dredging under the conditions then prevailing was over £6,000 per annum, and that with the extension of the northern breakwater the quantity of sand coming round the end would be so reduced as to effect an estimated saving of £3,000 per annum, which, capitalized at $3\frac{1}{2}$ per cent., represented £85,000, and thus the expenditure of such a sum on the extension of the two breakwaters would be a sound commercial undertaking, resulting in an improved entrance without increasing the charge for the port.

The Committee eventually reported in favour of the simultaneous extension of the two breakwaters by 420 feet, at a cost of £90,000, but as the Parliamentary reference only related to the extension of the northern breakwater, this alone could be dealt with in the Authorizing Act, and thus the extension of the northern wall only by 420 feet, at a cost of £34,750, was provided for.

Construction of the Northern Breakwater Extension.—Work was begun on the 28th February, 1910, the general cross section of the breakwater being as shown in *Fig. 6*.

It is built of rough sandstone blocks tipped to natural slopes which in practice are somewhat flatter than shown. The stone was quarried at Waratah, railed thence $5\frac{1}{2}$ miles to a fixed 30-ton crane

on the western side of the harbour, and transferred to 250-ton deck punts. The punts were towed half a mile across the harbour and brought under a 30-ton gantry built over the water, where the stone was lifted on to tip-trucks (Figs. 7, Plate 1), which were run out $1\frac{3}{4}$ mile (Fig. 3) to the tip-head.

In the quarry were two 10-ton and one 30-ton steam cranes, whilst steam rock-drills were installed, as well as a weighbridge over which the trucks were passed, each stone being lettered and numbered. The number of stones and total weight on each truck was recorded at each point of transfer until finally booked over the tip-head. A telephone message at the start of work each morning gave the length of wall extended with the number and weight of stones tipped for the previous day, and thus the Author had early intimation of any drop in the output. This, in conjunc-

tion with the information from the quarry as to the number and weight of stones and the particulars from the 30-ton crane, admitted of steps being taken to trace at once the cause of any delay which had affected the previous day's work.

At the end of each week a return was submitted from each place, showing in diagram form the output for each day, with the total for the week, and a summary from start of work to date.

At first the stones were sent in from the quarry without slings: this meant both risk and delay at each point of transfer. Subsequently the large and small stones respectively were sent in with chain and wire rope slings, which were not removed until the stones were placed on the tipping-trucks at the gantry.

Two 28-ton locomotives were employed, one for taking the rake of trucks from the gantry to the breakwater, and the other at the tip-head. Two dummy trucks were used between the locomotive

and the tip-truck as a safeguard against a run of bank, to which a thin section of wall rapidly pushed forward in a strong tideway is always liable. With the booking of the number and weight of stones going over the tip-head there was—when work got behind—an inclination to make up the day's record by the quicker work of side-tipping and "fattening" the wall beyond the limits of cross section. To check this, three sets of iron profiles were fixed on the completed portion of the breakwater with iron lugs at certain levels, so that the foremen could, with a set of boning-rods, quickly check the cross section as work progressed. The daily recording of the length of wall tipped had a moderating effect on excess dimensions.

This endeavour to get length without increased cross section was carried on with success, with but one exception, when, after a

heavy gale, a run of bank occurred which took with it into the sea the tip-truck, the two dummies and the locomotive. The men, fortunately, managed to get clear. The locomotive and two of the trucks were fished up with a steam lighter, taken into port, repaired, and again put into commission.

Owing to uncertainty as to further extensions, every breakwater on the coast of New South Wales has been left with a raw end, which has resulted in much washing down and costly repairs from time to time. At Newcastle, as the north breakwater was not carried beyond the authorized length of 420 feet, it was finished off with a large round head of dimensions shown on Fig. 8.

Fig. 9 shows the longitudinal section of the wall and the progress of the work.

The wall contains 27,315 stones weighing 108,907 tons, the stones

The expenditure on dredging, previous to the extension of breakwater, was £6,089 per annum, so that in $6\frac{1}{2}$ years there has been a saving of £36,690.

Despite the removal of Scots Point and the provision of two additional small wave-traps on the north (*Fig. 3*) together with the removal of a large portion of Stoney Point on the south, strong representations were made by shipping companies, that the then extension of the northern breakwater by some 235 feet had seriously increased the range in the harbour, and made the entrance to the port more dangerous. These representations resulted in a reference to the Standing Committee, concerning the expediency of extending the southern breakwater. Eighteen witnesses gave evidence, and were unanimous as to the increased range. The committee eventually came to the same conclusion

as the previous committee and, as regards the southern breakwater, recommended an extension of 460 feet, at a cost of £54,000. Parliament duly passed the necessary Authorizing Act.

Construction of Southern Breakwater Extension.—The cross section adopted is shown above, having 6 feet more freeboard than in the northern wall.

Unlike the northern breakwater, stones to be end-tipped can be railed direct from the quarry, and put overboard without transshipment. In the case, however, of stones to be side-tipped, or when several stones are sent from the quarry on a platform truck, a transfer to the smaller tipping-trucks is made at the gantry (*Fig. 3*).

Figs. 7 and 10, Plate 1, show the 30-ton end-tip and platform trucks, specially designed under the Author's direction to supplement the existing truck plant. These trucks cost respectively £239 and

£242 each, delivered on rails at Newcastle. A second 30-ton crane was also installed in the quarry.

Work was begun in January, 1913, but the money provided was insufficient to admit of it being pushed forward with the rapidity so essential to the economical construction of breakwaters, with the result that the stone was flattened down nearly as fast as it was tipped, and after an expenditure of some £10,000 without much gain in length, the work was stopped and has not yet been resumed.

The Author is of opinion that until the southern breakwater is extended, vessels entering the port in heavy weather will be subject to the grave risk of being left on the end of the northern breakwater. A 12,000-ton steamer, making the port in light trim, was thrown by a heavy sea almost across the entrance and so close to the north breakwater as to make it appear she had actually stopped on the wall.

Until the extension is carried out, the Author considers the range which now extends far up the harbour to the Wickham shore, and beyond the McMyler Hoist (*Fig. 3*), will continue to cause trouble.

New Coal Loading Wharf.—In the year 1910 there existed, apart from 1,000 feet of privately owned wharfage, 5,500 feet of Government coal wharfage along the dyke, and 2,000 feet on the eastern side of the basin. Although this had accommodated at one time as many as sixteen vessels, it was considered insufficient for the growing requirements of the port, and after inquiry by the Standing Committee, it was decided to construct a longshore wharf on the western side of the basin (*Fig. 3*.)

In view of the cheapness and reasonably long life of the existing timber wharves it was decided to use this material, the piles being of turpentine and the superstructure of ironbark, a timber of great strength and durability.

The wharf (*Figs. 11, Plate 1*), 1,725 feet long by 41 feet 5 inches in width, provides three berths for the larger type of steamers trading to Australia. It is designed to carry six 15-ton high-speed electric travelling cranes, each weighing 209 tons, with a maximum load of 72 tons on each bogie, the wheel-base of which is 5 feet. Extra strength is provided to withstand the moving loads and the surging of vessels lying alongside.

Although the present depth at the entrance to the port is but 23 feet 6 inches at L.W.S.T., yet along the face line of the wharf 30 feet has been provided, whilst the piles have been driven sufficiently to admit of deepening to 35 feet. The extra depth at the

wharf is to meet the case of vessels, when loading, being "dipped" beyond the normal draft line when fully loaded ready for sea.

Figs. 11, Plate 1, show the cross section of wharf, in which the turpentine piles are pitched 5-foot centres longitudinally. A minimum diameter under bark at toe was specified.

The maximum static load on a pile is 42 tons, 6 tons being due to pile and superstructure, and the remaining 36 tons to crane.

The maximum set of a pile was $2\frac{1}{4}$ inches for three blows from a $42\frac{1}{2}$ -cwt. monkey falling 10 feet, which gives by Wellington's formula, which assumes a factor of safety of six :—

$$\begin{aligned}\text{Ultimate resistance} &= 6 \times \frac{2 \text{ } wh}{s + 1} \text{ tons.} \\ &= 6 \times \frac{2 \times 2 \cdot 125 \times 10}{1 \cdot 75} \text{ tons.} \\ &= 145 \cdot 6 \text{ tons.}\end{aligned}$$

Thus there is a factor of $\frac{145 \cdot 6}{42} = 3 \cdot 46$ against further settlement.

The piles were driven with the bark on, and were kept in the water until used, to prevent the shedding which occurs if they are left in the dry for any considerable time. Some consider the bark to act as a protection against teredo; others hold the opinion that it is not the bark which is teredo-resisting, but a thin vein of resin between the bark and the sapwood, which, if the bark be removed, will come away with it. The Author took special care in this case to have the bark kept intact, but he would point out how impracticable it is to avoid portions being rubbed off before piles are finally in place. He considers that the timber itself is teredo-resisting for long periods, and $16\frac{1}{2}$ years ago, when building the large protecting platforms for the Pyrmont and Glebe Island electric swing spans in Port Jackson, Sydney, had all the turpentine piles stripped before driving. These piles are still in good condition.

The pile machine used (*Figs. 12*) was specially designed under the Author's direction.

With this machine the pile is placed between the leaders, the head fitting into a cast-steel cap (*Figs. 13*) working on channel iron runners, a soft wood block being used on top of the cap to cushion the blow.

The monkey, weighing $42\frac{1}{2}$ cwt., is operated by a steam-driven friction winch which permits of a quick succession of blows, so necessary for economical driving.

Seven piles driven through an average of 26 feet of stiff clay constituted an average day's work.

The longitudinal capsills are dapped over pile heads as well as morticed (Figs. 14, Plate 1). The transverse round girders, flatted on the top to receive 3-inch longitudinal planking, are placed at 2 feet 6 inches centres, and checked over the capsills, whilst the 120 lbs. per yard running-rails for the cranes are spiked direct to

Figs. 12.

these girders. As the inner width of wharf sustains no considerable load, alternate girders only extend to the back row of capsills.

To minimize the trouble due to the crane rails getting out of alignment, and to distribute the surge from large vessels over a considerable length of wharf, a heavy system of horizontal diagonal

bracing is provided between the superstructure and high-water

Figs. 13.

mark (Figs. 11, Plate 1). The diagonal members are checked over
 [THE INST. C.E. VOL. CCXII.] C

the intermediate capsill, and at their ends butt against both capsill and pile, so as to avoid the whole stress being taken up by the tenon on the pile. The stresses in the diagonal braces are transferred to the back pile by a heavy strut, thence to the filling behind the wharf. This system of bracing gives great lateral stiffness, there being an absence of vibration in the structure and but little "talk" when the cranes are moving at high speeds. The iron fastenings throughout the structure are so arranged as to admit of all nuts being easily got at and tightened up as the timber shrinks.

Land-ties formed of 80-lb. rails anchored back to driven piles are provided at every 10 feet to take the outward pressure from the filling behind wharf. These piles are connected with longitudinal round logs running the whole length of wharf.

The filling behind the wharf is held up by a rubble mound and reinforced-concrete plates (Fig. 15, Plate 1).

In the construction of the rubble mound (Figs. 11, Plate 1), the toe "A" was first deposited. When this toe had been completed, the portion "B" of the mound was tipped. The concrete plates were next placed in position and the rubble mound completed with a hand-packed wall. With this method of construction the outward thrust on the structure is practically reduced to that due to the filling held up by the concrete plates, which in turn is transferred to the land-ties.

The reinforced-concrete plates (Fig. 15, Plate 1) holding up the filling behind the wharf upon which the "feeder sidings" are laid, are designed for a load due to heavy main-line locomotives, which may from time to time bring coal trains direct from the mines to the point of shipment. These locomotives weigh 127 tons when in steam. The working stresses adopted for steel in tension and concrete in compression were 15,900 lbs. and 480 lbs. per square inch respectively.

The steel was delivered free from oil, grease, dirt and paint, and all reinforcing rods, stirrups, and hooks were bent cold at the site. The rods were all in one length, arranged to form a grill and tied at each crossing with No. 16 gauge soft black binder wire.

The forms were of planed timber, covered on the inside with No. 24 gauge galvanized iron, and before use were coated with whitewash. All forms were cleaned thoroughly immediately after removal, which took place at the end of a week; the plates were left to harden for 4 weeks, and were, during such period, protected by damp bags and hosed twice a day.

The concrete was composed of 27 cubic feet of granite and $13\frac{1}{2}$ cubic feet of sand to 7 cwt. of cement. The aggregate of clean

broken granite of various sizes was screened to pass freely in either direction through a screen of $\frac{3}{4}$ -inch square mesh, the fine stuff being

Fig. 16.

then screened out with a $\frac{1}{8}$ -inch square mesh. The sand was from $\frac{1}{8}$ -inch square mesh downwards. The materials were mixed in a

screw-type concrete-mixer with slide feeds and separate hoppers for gauging the stone, sand, and cement.

Vertical "pudding" fenders (*Fig. 16*), 6 feet long by 2 feet 6 inches diameter, of similar make to those adopted at Hobart, are hung along the front of the wharf at intervals of 30 feet.

The fenders are made of young ti-tree, of an average diameter of $\frac{7}{8}$ inch. The sticks, about 600 to a fender, are bound up in three

consecutive layers, the two inner layers tied with No. 8 wire, and the outer layer secured in three places with eight turns of $1\frac{1}{2}$ -inch wire rope. The strap passes through the centre of the fender, and is substantially bound with bagging to about 6 inches diameter.

The construction of the wharf, including rubble mound, was carried out by day labour, the timber, reinforced-concrete plates, and iron-work being supplied under contract. It cost complete £47,700. The unit costs and rates of wages are given in Tables III and IV of the Appendix.

Three new mooring-berths have been provided on the Newcastle side of the harbour for vessels discharging ballast or waiting to go to sea.

Each berth consists of three "dolphins," of cross section shown in *Fig. 17*,

and each 20 feet in length. The dolphins are spaced 140 feet apart from centre to centre, and are designed as sections of a longshore cargo wharf. The intermediate spaces between the dolphins will, when trade warrants, be filled in with wharfage of similar cross section.

In carrying out the work the stone retaining-wall was first tipped. The harbour bed was then excavated with a sand-pump dredge to

the cross section shown in *Fig. 17*, the material being pumped ashore behind the retaining wall.

On completion of dredging, the dolphins were constructed, timber land-ties and back-logging being used in place of iron land-ties, reinforced-concrete retaining plates, and rubble mound, which will be added when the dolphins are transformed into cargo wharfage.

With mooring-buoys a swinging circle of 1,200 feet diameter is required for a single vessel, but with longshore dolphins as many as five vessels can be moored abreast.

Coal-Shipping Appliances.—The hopper and box coal-wagons owned by the colliery proprietors are hauled by Government locomotives from the collieries to the compound at North Carrington, where storage is provided for 5,000. Here they are sorted, and shunted an average distance of $1\frac{3}{4}$ mile to the feeder sidings, as required at the different cranes. Each crane is provided with two feeder and two empty sidings on the level, each capable of holding forty wagons. Horse traction is employed for transferring the wagons between sidings and cranes, but electric capstans are now being installed.

The hopper and boxes respectively are lifted from the body of the wagon and lowered to the bottom of the ship's hold, or to the top of the pile of coal, before the door is released and the coal discharged, thus reducing breakage and minimizing coal-dust, a fact which reduces the risk of spontaneous combustion. For long voyages a ship's charter usually stipulates that the hoppers shall be lowered to the bottom of the vessel's hold.

The largest hopper wagons weigh 14 tons when loaded, and carry 9 tons of coal, the unpayable load lifted being only that of the hopper itself, the heaviest weighing 30 cwts. Of the comparatively few box wagons remaining in service, the largest weighs, when loaded, $14\frac{1}{4}$ tons, and carries $8\frac{1}{2}$ tons of coal in the two boxes which, when empty, weigh together 2 tons.

It has been estimated that the colliery proprietors have £750,000 invested in hopper and box wagons, so that any suggestion to introduce more economical high-capacity wagons is not to be thought of at the moment, although the appliances are capable of lifting much heavier wagons than those at present in service.

The coal-shipping appliances are owned by the Government and worked by the Railway Commissioners, who charge a rate per ton per mile for haulage, including shunting, shipping of coal, and return of empty wagons. The trimming of the coal, however, is left with the shipping companies, and the output of the different coal-shipping appliances is usually limited by this, though delay

sometimes arises in bringing the coal from the colliery to the storage sidings, in shunting, in keeping the coal up to the appliance, in berthing the vessels, in moving the vessel when a hatch is run up, and in repairs and renewals, any, or all, of which may largely discount the output of appliances capable in themselves of loading at high speed.

In a Paper read before the American Society of Civil Engineers in December, 1914, on "Coal Piers on the Atlantic Seaboard,"¹ it was stated that in New York the maximum output developed for any one of the previous 8 years was 51 per cent. of the maximum capacity, and in Philadelphia, Baltimore, and Norfolk, only about 30 per cent.

At Newcastle, although the hydraulic travelling cranes have shipped 270 tons of coal in an hour, and the McMyler hoist 500 tons per hour for short periods, yet these figures cannot be taken as an index of the annual output of these appliances under everyday working conditions. This can only be gauged by taking a long period, such as the 4 months subsequent to the coal-employees' strike in March, 1910. At that time there were over 100 vessels in port waiting for coal cargoes, whilst all concerned in the trade were, after 4 months' idleness, anxious to obtain the largest shipment possible.

Under these favourable conditions, in 4 months the McMyler hoist shipped 229,224 tons, the six travelling cranes in the basin 690,386 tons, and the remaining cranes along the Dyke 840,654 tons, making a total of 1,760,264 tons for all the appliances, equivalent to an annual output of 5,280,792 tons, which may be taken as a maximum figure. This averages 117 tons per hour for the hoist and 59 tons per hour for the cranes.

Since 1910 the coal-shipping appliances and adjuncts have been augmented by a travelling crane on the Basin Wharf and by two 15-ton cranes replacing the 9-ton cranes, Nos. 12 and 13 on the Dyke, together with various minor improvements. With these improvements the Railway Commissioners estimate the capacity of the hydraulic and steam coal-shipping units at 7,500,000 tons per annum, under the ordinary working conditions of the port, as against the record shipment of 5,236,621 tons for the year 1913.

To this estimated output of 7,500,000 tons must be added the 2,000,000 estimated output of the recently-installed six electric cranes on the western side of the Basin, making a total of 9,500,000 as the estimated output of the shipping appliances of the port at the present date.

¹ Transactions Am. Soc. of C.E., vol. lxxvii, p. 455.

As the supply of pressure-water from the pumping station was only sufficient for the existing hydraulic appliances, it was a question whether it should be augmented, or whether the six new cranes to be installed on the western side of the Basin should be operated electrically. Eventually the latter course was decided upon, owing to the fact that a new electric station was contemplated for the railway department and, further, that it was unlikely the cranes would be working to their full load for some years, during which period, if hydraulic, they would be uneconomical in work.

Electric Cranes.—The main features of the design of these cranes (Figs. 18 and 19, Plate 2) are the distribution of the loading on the live ring of rollers, the high speeds, and the low unit-stresses adopted to secure stiffness.

The six cranes of 15 tons capacity are each of the fixed-jib type with the revolving platform on a portal carriage carried on four two-wheeled bogies.

The diameter of roller path is 22 feet 6 inches at centre of track, whilst the running-track rails are 22 feet 6 inches centre to centre, a figure which also obtains for the centre to centre distance between the bogies.

The machinery for hoisting, sluing, and travelling is actuated by separate d. c. series-wound electric motors, driven by current taken from a third rail running the whole length of wharf. The current is supplied from the Tramway Power House about 2 miles away through a sub-station at Carrington. The voltage ranges from 550 to 600 volts.

The girders forming the platform for the hoisting machinery and ballast tank, and for transferring the jib and back-strut thrusts to the distributing girders below consist of longitudinal girders A, A', B, and cross girders C, D, E, as shown in *Fig. 20*.

The girders A, A', B carry between them the weight of the hoisting machinery, cabin, etc., making a total of about 30 tons, of which 15 tons is carried by the centre girder, and $7\frac{1}{2}$ tons by each of the side girders. The load on B is transferred to the side girders A, A' by the cross girders C, D. The girders D, E each carry half the balance weight of 50 tons. The downward thrust of the jib is received at the intersection of C with A, A', and is transmitted to the distributing girders immediately beneath.

The load from the hoisting-machinery platform-girders is carried by and transferred from the distributing girders to eight equidistant points on the two segmental girders of the turntable below.

The load carried by the two front distributing girders, when the crane is loaded, is 84 tons (*Fig. 21*).

The turntable consists of two segmental girders and eight radial struts (*Fig. 20*). The half of each segmental girder was treated as a straight girder of 10 feet 8 inches span with an effective depth of 2·8 feet, supported at the ends and loaded with two symmetrical concentrated weights 5 feet 4 inches apart (*Fig. 21*), under which conditions, and with crane loaded, the stresses in tension and compression flanges are 3·10 tons and 2·76 tons per square inch

Fig. 20.

respectively, whilst the stress in web is 1·63 ton per square inch. The live ring contains 48 coned cast-steel rollers, 12 inches mean diameter with $1\frac{1}{2}$ -inch radial rods connected to two $\frac{5}{8}$ -inch steel disk plates revolving round the cast-steel pivot (Figs. 22 and 23, Plate 2).

With crane loaded, the weight of the revolving portion of the structure is 125·62 tons. Of this, 5·05 tons, due to the sluing machinery and a portion of the radial struts, is carried directly by

the pivot, whilst of the remaining 120·57 tons, 87·08 tons are distributed by the front segmental girder and 33·49 tons by the back segmental girder to 28 of the rollers in the live ring below; the centre of gravity of the revolving portion of the crane being 5·4 feet from the centres of the front distributing girders.

With crane unloaded the centre of gravity is 11·64 feet measured from the centre of the front distributing girders, the front and back segmental girders distributing 42·73 tons and 62·84 tons respectively to the rollers.

The maximum load of 87·08 tons is carried by 14 rollers having an effective face of $5\frac{1}{2}$ inches, equivalent to a load of 1·13 tons per

linear inch of face. This load per linear inch compares well with the loads adopted in other works, a list of which is given in the discussion on the Paper by the Author on the Pyrmont Bridge.¹

The rollers run on a coned rolled-steel machined tread, secured with set screws to a cast-iron track, machined top and bottom (Figs. 22, Plate 2). The track, which is in eight segments, was levelled up on wedges and bolted down to the horizontal girders on the top of the portal carriage, the $\frac{3}{8}$ -inch space being then run in with spelter in 15-inch lengths, and caulked.

The portal carriage is made stiff enough to resist injury in the event of one leg being unsupported by reason of settlement. The maximum load on any travelling wheel is 36 tons.

¹ Minutes of Proceedings Inst. C.E., vol. clxx, p. 202.

The factor of stability against overturning of the revolving portion of the crane on a calm day with 15 tons on the hook is 1·77, which is reduced to 1·37, with a wind pressure of 56 lbs. per square foot in the direction to assist the overturning moment.

Circumstances often require cargo to be first removed from the further side of hold, with consequent inward listing of vessel, and it is usual to keep the appliances well back from face of wharf. With appliances for outward loading only—where the mooring and loading of vessels are under the control of the loading authorities—this consideration is not material, the usual practice in this case being to secure maximum reach by keeping the appliance as close to the face of the wharf as practicable. At Newcastle the crane structure is 3 feet 6 inches from the face line of wharf; the following Table shows how this clearance compares with that adopted with a number of loading appliances in other parts of the world:—

Locality.	Appliance.	Distance from Face Line of Wharf to Framework of Appliance.
		Feet. Inches.
Penarth Dock, South Wales . . .	Movable hoist	1 6
Cardiff, Bute Docks	„	2 0
Cardiff, South Dock	Movable crane	2 0
Newport, Alexandria	Fixed hoist	2 3
„ „	Movable hoist	1 6
Glasgow, Rothsay Dock	Fixed hoist	1 6
„ „	Movable crane	2 6
Immingham Dock	Fixed hoist	2 6
Newcastle, New South Wales . .	Movable electric cranes	3 6

The hoisting machinery (*Fig. 23*) is so arranged as to lift the load in the bight of a rope, each end of the rope being attached to a separate drum having its own train of gearing and separate motor. Either set of gearing can be driven independently of the other, so that in the event of a motor or its winch becoming disabled, the crane can still be operated at half speed.

The two drums run on a common shaft, one being keyed directly thereto, and the other running loose but capable of being locked to

the shaft by means of a disk clutch. Under normal conditions the two drums are locked and run together, each lifting $7\frac{1}{2}$ tons, or half the load.

Each drum is 36 inches diameter at the bottom of the turned grooves, and takes 197 feet of rope without overlapping.

Each motor is provided with a solenoid which actuates two brake-straps lined with "Ferodo bonded asbestos." These pass round a

Fig. 23.

DIAGRAM OF HOISTING MACHINERY.

brake-wheel keyed to the armature shaft. The speed of application of the brake is controlled by a dash-pot (Figs. 24, Plate 2).

Each set of machinery is provided with a multiple-disk brake formed of nine $\frac{1}{4}$ -inch machined saw-steel disks and ten $\frac{1}{2}$ -inch machined gun-metal disks.

The unit pressure on the disks is 265 lbs. per square inch, and the maximum rubbing velocity 371 feet per minute, which is considered to be within the limits of good practice. Mr. Bagshaw¹ stated that

¹ Minutes of Proceedings Inst. C.E., vol. lxxxviii, p. 369.

some clutches have been continuously at work for years without appreciable wear, though the velocity of the rubbing surfaces in some instances exceeded 3,000 feet per minute, and the pressure 500 lbs. per square inch.

The sluing is effected by a 25-HP. motor mounted on the machinery platform, operating by means of cut gearing, two pinions working into the circular rack at diametrically opposite points (Figs. 19, Plate 2), the reduction being such that 537·39

Fig. 25.

DIAGRAM OF TRAVERSING MACHINERY.

revolutions of the motor correspond to one complete revolution of the crane. A magnetic brake is provided on the armature shaft.

The travelling is effected by two 25-HP. motors (*Fig. 25* above, and *Figs. 26, Plate 2*) fixed on the respective sole girders. Each armature revolves 4·36 times for 1 foot of crane travel.

The feeders are of 0·4 square inch sectional area, and are carried overhead to a point opposite the centre of the wharf, where the positive cable is branched and brought down into two service boxes,

each containing a 600-ampere quick-break knife switch. A cable is taken out from each of these switches, and, together with the negative, is conveyed under the railway sidings in a bitumen-filled wood trough to the wharf.

The negative cable is connected to the two track rails, whilst the two positive ones are connected separately to the two sections of the copper conductor-rail on either side of a section insulator. The conductor rail, of hard-drawn copper, of T section, with an area of $\frac{1}{2}$ square inch and a contact face 2 inches wide, is supported at every 5 feet by insulators carried on a dressed ironbark bearer, secured to the deck-planks of the wharf, whilst a horizontal cover and vertical barge-boards protect the conductor-rail from injury.

Collector shoes—two for each crane—are of the design shown in Figs. 27, Plate 2.

The two collector shoes are coupled to a 600-ampere single-pole knife switch in a service box on the portal carriage of the crane, at a convenient height for operating from the wharf decking. From this point the two main positive cables are carried to the slip rings (Figs. 28, Plate 2) and thence to the main circuit breaker on the switchboard.

The master controllers, which are floor-mounted, are installed in the front left-hand corner of the cab, in a position affording the operator a clear view of his work.

The switchboard in the cabin is of the ironclad type, consisting of an angle-bar framework on which are mounted the various pieces of apparatus in cast-iron watertight cases.

Sympathetic control is provided for the hoisting and sluing motions, one handle of the combined master controllers operating either sluing or hoisting controller separately, or the two controllers simultaneously, in accordance with the direction in which the handle is moved. By the application of this gear the manual effort required of the operator has been reduced to a minimum.

In the case of the hoisting and traversing motors, series-parallel operation is provided for. The hoisting controller gives nine speeds in either direction, whilst the travelling controller gives eight, and the sluing five.

A separate reverser is provided for the hoisting motors, and is of the drum type. It is mounted on the floor behind the switchboard. The movement of the drum is effected by two solenoids, and a set of contact fingers is fitted for interlocking purposes, making it impossible to operate the motors unless the reverser drum is in the position corresponding with the direction in which the master-controller handle is being moved.

An overwinding switch is provided in the hoisting circuit of the master controller and is operated by a flexible steel wire attached to a lever at the head of the jib.

When the handle of the controller is moved into the "lowering" position after an "overwind," the motors operate in that direction, and the overrunning switch automatically resets itself.

Two lighting circuits are provided on the revolving portion of the crane. In the cabin five points are fitted, each having a 120-volt 30-watt lamp in a cast-iron watertight casing. On the underside of the jib two cast-iron watertight fittings are installed, each having two 120-volt 30-watt lamps wired in series with similar lamps on the sluing platform. In addition, two 240-volt 200-watt and one 120-volt 100-watt lamps in weatherproof lanterns are installed on the portal carriage.

When erected complete on wharf, each crane before being put into service for its 3 months' maintenance period, was subjected to a series of tests with a 15-ton load. The detailed results in connection with No. 5 crane are given in Table V.

As a consequence of the great headway and long reach, the electric cranes have been largely employed for bunkering such vessels as could not get under the other appliances. This, whilst flattering to the facilities afforded by the new installation, does not tend to large outputs, as the usually confined hatchways leading to the bunkers limit the speed of trimming, with consequent slow rates of loading.

With the shipping of cargo coal, however, the bunkering occasions no delay, and vessels which previously took 50 hours to load 4,400 tons at a fixed crane, can now—by grouping the electric cranes—be given despatch in 10 hours.

The six cranes were made by Messrs. Cowans, Sheldon and Company, of Carlisle, the contract price complete, including conductor-rail, being £48,197, ship's slings, Newcastle.

The north breakwater extension was designed by Mr. E. M. de Burgh, M. Inst. C.E., then Chief Engineer for Harbours and Rivers, and was carried out under the supervision of the Author, with Mr. F. Howard as assistant engineer in immediate charge of the work.

The wharf was designed by the Author, and was, with the exception of the contract supply of the reinforced-concrete plates, carried out by day labour under the supervision of Mr. H. A. Blomfield, M. Inst. C.E., then District Engineer at Newcastle, with Mr. F. Howard as assistant engineer on the work.

The cranes are to the Author's design, whilst the plans were

TABLE V.—SUMMARY OF TESTS OF CRANE NO. 5 MADE ON 28TH NOVEMBER, 1916, SHOWING THE SPEED AND POWER REQUIRED, AND COST OF CURRENT FOR HOISTING LOAD OF 15 TONS AND SLUING AND TRAVERSING CRANE WITH LOAD. (CALM DAY, NO WIND.)

No. of Run.	Hoisting with Two Motors.				Sluing.				Traversing.				" Aeroplaning."			
	Time taken to Hoist Load of 15 Tons through 50 Feet.	Maximum Electrical HP. Input.	Power Consumed by Motors and Resistances.	Time taken to Slue Load through and through Three-Eighths of Circle.	Time taken to Slue Load through Full Circle.	Time taken to Slue Load through Circle.	Maximum Electrical HP. Input.	Power Consumed by Motor and Resistances.	Time taken to Traverse Crane with Load along Wharf.	Maximum Electrical HP. Input.	Power Consumed by Motors with Resistances.	Time taken to Hoist Load of 15 Tons through 50 Feet.	Maximum Electrical HP. Input.	Power Consumed by Five Motors and Resistances.	Cost of Current for Each Run at 8d. per Unit.	
1	Seconds, 25½	HP. 153	Watt-Hours, 791	Seconds, 21½	Seconds, 47½	Seconds, 21½	HP. 21	Watt-Hours, 136	Seconds, 42½	HP. 33	Watt-Hours, 287	Seconds, 28½	HP. 226	Watt-Hours, 1,172	0.938	
2	25	163	785	20½	45½	45	29	130	43½	38	297	28½	207	1,180	0.944	
3	25½	163	804	20½	45	45	21	129	43	38	292	33½	216	1,365	1.094	
Totals .	75½	494	2,380	62½	137½	137½	71	395	129	109	876	90½	649	3,717	2.976	
Average of three runs .	25.26	165	793	20.83	45.8	43.3	24	132	43.3	36	292	30.26	216	1,239	0.992	

¹ Equivalent to a speed of 118 feet per minute.

² Equivalent to a speed of 366 feet per minute for three-eighths of a circle and 452 feet for complete revolution.

³ Equivalent to a speed of 139 feet per minute.

⁴ Hoisting, sluing and traversing motors in simultaneous operation. Weight hoisted 50 feet, slued through 195 feet whilst crane travelled along wharf 54 feet. All in a period of 30.26 seconds.

prepared by Mr. H. Leahy, and Mr. O. W. Brain, Chief Electrical Engineer for New South Wales Railways, was consulted in regard to the electric equipment.

With the exception of the layout of the cables and wiring, the details of slip ring, solenoid and magnetic brakes, controllers, resistances and switchboard, which it was left to the contractors to design and supply to the approval of the consulting engineer in London, the whole of the work was manufactured strictly to the details shown on the contract plans or definitely set out in the specification.

Mr. W. Shellshear, M. Inst. C.E., consulting engineer in London to the New South Wales Government, supervised the manufacture of the cranes, whilst the reassembling in situ was carried out by the Government Dockyard authorities at Newcastle.

The Author desires to express his acknowledgments to Mr. J. Davis, M. Inst. C.E., late Director-General of Public Works, New South Wales, during whose term of office the wharf and cranes were constructed, and to thank Mr. T. B. Cooper, Under-Secretary for Public Works, New South Wales, for photographs, lantern-slides, and wall-diagrams accompanying the Paper.

The Paper is illustrated by twenty-nine tracings, from which the Figures in the text and Plates 1 and 2 have been prepared, and is accompanied by an Appendix giving costs and rates of wages.

APPENDIX.

TABLE I.—UNIT COST OF NORTHERN BREAKWATER EXTENSION.

Item.	Rate <i>d.</i>	Unit.
Stripping	3·00	per ton.
Quarrying and loading.	35·00	"
Hauling to 30-ton crane	8·50	"
Unloading trucks and loading punts	5·50	"
Towage	2·20	"
Unloading punts and loading tip-trucks	4·90	"
Haulage from Gantry and Tipping	4·90	"
Repairs to road and plant	6·00	"
Plant and depreciation	4·00	"

TABLE II.—RATE OF WAGES.

	<i>s.</i>	<i>d.</i>	
Foreman (quarryman)	15	0	per day of 8 hours.
" (breakwater)	11	0	" "
" (30-ton crane)	10	0	" "
Blacksmiths	11	0	" "
Strikers	8	0	" "
Locomotive and crane drivers.	10	8	" "
Gantry-winch drivers and shunters	9	0	" "
Quarryman (first-class)	10	0	" "
" (second-class)	9	0	" "
Loaders	8	0 to 9	0 " "
Rock drillers	8	6	" "
Slingers	8	0 to 8	6 " "
Tipmen and platelayers	9	0	" "
Labourers	8	0	" "
Boys	5	0	" "
Man and horse	11	0	" "

TABLE III.—UNIT COST OF WHARF.

Item.	Rate in situ. <i>£ s. d.</i>	Unit.
Piles	3 2	per linear foot.
Capsills, fenders, struts, mooring-posts, chocks and curbs	5 1	per cubic foot.
Round girdlers	4 2	per linear foot.
Walings, including metal sheathing	4 3	" "
Planking, 9 inches by 3 inches	8	" "
Monier plates	4 13 8	each.
Tarring, three coats	2 10	per 100 super feet.
Painting, three coats	7 3	per super yard.
Rubble backing, including wall	2 7	per ton.
Land-ties	6 13 3	per set.
Wrought iron	3 3	per lb.

[THE INST. C.E. VOL. CCXII.]

p

TABLE IV.—RATE OF WAGES.

	£	s.	d.	
Foreman	265	0	0	per annum.
Under-foreman	12	0		per day.
Divers	15	0		per day of 6 hours.
Carpenters	12	0		per day of 8 hours.
Blacksmiths	11	0		" "
Crane and pile-machine drivers .	11	0		" "
Attendants on divers	10	5		" "
Labourers (special)	9	4		" "
Labourers	9	0		" "
Boys	6	0		" "

PORT IMPROVEMENTS AT NEWCASTLE, NEW SOUTH WALES.

PLATE 1.
PORT OF NEWCASTLE.

Fig. 7.

Scale: 3/4 inch = 1 Foot.

END ELEVATION.

END ELEVATION.

30-TON END TIP TRUCK.

Fig. 10.

SECTION B.B. - SIDE ELEVATION

Scale: 3/4 inch = 1 Foot.

PLAN

30-TON PLATFORM TRUCK

SECTION C.C.

END ELEVATION.

Fig. 14.

FRONT ELEVATION.

ELEVATION OF PILE.

ELEVATION OF PILE.

ELEVATION OF PILE.

SECTION AT A-B.

SECTION AT C-D.

SECTION AT E-F.

SECTION AT G-H.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

PLAN.

Fig. 11.

CROSS SECTION.

Scale: 1 inch = 16 Feet.

PLAN.

ARRANGEMENT OF NEW WHARF.

Fig. 15.

REINFORCED CONCRETE PLATE.

Scale: 1 inch = 60 Feet.

GENERAL PLAN OF PILES.

P. ALLAN.

PORT IMPROVEMENTS AT NEWCASTLE, NEW SOUTH WALES.

PLATE 2.
PORT OF NEWCASTLE.

Fig. 18.

Scale, 1 Inch = 10 Feet.
Feet 5 10 15 20 Feet.

15-TON ELECTRIC CRANE.

Fig. 19.

ARRANGEMENT OF MACHINERY

Fig. 20.

PLAN

Fig. 21.

SIDE ELEVATION. TRAVERSING MACHINERY.

END ELEVATION.

Scale for Fig. 22, 23, 24, 25 & 27 1/2 Inch = 1 Foot.
Inches 1 2 3 4 Feet.

Fig. 24.

ELEVATION. HOISTING MACHINERY BRAKE.

END VIEW.

Fig. 22.

LIVE RING

Fig. 26.

SECTIONAL ELEVATION AA.

SECTIONAL PLAN.

COMPENSATING BOGIE.

DETAILS OF 15-TON ELECTRIC CRANE.

Fig. 27.

CROSS SECTION BB: LIVE RAIL AND COLLECTOR-SHOE.

SECTION AA: PIVOT

SECTION CC: PIVOT

Fig. 23.

PLAN

Fig. 28.

SLIP RINGS.